

NASA CR-

1320905

Hamilton
Standard

DIVISION OF UNITED AIRCRAFT CORPORATION

U
A®

SVHSER 6226

Reproduced from
best available copy.



FINAL REPORT

for the

VELOCITY CONTROL PROPULSION SUBSYSTEM

of the

RADIO ASTRONOMY EXPLORER SATELLITE

for

GODDARD SPACE FLIGHT CENTER

under

CONTRACT NO. NAS 5-11463

Prepared By:

W. Braught

W. Braught,
Senior Experimental Engineer

E. K. Moore

E. K. Moore,
RAE-B Engineering Manager

R. L. Steinberg

R. L. Steinberg,
RAE-B Program Manager

REPRODUCED BY
NATIONAL TECHNICAL
INFORMATION SERVICE
U.S. DEPARTMENT OF COMMERCE
SPRINGFIELD, VA. 22161

NASA-CR-132905) VELOCITY CONTROL
PROPULSION SUBSYSTEM OF THE RADIO
ASTRONOMY EXPLORER SATELLITE FOR GODDARD
SPACE FLIGHT CENTER Final (Hamilton
Standard Div.) 347 p

N74-15463

CSCL 21H

Unclas
G3/23 27601

324


337


N O T I C E

THIS DOCUMENT HAS BEEN REPRODUCED FROM THE
BEST COPY FURNISHED US BY THE SPONSORING
AGENCY. ALTHOUGH IT IS RECOGNIZED THAT CER-
TAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RE-
LEASED IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.

FINAL REPORT
for the
VELOCITY CONTROL PROPULSION SUBSYSTEM
of the
RADIO ASTRONOMY EXPLORER SATELLITE
for
GODDARD SPACE FLIGHT CENTER
under
CONTRACT NO. NAS 5-11463

Prepared By:


W. Braught,
Senior Experimental Engineer


E. K. Moore,
RAE-B Engineering Manager



R. L. Steinberg,
RAE-B Program Manager

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
1.0	Introduction	1
2.0	Summary	2
3.0	Acceptance Test	5
4.0	Qualification Test	7
5.0	Heater Power Thermal Analysis	26a
6.0	Post Delivery Activity	57

APPENDICES

A	Photographs
B	GSFC Malfunction Reports
C	Test Engineering Vibration Report
D	GSFC Mass Properties Report
E	SVHSER 6184 - RAE-B Gas Manifold Modification Report

LIST OF FIGURES AND TABLES

<u>FIGURE NO.</u>	<u>TITLE</u>	<u>PAGE</u>
1	VCPS Mechanical Schematic	3
2	VCPS Electrical Schematic	4
3	Vibration Test Setup	19
4	Thermal Verification, Sun Angles	23
5	VCPS, Mission Profile Impulse vs. Time, Run 5719	26b
5b	Impulse vs. Time, Runs 5720, 5721, 5722	26c
6	VCPS Extreme Temp. Firing Impulse vs. Time	26d

<u>TABLE NO.</u>		
1	Acceptance Test Summary	6
2	Qualification Tests Tabulation	8
3	Qualification Test Summary	9
4	Accelerometer Location List	20

1.0

INTRODUCTION

The Velocity Control Propulsion Subsystem (VCPS) was designed, manufactured and tested by Hamilton Standard under contract to Goddard Space Flight Center for use on the Radio Astronomical Explorer (RAE-B). The purpose of the VCPS is to provide the propulsion required for trajectory and lunar orbit corrections of the spacecraft. A GFE clamp assembly physically attaches the VCPS to the spacecraft and the unit is ejected after completing the required corrections. The VCPS is physically and functionally separated from the spacecraft except for the electrical and telemetry interfaces.

A GFE transtage provides the superstructure on which the VCPS is assembled. The subsystem consists of two 5 lbf rocket engine assemblies (REAs), 4 propellant tanks, 2 latching valves, 2 fill and drain valves, a system filter, pressure transducer, gas and propellant manifolds and electrical heaters and thermostats. Figures 1 and 2 provide schematics of the fluid and electrical systems respectively. A series of photographs of the VCPS are presented in Appendix A to provide a visual reference of the unit.

The RAE-B VCPS program covered the design, manufacture and qualification of one subsystem. This subsystem was to be manufactured, subjected to qualification tests; and refurbished, if necessary, prior to flight. The VCPS design and test program precluded the need for refurbishing the subsystem and the unit was delivered to GSFC at the conclusion of the program described herein.

2.0

SUMMARY

The VCPS was acceptance tested per Hamilton Standard Plan of Test SVHS 5618 and met all test requirements. The unit was released for qualification testing on 24 March 1972.

Qualification testing was performed in accordance with Hamilton Standard Plan of Test SVHS 5619. Testing was grouped into structural, environmental and firing performance tests. Appropriate base point and monitoring tests were included before and after each significant test sequence. All testing was conducted at Hamilton Standard with the exception of Mass Properties, Acceleration and Thermal Verification; these tests were performed at GSFC, D. T. Brown and General Electric; respectively.

The qualification testing was completed on 18 August 1972. Two hardware discrepancies were encountered and successfully resolved during qualification program. The first involved an REA heater and was detected during the first electrical test when the REA/tank heater circuit gave an incorrect resistance reading. An analysis of the REA heater malfunction was performed, reference GSFC malfunction report #D02908, and as a result, all flight and flight spare heaters were replaced with new equipment manufactured in accordance with more stringent procedures to prevent a recurrence of the malfunction.

The second anomaly occurred during the thermal verification test conducted at General Electric, Valley Forge, Pennsylvania in its solar simulation chamber. The VCPS thermal control subsystem was unable to maintain the propellant tanks and line temperatures to specification requirements. Hamilton Standard subsequently modified the tank thermal analysis by incorporating the test results and changed the tank coating pattern as required to maintain a 45°F min. fuel temperature. The propellant line insulation was redesigned and the heater power changed to provide the required line temperatures. A thermal vacuum test of the VCPS verified the acceptability of these modifications.

Subsequent to the delivery of the VCPS, a need for modification of the gas manifold was established; a copy of the report on that hardware change is included in Appendix E.





FIGURE 2. SUBSYSTEM ELECTRIC SCHEMATIC



- NOTES:
1. HEATERS AND REDUNDANT TEMPERATURE CONTROLS ARE LOCATED ON COMPONENT MOUNTING BRACKET.
 2. TANK HEATERS (4) CONTROLLED BY PARALLEL REDUNDANT THERMOSTATS.
 3. TEMPERATURE SENSORS ARE THERMISTOR TYPE.
 4. LINE HEATERS CONTROLLED BY REDUNDANT THERMOSTATS.

FIGURE 1

3.0

ACCEPTANCE TEST

The VCPS acceptance test was designed to verify the proper assembly of the wiring harness, the operation of the electrical components and the leakage integrity of the manifold and the flow control valves. Testing was performed in accordance with Hamilton Standard Specification SVHS 5618.

After the VCPS was fully assembled and passivated, the acceptance test was started with a visual examination of the unit. The unit met all drawing requirements; some cosmetic defects were noted and repaired. The acceptance test was successfully completed on 3/18/72. Table 1 is a summarization of the Acceptance testing and shows the test sequence and provides a brief description of the test requirements and results.

TABLE I
RAE-B VCPS ACCEPTANCE TEST SUMMARY

Test No.	Test Name	References		Specification Requirement	Test Results																				
		SVHS5619 Para.	AT Sheet Page																						
1	Examination of Product	4.5.1	5	Visual Examination. Inspection of installation dimensions.	Unit passed visual examination. All dimensions within drawing requirements.																				
2	Electrical Check	4.5.2	6 - 27	Verify VCPS electrical interface.	All circuits demonstrated proper continuity and pin usage.																				
				<u>Pressure Transducer</u>																					
				<u>PSIA</u> <u>Req'd Output ($\pm .05$ VDC)</u>	<u>Pressure</u> <u>Output</u>																				
				100 1.61 \pm .05 VDC	100 psia 1.59 VDC																				
				200 3.12 \pm .05 VDC	200 psia 3.13 VDC																				
				260 4.62 \pm .05 VDC	300 psia 4.67 VDC																				
				<u>REA & Latch Valves</u>																					
				Determine baseline values for resistance, opening response and closing response.	<table><tr><td>Actual</td><td>REA #1</td><td>REA #2</td><td>Latch #1</td><td>Latch #2</td></tr><tr><td>Resistance</td><td>41.6 ohms</td><td></td><td>47.5 ohms</td><td></td></tr><tr><td>Opening</td><td>13 ms</td><td>15 ms</td><td>25 ms</td><td>25 ms</td></tr><tr><td>Closing</td><td>38 ms</td><td>28 ms</td><td>26 ms</td><td>24 ms</td></tr></table>	Actual	REA #1	REA #2	Latch #1	Latch #2	Resistance	41.6 ohms		47.5 ohms		Opening	13 ms	15 ms	25 ms	25 ms	Closing	38 ms	28 ms	26 ms	24 ms
Actual	REA #1	REA #2	Latch #1	Latch #2																					
Resistance	41.6 ohms		47.5 ohms																						
Opening	13 ms	15 ms	25 ms	25 ms																					
Closing	38 ms	28 ms	26 ms	24 ms																					
				<u>Thermistor</u>	<u>Actual:</u> Amb. temp. 70.8°F																				
				Calibrate within 10% at ambient temperature.	Tank #1 70.1°F Line 70°F																				
					Tank #2 70.1°F Bracket 70.1°F																				
				<u>Heaters</u>	<u>Actual:</u>																				
				Circuit resistance within 5% of:	21.0 ohms																				
				REA & Tank 20.5 ohms	74.4 ohms																				
				REA 72.0 ohms	34.8 ohms																				
				Bracket 36.0 ohms	144.2 ohms																				
				Line 144.0 ohms																					
3	Proof Pressure	4.5.4	29 - 31	Proof 450 psia min. Collapse 5 mm Hg max.	The VCPS fluid manifold and tanks suffered no permanent deformation after being subjected to 452 psia proof and 1.8 mm Hg collapse pressure.																				
4	Internal Leakage	4.5.5	32 - 34	8 scc/hr GN ₂ for sum of latching valves or thrust control valves.	Latching Valves 1.25 scc/hr Thrust Control Valves 0.4 scc/hr																				
5	External Leakage	4.5.6	35 - 43	Total VCPS external leakage shall not exceed 1 x 10 ⁻⁴ scc/sec He.	Actual: 4.7 x 10 ⁻⁶ scc/sec He																				
6	Dry Weight	4.5.3	28	VCPS dry weight less GFE shall not exceed 20.5 lbs	Actual: 19.257 lbs																				
7	Post Test Inspection	4.5.7	44	Review tests for compliance to specification requirements. Visual Examination	Unit met all acceptance test requirements. Unit passed visual examination.																				

4.0

QUALIFICATION TEST

Qualification testing was conducted in accordance with Hamilton Standard specification SVHS5619 and appropriate operation sheets. An additional thermal vacuum test was run after the completion of the original sequence due to the out of specification conditions which occurred in the thermal verification test sequence 19. A sequential tabulation of the qualification test program is given in Table II. Each of the test sequences is summarized in Table III and a more detailed description of each test is provided in the following paragraphs.

TABLE IIRAE-B VCPS QUALIFICATION TEST SEQUENCE

<u>Test</u>	<u>Completion Date</u>
1. System Firing Base Point	3/25/72
2. Decontamination and Contamination Check	3/25/72
3. Internal Leakage	3/26/72
External Leakage	3/27/72
4. Electrical Check	3/28/72
5. Mass Properties	4/6/72
6. Contamination Check	4/6/72
7. Acceleration	4/11/72
8. Contamination Check	4/12/72
9. Internal Leakage	4/13/72
External Leakage	4/13/72
10. Electrical Check	4/14/72
11. Vibration	4/19/72
12. Contamination Check	4/19/72
13. Proof Pressure	4/20/72
14. Internal Leakage	4/20/72
15. Alignment	4/20/72
16. Electrical	4/21/72
17. External Leakage	4/22/72
18. Visual Examination	4/22/72
19. Thermal Verification	5/9/72
20. Contamination Check	5/11/72
21. Thermal Vacuum	5/19/72
22. Contamination Check	6/1/72
23. Internal Leakage	6/1/72
External Leakage	6/2/72
24. Electrical Check	6/3/72
25. Spin Firing	6/7/72
26. System Firing Base Point	6/9/72
27. Wet Weight	6/9/72
28. Mission Profile	6/10/72
29. Extreme Temperature and Vacuum Firing	6/19/72
30. Decontamination and Contamination Check	6/20/72
31. Insulation Verification	7/28/72
32. Contamination Check	7/28/72
33. Alignment	8/14/72
34. Internal Leakage	8/15/72
External Leakage	8/16/72
35. Electrical Check	8/18/72
36. Post Test Inspection	8/23/72

TABLE III
RAE-B VCPS QUALIFICATION TEST SUMMARY

Test Sequence	Test Name	References		Specification Requirement	Test Results
		Spec. Para.	AT Sheet Pages		
1	System Firing Basepoint	4.3.1	1 - 6	Provide baseline performance impulse vs. time for VCPS.	See Sequence 26.
2	Decontamination and Contamination Check	4.3.2	7 - 11	Cleanliness Verification	
				Particle Size No. Allowable	Actual No.
				0 - 5 microns Unlimited	-
				5 - 10 1200	25
				10 - 25 200	4
				25 - 50 50	2
				50 - 100 5	1
				100 0	0
				50 metallic 0	0
3	Leakage	4.3.3	12 - 25	Allowable internal leakage	
				Sum of Latch Valves 8 scc/hr GN ₂	Sum of Latch Valves 0.4 scc/Hr GN ₂
				Sum of Thrust Control Valves 8 scc/hr GN ₂	Sum of REAs 0.2 scc/hr GN ₂
				External Leakage 1 x 10 ⁻⁴ scc/sec He	Total VCPS External Leakage 2.6 x 10 ⁻⁶ scc/sec He
4	Electrical	4.3.4	26 - 50	Pressure Transducer	
				PSIA Output Req'd	Pressure Output
				100 1.61 ± .05 VDC	101 psia 1.62 VDC
				200 3.12 ± .05 VDC	200 psia 3.12 VDC
				260 4.01 ± .05 VDC	258 psia 3.97 VDC
				Thermistor	Actual
				Calibrate to within 10% of amb. temp.	Tank #1 73.5°F Line 74°F
				Ambient 73.5°F	Tank #2 71°F Bracket 74°F
				Heaters	
				Circuit resistance shall be:	Actual Resistance
				REA and Tank 20.5 ± 1 ohm	20.8 ohms
				REA 72 ± 3.6 ohms	73.8 ohms
				Bracket 36 ± 1.8 ohms	35.0 ohms
				Line 144 ± 7.2 ohms	143.0 ohms
				Valves Current and voltage traces of the latching and thrust control valves actuation shall exhibit standard characteristics.	Visual examination of valve traces showed no discrepancies.

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results																				
		Spec. Para.	AT Sheet Pages																						
5	Mass Properties	4.3.5	50 - 53	Center of Mass: ± 0.015 of 2 axis Static Balance: 20 oz-in max Dynamic Balance: 250 oz-in ² max	Testing performed at GSFC. Reference NASA GSFC Mass Properties Report Appendix E of this report.																				
6	Contamination	4.3.2	54	Same as Sequence 2	<u>Actual No. Particles</u> 10 8 7 1 0 0																				
7	Acceleration	4.3.6	55 - 57	Simultaneous application of 3 g's in the +X and 14.7 g's in the +Z 3 g's in the +Y and 14.7 g's in the +Z	Test performed at D. T. Brown Resultant load 15 g's applied at 137.5 in at 62 RPM for 1 minute.																				
8	Contamination	4.3.2	58 - 60	Same as Sequence 2.	<u>Actual No. Particles</u> 2.5 1 1 0 0 0																				
9	Leakage	4.3.3	61 - 73	Same as Sequence 3.	Sum of Latching Valves: 1.4 scc/hr GN ₂ Sum of REAs : 0.6 scc/hr GN ₂ Total VCPS External : .15 x 10 ⁻⁴ scc/sec He																				
10	Electrical	4.3.4	74 - 91	Same as Sequence 4.	<u>Pressure Transducer</u> <table><tr><th>Pressure</th><th>Output</th></tr><tr><td>105 psia</td><td>1.67 VDC</td></tr><tr><td>202 psia</td><td>3.16 VDC</td></tr><tr><td>260 psia</td><td>3.99 VDC</td></tr></table> <u>Thermistor:</u> <table><tr><td>Room Ambient</td><td>76°F</td><td></td><td></td></tr><tr><td>Tank #1</td><td>75°F</td><td>Line</td><td>75.5°F</td></tr><tr><td>Tank #2</td><td>74°F</td><td>Bracket</td><td>75°F</td></tr></table>	Pressure	Output	105 psia	1.67 VDC	202 psia	3.16 VDC	260 psia	3.99 VDC	Room Ambient	76°F			Tank #1	75°F	Line	75.5°F	Tank #2	74°F	Bracket	75°F
Pressure	Output																								
105 psia	1.67 VDC																								
202 psia	3.16 VDC																								
260 psia	3.99 VDC																								
Room Ambient	76°F																								
Tank #1	75°F	Line	75.5°F																						
Tank #2	74°F	Bracket	75°F																						

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results
		Spec. Para.	AT Sheet Pages		
					Heater Circuit Resistance
					REA and Tank: 20.8 ohms
					REA 73.8 ohms
					Bracket 34.75 ohms
					Line 143.0 ohms
					Visual examination of valve traces showed no discrepancies.
					See Appendix C for control accelerometer plots. No structural damage noted.
					Actual No. Particles
					2
					1
					0
					0
					0
					0
11	Vibration	4.3.7	92 - 98	Vibration - See Appendix C for levels required and visual examination for structural damage.	
12	Contamination	4.3.2	99 - 100	Same as Sequence 2.	
13	Proof	4.3.8	102	450 ± 10 psia.	450 psia, visually examination showed no structural damage.
14	Internal Leakage	4.3.3	103 - 104	Same as Sequence 3	Sum of latching valves: 1 sec/hr GN ₂ max. Sum of REAs: Nil
15	Engine Alignment	4.3.10	117 - 118	Each REA must be within ±30 minutes of the spacecraft center of gravity location.	Actual misalignment: REA #1 9.0 minutes max. REA #2 7.5 minutes max.
16	Electrical	4.3.4	119 - 136	Same as Sequence 4.	Pressure Transducer
					Pressure Output
					101 psia 1.62 VDC
					205 psia 3.20 VDC
					258.4 psia 3.98 VDC
					Thermistors: Ambient temperature 75°F
					Tank 1 75°F Bracket 74.5°F
					Tank 2 74.5°F Line 75°F

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results
		Spec. Para.	AT Sheet Pages		
17	External Leakage			Total VCPS external leakage shall be 1×10^{-4} scc/sec He max.	Heater Resistances REA and Tank 20.9 ohms REA 73.8 ohms Bracket 34.9 ohms Line 142.8 ohms Visual examination of valve traces showed no discrepancies. Actual .13 x 10 ⁻⁴ scc/sec He
18	Visual Examination			Visually examine the VCPS for physical damage.	No discrepancies were noted.
19	Thermal Verification	4.3.11	137 - 145	No recorded VCPS temperature shall exceed the range of 45°F to 140°F. The VCPS tank electrical heaters shall not be required to actuate in the 2 hour cold case.	Propellant line temperatures were below 45°F in the 60° cruise condition. Propellant line and tank temperatures were below 45°F in both 60° and 0° case. The tank heater actuated in the 0° cold case. Corrective action for this malfunction is detailed in the engineering report of Appendix D.
20	Contamination Check	4.3.2		Same as Sequence 2.	<u>Actual No. Particles</u> 16 12 2 1 0 0
21	Thermal Vacuum	4.3.12	146 - 155	Temperature cycle the VCPS between 45°F and 140°F; 6 times; a) Thrust Control Valves - power drain shall not exceed 10 watts b) Latch Valve shall actuate as indicated by position switch c) A thermostates shall actuate between 55 ± 5°F and deactuate between 65 ± 5°F.	a) Thrust Control Valve's average power: REA #1 @ 45°F 1.38 watts @ 140°F 1.17 watts REA #2 @ 45°F 1.38 watts @ 140°F 1.17 watts b) No discrepancies.

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results
		Spec. Para.	AT Sheet Pages		

c) NOTE: (*) The recorded line and tank thermostat temperatures during the first three cycles were in error due to the time lag in the VCPS temperature duration.

	CYCLE											
	1		2		3		4		5		6	
	On	Off	On	Off	On	Off	On	Off	On	Off	On	Off
Line	(*)	(*)	(*)	(*)	52.5	(*)	53	67.5	51.5	69.0	51.5	68
Bracket	56	(*)	55.5	65.5	56.0	64.5	55.0	62.0	57.0	65.0	55.0	61.5
Tank	52.0	(*)	52.5	(*)	52.5	(*)	52.7	66.5	52.5	67	52.0	67

°F

22

Contamination Check

4.3.2

156 - 158

Same as Sequence 2.

Actual No. Particles

2.0

1.0

0

0

0

0

23

Leakage

4.3.3

159 - 171

Same as Sequence

Latching Valve - Nil

Thrust Control - Nil

Total VCPS External Leakage - .336 x 10⁻⁴

24

Electrical Check

4.3.4

172 - 189

Same as Sequence 4.

Pressure Transducer

Pressure	Output
100.3 psia	1.60 VDC
201.4 psia	3.14 VDC
261.7 psia	4.02 VDC

Thermistor - Room Ambient Temp. 74.0°F

Tank #1 73.5°F Bracket 73.5°F

Tank #2 73°F Line 73.0°F

Heater Circuit Resistance

REA and Tank	20.8 ohms
REA	73.8 ohms
Bracket	34.7 ohms
Line	142.1 ohms

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results															
		Spec. Para.	AT Sheet Pages																	
25	Spin Firing	4.3.16	214-219	VCPS shall not exhibit any abnormal firing characteristics such as P_c discontinuities or roughness when compared to previous non-spinning firings.	Visual examination of valve traces showed no discrepancies. Engine P_c and tank pressure traces were visually examined and found to be smooth and continuous.															
26	System Firing Basepoint	4.3.1	190 - 195	Impulse delivered shall be within 5% of the Sequence 1 basepoint data.	Impulse delivered by VCPS in 2 minutes. <table><tr><td></td><td colspan="2">Initial Tank Pressure</td></tr><tr><td></td><td>100 psia</td><td>260 psia</td></tr><tr><td>Sequence #1</td><td>667 lb-sec</td><td>1413 lb-sec</td></tr><tr><td>Sequence #26</td><td>653 lb-sec</td><td>1369 lb-sec</td></tr><tr><td>Tolerance</td><td>- 2.1 %</td><td>- 3.1%</td></tr></table>		Initial Tank Pressure			100 psia	260 psia	Sequence #1	667 lb-sec	1413 lb-sec	Sequence #26	653 lb-sec	1369 lb-sec	Tolerance	- 2.1 %	- 3.1%
	Initial Tank Pressure																			
	100 psia	260 psia																		
Sequence #1	667 lb-sec	1413 lb-sec																		
Sequence #26	653 lb-sec	1369 lb-sec																		
Tolerance	- 2.1 %	- 3.1%																		
27	Wet Weight	4.3.13	198 - 199	VCPS wet weight shall not exceed 66 lbs. The propellant consumed during the mission profile test shall be determined.	VCPS weight 65.8 lbs. Propellant consumption 42.4 lbs															
28	Mission Profile	4.3.14	200 - 205	The VCPS mission average I_{sp} shall be 220 sec. or greater.	Mission Average I_{sp} 225.6 sec.															
29	Extreme Temperature and Vacuum Firing	4.3.15	206 - 213	Demonstrate thermal vacuum operation of the REAs at 140,000 ft. altitude min. and 45°F and 120°F.	Reference Figure 3 for impulse delivered by VCPS.															
30	Decontamination and Contamination Check	4.3.2	220 - 223	Same as Sequence 2.	<u>Actual No. Particles</u> 10 2 1 0 0 0															
31	Propellant Line Insulation Verification Test		Appendix #1 1 - 10	The VCPS propellant lines temperature shall not be less than 45°F.	Actual minimum line temperature was 51°F. See Appendix B for full thermal report.															
32	Contamination Check		Appendix #1 11 - 13	Same as Sequence 2.	<u>Actual No. Particles</u> 8 3 1 1 0 0															

TABLE III (continued)

Test Sequence	Test Name	References		Specification Requirement	Test Results
		Spec. Para.	AT Sheet Pages		
33	Alignment	4.3.10	Appendix #1 45 - 47	Same as Sequence 15.	<u>Actual Misalignment</u> REA #1 12 minutes REA #2 12 minutes
34	Leakage	4.3.3	Appendix #1 14 - 26	Same as Sequence	<u>Internal Leakage</u> Latching Valves 0.4 scc/hr GN ₂ Thrust Control Valve 0.7 scc/hr GN ₂ <u>External Leakage</u> Total VCPS .5 x 10 ⁻⁶ scc/hr GN ₂ <u>Pressure Transducer Output</u> 101.7 psia 1.61 VDC 203.0 psia 3.17 VDC 255.7 psia 3.94 VDC <u>Thermistor:</u> Ambient Temperature 72°F Tank #1 71.5°F Line 71.4°F Tank #2 71.5°F Bracket 71°F <u>Heater Circuit Resistance</u> REA and Tank 20.7 ohms REA 71.6 ohms Bracket 34.6 ohms Line 36.0 ohms
35	Electrical Check	4.3.4	Appendix #1 27 - 44	Same as Sequence 4.	<u>Heater Circuit Resistance</u> REA and Tank 20.7 ohms REA 71.6 ohms Bracket 34.6 ohms Line 35.7 ohms Visual examination of valve traces showed no discrepancies.
36	Post Test Inspection		Appendix #1 47	Review data for compliance to specification requirements. Visual inspection of VCPS.	All data conformed to specification requirements or was reviewed and found acceptable via MRA.

4.1 System Firing Base Point, Sequence 1 and 28

The purpose of this test was to provide a firing base point for comparison of VCPS performance before and after the structural and environmental qualification tests.

Both sequences were performed at identical conditions in the H-5 vacuum test cell. The VCPS was loaded with 12 lbs of hydrazine and pressurized to 260 psia. The unit was fired for 2 minutes with an initial pressure of 260 psia and then refired for 2 minutes after venting the VCPS pressure to 100 psia. No test anomalies were encountered during either test sequence.

The following table shows the impulse delivered by the VCPS and each REA for each firing.

	IMPULSE DELIVERED (lbs-sec)			
	Sequence 1		Sequence 26	
	@ 100 psia	@ 260 psia	@ 100 psia	@ 260 psia
VCPS Total	667	1413	653	1369
REA #1	333	707	330	689
REA #2	334	706	323	680

Impulse delivered by the system was repeated within 3.2% of the initial base point after being subjected to test sequences 2 thru 25. This repeatability is considered excellent and demonstrates that the VCPS performance capabilities were unaffected by the structural and environmental testing.

4.2 Decontamination and Contamination Check, Sequence 2, 8, 12, 20, 22, 30 and 32

The VCPS was decontaminated after each test sequence in which the unit was loaded with hydrazine or referee fluid. Contamination checks were made after each decontamination check and after major structural and environmental tests and prior to delivery.

The purpose of the decontamination procedure was to assure the complete removal of hydrazine propellant from the system. This was done by gravity draining the residual hydrazine and flushing the VCPS with high purity water. The water is then drained and removed by an IPA flush and vacuum drying of the system.

A contamination check was made during the IPA flushing sequence by withdrawing an effluent sample and performing a particulate count on the sample. Each contamination check made during the qualification test was found to be well within the allowable CE-5 cleanliness level.

4.2 continued

CE-5 Cleanliness Level	
Particle Size	Allowable Count
0 - 5 Micron	Unlimited
5 - 10	1200
10 - 25	200
25 - 50	50
50 - 100	5
100	0
50 Metallic	0

4.3 Leakage, Sequence 3, 9, 14, 17, 23

Internal leakage test was performed after various environmental tests to verify the leakage rate between the propellant source and the thrust chamber. Four internal leakage measurements were made during each sequence:

1. the sum of the latching valve leakage at 300 psia
2. the sum of the latching valves leakage at 15 psia
3. the REA #1 thrust control valve at 300 psia
4. the REA #2 thrust control valve at 300 psia

The internal leakage rates were measured by pressurizing the VCPS, as required, with the appropriate valves closed and collecting the gaseous nitrogen leakage via the water displacement method. The external leakage was measured by the mass spectrometer method with the unit pressurized to 300 psia GH_e .

The following table shows the allowable leakage rates compared to the maximum values exhibited during any of the test sequences.

Leakage Check	Allowable	Maximum Recorded	Sequence
Internal			
Sum of Latching Valves	8 scc/hr GN_2	1.4 scc	9
Sum of REAs	8 scc/hr GN_2	.6 scc	9
External Leakage	1×10^{-4} scc/ sec GH_e	3.4×10^{-5}	23

4.4 Electrical Check, Sequence 4, 10, 16, 24, 35

The purpose of the electrical check was to verify the nominal operation of each electrical component by a functional check at appropriate intervals throughout the qualification test. Included in the test are functional checks of the REA valves, latching valves, pressure transducer, electrical heaters, thermostats and thermistors.

4.4 continued

All the electrical components checked out properly throughout the qualification test except the REA heater. During the first electrical check, sequence 4, an REA heater was found to be defective. The defective unit was removed and replaced with a spare heater. The malfunction analysis of the REA heaters is covered in RDR #02908 in Appendix B. As a result of the investigation, heater manufacturing procedures were revised and all REA heaters were replaced with new units made to the revised procedures.

Test Sequence 35 shows a line heater circuit resistance of 36 ohms compared to 144 in previous tests, this change reflects the line heater wiring change from series to parallel heating elements, required as a result of the propellant line temperature problem.

4.5 Mass PropertiesSequence 5

This test was performed at the NASA facility at GSFC. The NASA provided test report is included in Appendix D. During the mass properties testing it was found that the balance of the VCPS could be varied by the propellant filling rate. The proper fill rate will subsequently be determined by GSFC after delivery of the unit.

4.6 AccelerationSequence 7

Acceleration testing was conducted at D. T. Brown test facility. The VCPS contained high purity water and was pressurized to 250 psia. The mounting fixture was designed to provide 3 g's in the X or Y axis while applying 14.7 g's simultaneously in the Z axis. Two one minute runs were made accelerating the unit in the +X, +Z and +Y +Z axes. The acceleration parameters were: arm length - 137.5 inches, 62 RPM with a resultant load of 15 g's. All test parameters were within specification.

4.7 VibrationSequence 11

The purpose of the vibration test was to demonstrate that the VCPS and GFE transtage could structurally withstand and successfully operate after being subjected to the required vibration levels. Since the transtage hub was to be tested at the same time as the VCPS, GSFC provided Hamilton Standard with a mass simulating spacecraft and the personnel to assemble the system. The VCPS/spacecraft assembly was tested as a unit during the sinusoidal vibration below 200 Hz and for the entire random input. The spacecraft was removed for sinusoidal inputs above 200 Hz. The VCPS was fully loaded with high purity water and pressurized to 245 psia. Figure 3 shows the test set up and Table 4 provides a listing of the recording accelerometers used. The test engineering report including the control input level plots are provided in Appendix C.




FIGURE 3 VIBRATION TEST SETUP

TABLE 4

Install accelerometers on the test item and record outputs during testing as shown in the following Table:

ACCELEROMETER LOCATIONS	VIBRATION INPUT AXIS		
	X	Y	Z
Fixture (Control)	X, Y, Z	X, Y, Z	X, Y, Z
Spacecraft C.G.	X, Y	X, Y	X, Y
REA Mount	X	Y	Z
Tank Mount	X	Y	Z
Latch Valve Mount			Z
Junction Box Mount			Z
Pressure Transducer			Z
Hub (Inside, near arm bracket mount)	X	Y	Z

4.8 Proof PressureSequence 13

The purpose of the proof pressure test was to verify the integrity of the VCPS tanks and manifold after the structural qualification test sequences. The VCPS was pressurized to 450 psia for 2 minutes. No visual damage was incurred by the VCPS and the unit passed all subsequent leakage tests.

4.9 Engine AlignmentSequence 15 & 33

The REAs were initially aligned during the VCPS assembly. The alignment tests were performed after the structural qualification test and after the firing test prior to shipment. Auto collimators and optical targets were used to initially align and subsequently check the alignment of the REAs to within $\pm 30'$ from the theoretical VCPS C.G. The test values in all cases fell between 7.5 and 13 minutes from the C.G.

4.10 Visual ExaminationSequence 18

At the completion of the structural qualification tests the VCPS was thoroughly examined by Hamilton Inspection personnel for any damage which may have been incurred. No damage was noted.

4.11 Thermal VerificationSequence 19

The purpose of the thermal verification test was to demonstrate the capability of the VCPS thermal design to maintain the propellant system within the temperature range of 45°F to 140°F, under solar simulated flight conditions. Testing was performed at General Electric's test facility in Valley Forge, Pennsylvania.

The VCPS was instrumented throughout with non-flight thermocouples, loaded with 6 lbs of referee fluid and pressurized to 100 psia. Figure 4 shows the spacecraft/VCPS sun angle relationship. The spacecraft/VCPS was mounted on a spin fixture which was capable of rotating the system to achieve sun angles of 120° (warm cruise) and 60° (cold cruise), while spinning at 55 rpm. The zero degree sun angle was achieved by turning of the solar simulator. Although the problems associated with the use of thermocouples readout through a slip ring greatly reduced the amount of useful data achieved, it was evident that the VCPS was unable to maintain propellant lines and tanks pressure above freezing during the 60° and 0° sun angle modes. The following table briefly summarizes and compares the test results to the expected temperatures.

4.11 continued

Thermocouple Location	Sun Angle					
	120°		60°		0°	
	Predicted	Actual	Predicted	Actual	Predicted	Actual
Propellant Tank Outlet	82°F	84°F	112°F	72°F	67°F	10°F
Bracket Area	ALL READINGS WERE WITHIN SPECIFICATION					
Propellant Line	N/A	101°F	55°F	42°F	48°F	10°F

This problem and the subsequent corrective action, as agreed to by Hamilton Standard and GSFC is documented in GSFC Malfunction Report D02909 ref. Appendix B. A detailed description of the subsequent thermal analysis and verification test is provided in the engineering report included as Appendix

4.12 Thermal VacuumSequence 21

The purpose of this thermal vacuum test was to demonstrate the operation of the VCPS components, except engine firing, at the specified temperature extremes of 45°F and 140°F. This testing was performed in Hamilton Standard's 10 ft. x 10 ft. thermal vacuum chamber. The VCPS was loaded with referee fluid and pressurized to 250 psia for the testing.

The unit was subjected to six (6) temperature cycles between the temperature limits with a 2 hour hold period at each extreme. The operation of each component was checked during each temperature hold and the electrical heaters and thermostats operation was tested on each cycle. All components demonstrated satisfactory operation.

Two test conditioning problems were encountered during the thermal vacuum testing. First, some difficulty in maintaining the required 1×10^{-5} torr pressure was encountered. The chamber pressure slipped up to 1.5×10^{-5} torr for two short periods during the 48 hour test. The second problem involved the rate of temperature cycling. The rate of temperature change during the first three cycles was too fast causing a temperature distribution within the VCPS because of what appeared to be improper thermostat activation. During the last three temperature cycles the cycling rate was sufficiently slow to allow the proper recording of the thermostat temperatures.




FIGURE 4 THERMAL VERIFICATION

4.13 Spin FiringSequence 25

The spin firing test was conducted to demonstrate that the engine thrust and tank blowdown characteristics are not affected by the vehicle spin rate.

Testing was performed in the H-4 firing cell at ambient temperature and pressure. The VCPS was loaded with 45 lbs of hydrazine and pressurized to 245 psia. REA chamber pressure and the VCPS pressure transducer were recorded via a slip ring during each firing. Two firings of 2 minutes each were conducted at 55 ± 5 rpm and 12 ± 2 rpm for a total of 8 minutes firing time. Visual examination and comparison of the REA P_c and tank pressure traces show the traces to be smooth, continuous and typical of non-spin firing traces.

4.14 Wet WeightSequence 27

The purpose of the wet weight test was to determine the mass of propellant consumed during the mission profile test. In order to achieve the accuracy required to provide significant data, a balance scale was built into the firing cell for this test.

Dry Weight	45.65 lbs
Propellant Loaded	+45.20
Gas	+ .42
Total Wet Weight	91.27

Less Weight of VCPS after Mission Profile	48.87
--	-------

Propellant Consumed	42.4 lbs.
---------------------	-----------

4.15 Mission ProfileSequence 28

The purpose of the mission profile test was to subject the VCPS to a typical mission firing sequence and verify the average specific impulse for that mission. The system was initially loaded with 45.2 lbs of N_2H_4 pressurized to 245.5 psia. Testing was conducted in the H-5 firing cell with the initial chamber pressure at 100,000 ft. minimum. Four (4) firings were performed with firing time based on the engine performance required to provide impulse of 7253, 770, 1377 and 151 lbs/second respectively. No test anomalies were encountered. The test result for the mission profile are summarized in the following table.

4.15 continued

		<u>Initial Conditions</u>		<u>Firing Time</u>	<u>Delivered Impulse</u>	<u>Mission I_{sp}</u>
		<u>Tank Press.</u>	<u>REA Temp.</u>			
1	245.5 psia	68°F	870 sec	7356 lb-sec		
2	123 psia	87°F	114 sec	726 lb-sec		
3	112 psia	93°F	222 sec	1312 lb-sec		
4	100 psia	94°F	24 sec	125 lb-sec		
TOTAL			1230 sec	9519 lb-sec	225.6 secs	

4.16 Extreme Temperature and Vacuum Firing Sequence 29

The purpose of this testing was to provide firing data for temperature performance prediction and to demonstrate the operation of the REA in thermal vacuum environment. Testing was conducted in the H-5 firing cell with the chamber initially evacuated to 140,000 feet min. prior to each firing. The VCPS was installed loaded with 45 lbs. of propellant and pressurized to 245 psia.

Temperature conditioning was accomplished by preconditioning the VCPS and propellant prior to loading the system and evacuating the cell. The VCPS was then loaded with conditioned fuel and the VCPS temperature was maintained by conditioning the transtage mounting block while slowly evacuating the test cell. For the 40° firing, the firing cell had to be backfilled with dry GN₂ to prevent condensed moisture from freezing on the unit as the cell was evacuated.

The following table outlines the test conditions and results of the thermal vacuum firing test.

<u>Run</u>	<u>VCPS Bracket Temp.</u>	<u>Propellant/ REA</u>		<u>Initial Tank Pressure</u>	<u>Run Time (mins.)</u>	<u>Impulse Delivered (lb-sec)</u>		
		<u>Tank Temp.</u>	<u>Temp.</u>			<u>REA #1</u>	<u>REA #2</u>	<u>Total</u>
1	145°F	136°F	125°F	242 psia	2	624	630	1254
2	70°F	80°F	60°F	180 psia	2	502	507	1009
3	42°F	45°F	50°F	143 psia	2	428	431	859
4	143°F	125°F	136°F	163 psia	2	471	476	947
5	60°F	75°F	60°F	132 psia	2	402	405	807
6	40°F	45°F	40°F	112 psia	2	365	364	729

4.17

Propellant Line Insulation Verification TestSequence 31

The testing was performed in addition to the original qualification test program as a result of the malfunction of the VCPS during the thermal verification test, sequence 19. The purpose of the testing was to verify the selection of the proper insulation thermal characteristics, demonstrate the acceptability of the insulation assembly procedure, and to provide the data necessary for the thermal model to generate the space/flight temperatures.

The test was conducted at Hamilton Standard in the 10 ft. x 10 ft. thermal vacuum chamber. Test conditions were set to simulate worst case conditions by having zero sun input and controlling the line interfaces, hub and tanks, to minimum expected temperatures. Three thermal modes were tested. First, the VCPS was allowed to reach steady state with 12 VDC input to the line heaters. Secondly, heater input was then increased to 13.8 VDC until steady state was achieved. Finally, the heaters were deactivated and the VCPS temperatures were monitored during a 2 hour cool down.

The test results showed that the propellant line temperatures were maintained above freezing even in this worst case test and that the minimum expected line temperature under flight conditions is 51°F. A detailed description of this testing and the results of the subsequent thermal analysis is provided in the engineering report in Appendix E of this report.

4.18

Post Test InspectionSequence 36

This test sequence included a final visual examination of the VCPS by HS Inspection and DCASO personnel and a complete review of the test data for compliance to the specified requirements.

The visual examination revealed no major discrepancies although some minor cosmetic flaws were noted. These were repaired by simple cleaning or in the case of the gold surfaces, the flaws were covered by vapor deposited gold kapton tape. The test data was reviewed and found to be compliant with the specified requirements.

5.0

TANK THERMAL ANALYSIS AND PROPELLANT LINE THERMAL ANALYSIS

RAE-B VCFS
MISSION PROFILE
RUN 5719
PI- 237.8 - 125.5

S/N 00001 REA
+ S/N 00002 REA




FIGURE 5

26b

RAE-B VCPS
MISSION PROFILES/N 00001 REA
S/N 00002 REA

ACCUMULATED IMPULSE LBF-SEC.

RUN 5722
 $P_1 = 97.0 - 95.9$

TIME - SECONDS

ACCUMULATED IMPULSE LBF-SEC.

RUN 5721
 $P_1 = 108.6 - 100.0$

TIME - SECONDS


ACCUMULATED IMPULSE LBF-SEC.

RUN 7520
 $P_1 = 118.6 - 112.8$

TIME - SECONDS

FIGURE 5b

S/N 00001 REA
S/N 00002 REA



RUN 5723 $T_F=120^\circ\text{F}$
 $P_I=237.1 - 197.3$

RUN 5724 $T_F=70^\circ\text{F}$
 $P_I=173.6 - 153.1$

RUN 5726 $T_F=120^\circ\text{F}$
 $P_I=158.7 - 143.2$

RUN 5725 $T_F=45^\circ\text{F}$
 $P_I=138.8 - 125.5$

RUN 5727 $T_F=70^\circ\text{F}$
 $P_I=126.5 - 116.9$

RUN 5731 $T_F=45^\circ\text{F}$
 $P_I=109.1 - 103.0$

FIGURE 6

Hamilton
Standard

DIVISION OF UNITED AIRCRAFT CORPORATION

U
A®

RAE-B VCPS

TANK THERMAL ANALYSIS REPORT

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

1.0 INTRODUCTION

The intent of this report is to document the thermal analysis effort relative to the VCPS tanks conducted since the thermal verification test of May 1972. The pretest analysis and test results are included along with subsequent analyses which served to correlate the thermal model and provide definition of the tank coating changes required for operation within specification limits.

2.0 SUMMARY

The solar thermal verification test showed a large discrepancy between the pre-test tank temperature predictions and the actual test results. A large predicted thermal gradient across the tank failed to materialize and the cooldown rate during the 2 hour transient dark period exceeded the predicted rate by a large amount resulting in temperatures far below the specification minimum. Subsequent analyses have produced a thermal model which duplicates the test results. The original discrepancy has been found to be a combination of oversimplified thermal modeling together with factors unique to the test setup and solar lamps. The mission thermal analysis has been redone using the improved thermal model with the result that 56% of the Black Paint stripe on each tank must be taped over with vapor deposited gold to insure satisfactory operation in space.

3.0 DISCUSSION

3.1 Requirements

The VCPS specification S-723-P-19 requires that tank propellant temperatures remain between 45°F and 140°F with the additional requirement that the tank heaters not turn on; implying that the minimum tank temperature allowable is 50°F at the tank outlet. These criteria must be met over environmental variations characterized by two extremes, hereafter referred to as "HOT CASE" and "COLD CASE" defined as follows:

HOT CASE

Steady state cruise at 120° spin axis inclination (to the solar vector) followed by a 2 hour transient period at 180° inclination with minimum fuel load in the tanks of 6 lbs N₂H₄, total.

COLD CASE

Steady state cruise at 60° spin axis inclination followed by a 2 hour transient period at 0° inclination with minimum fuel load of 6 lbs N₂H₄, total.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.2 Thermal Design Philosophy

The principal thermal design objective was to establish a passive thermal control coating system which would minimize the difference in propellant temperature between the hot case and cold case cruise conditions so that the subsequent full sun and dark transients would not yield out of spec temperature excursions. This required that the effective solar absorptance of the tank be higher for the cold case than for the hot case to compensate for the difference in solar projected area (incident solar flux) between the 120° and 60° spin axis angles. Another requirement was to provide a low overall emittance to minimize the 0° spin axis cooldown rate while maintaining the proper α/ϵ ratio for cruise operation. The coating arrangement selected was vapor deposited gold (Vacuum Metallizing Corp.) with a stripe of black paint applied to the upper (+Z) half of the tank to reduce the overall α/ϵ to the desired value (2.2) and simultaneously, by its placement, effect a higher absorptance in the 60° spin axis attitude. Figure 1 shows the tank stripe orientation relative to the solar vector at the 60° and 120° spin angle. Vapor deposited aluminum would have been a more desirable coating, since it has a lower α and the same ϵ as gold, but the tank vendor was worried about a possible corrosion problem involving aluminum and the tank material. Figure 2 shows the solar projected area of the black paint stripe in its original configuration as a function of spin angle inclination. The effective solar absorptance of the tank with this stripe configuration is .412 at the 60° spin angle and .30 at the 120° spin angle.

3.3 Thermal Design Analysis

The original thermal design analysis was accomplished using the VCPS system thermal model which contains three tank nodes with associated vehicle and VCPS connectors. This model, the tank portion of which is shown in Figure 3, was input to HSD's general heat transfer computer program and run on the IBM 370-165 computer. A significant portion of the information required to set up this model was supplied by NASA/GSFC early in the design. These data, Table I, included the solar projected area of the tanks, arms and transtage, the view factors from the tanks to space and nearby vehicle surfaces, the temperatures of nearby spacecraft surfaces, and the emittance and solar absorptance of all system external surfaces. Since the tank model has three nodes, it was necessary to apportion the NASA/GSFC supplied solar inputs among the three equal surface area nodes. This was accomplished approximately through the use of the GSFC shadow photographs and hand calculations. The resulting solar projected area of the three nodes for the hot and cold cases is shown below:

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.3 (continued)

Solar Projected Area (4 tanks) \sim FT²

	<u>HOT CASE</u>		<u>COLD CASE</u>	
Spin Angle	120°	180°	60°	0°
Solar Ap				
Nodes 1	.5076	.633	.547	0
2	.4804	.916	.394	0
3	.384	.633	.122	0

It should be noted that the solar input is much more evenly distributed in the 120° spin axis case than in the 60° spin axis case where the input to the outboard tank node is considerably higher than that to the other nodes. The increase shadowing corresponding to the 60° spin angle intercepts the inboard areas of the tanks.

3.3.1 Pre-Test Predictions

Hot case and cold case temperature predictions were made after the VCPS had received the vapor deposited gold coating and the black tank stripe had been applied. The analysis was performed for space operation (as opposed to test chamber conditions which were not known at the time) with the intent of adjusting the model after the test to interpret the data at test conditions. Since the test was planned not to include the hot transient condition (180° spin angle) the predictions presented below omit this case. The predictions are based on a solar constant of 442 BTU/FT²-HR, 0°R radiation sink and the spec minimum fuel load of 6 lbs N₂H₄ (1.5 lbs per tank).

PREDICTED TEMPERATURES °F

<u>Case</u>	<u>NODE</u>		
	<u>Tank 1</u>	<u>Tank 2</u>	<u>Tank 3</u>
Cold Case Cruise (60° spin angle)	112	88	32
Cold Case Transient (0° spin angle, 2 hrs)	67	-4	-13
Hot Case Cruise (120° spin angle)	82	85	79

The most significant aspect of these predictions was the large temperature gradient between the outlet (fuel) end of the tank (NODE "Tank 1") and the opposite end ("Tank 3") for cold case cruise. The clarity afforded by hindsight would suggest that transport mechanisms within the tank tending to relax this favorable temperature gradient should have been added to the model at that point since the absence of the gradient at the design $\alpha/2$ would have resulted in excessively low fuel temperatures during the transient (0° spin angle) condition. This was not apparent at the time.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.4 Test Conditions and Operation

The test was conducted in the General Electric Co. solar simulator at Valley Forge Space Center, King of Prussia, Pa. The VCPS was mounted to a GSFC supplied engineering model of the spacecraft, which was in turn coupled at the +Z end of the spin fixture. The combination was rotated at 55 RPM during the test and was processed from the initial 120° spin axis inclination (hot case), after equilibrium was achieved, to the 60° attitude (cold case cruise). At the latter spin angle, the spacecraft Z axis was at 30° to the horizontal (the solar source is reflected from ceiling mounted mirrors). The tanks contained 5.3 lbs of isopropyl alcohol which was added to the 1 lb of water already in the system (but probably not in the tanks). The intent was that the tanks contain 6.3 lbs of alcohol-water mixture to match the thermal mass of 6 lbs of N_2H_4 . After equilibrium was achieved at the 60° spin angle, the solar source was turned off for 2 hours to simulate the transient condition at 0° spin angle.

A considerable amount of difficulty was encountered with thermocouple data errors generated by the slip ring temperature gradients. Fortunately the flight thermistors were utilized in the test providing very accurate tank temperatures at the outlet end and the means for correcting thermocouple data taken elsewhere on the tanks. The tank meridian thermocouple (NODE "Tank 2") failed early in the test.

The test conditions are summarized below:

Solar Power Intensity	118 w/ft ²
Cold Wall Temperature	-270°F
Tank Pressure	100 psia
Tank Load	5.3 lbm isopropyl alcohol
Vacuum	9.5×10^{-7} torr
Spacecraft RPM	55

3.5 Test Results

Table II shows the tank temperatures from the various test conditions compared to the pre-test predictions. The data shows two significant discrepancies when compared to the predictions:

The predicted temperature gradient was absent (the test data temperatures are roughly equal to the average value of the three predicted temperatures).

The cooldown rate during the 2 hour dark transient was far greater than predicted.

3.5 (continued)

Both discrepancies suggest the presence of some type of transport phenomena "shorting" the three tank nodes together, evening out the gradient and increasing the heat loss during the transient by distributing the stored heat of the liquid in NODE "Tank 1" over the entire tank surface.

3.6 Data Analysis

The post test analysis had the following major objectives:

- 1) Review the thermal model for errors and oversimplifications which may have contributed to inaccurate predictions.
- 2) Investigate the test conditions for phenomena peculiar to the test which will not occur in space.
- 3) Produce a thermal model which duplicates test results.
- 4) Replace "test conditions" with "space conditions" in the model and determine coating changes required for satisfactory thermal performance in space.

Prior to going into the details of converting the model to the G.E. test conditions, some runs were made using the space model with the following changes:

Run "A" - All 3 tank nodes were thermally shorted together and the cold case rerun. The results (Table III) agree far better with respect to cooldown rate and cold case temperature distribution than do the original predictions. A re-evaluation of the model calculations failed to reveal any errors other than failure to predict the thermal coupling of the 3 tank nodes. At this point, the various possible internal transport mechanisms were listed, evaluated, and added to the model if found significant:

1. Internal Radiation Among Tank Nodes and Fuel Puddle - A radiation network linking the 3 tank nodes (the fuel puddle is lumped into "Tank 1") and the tank attachment (NODE "ARM") was set up using 0.8 for the internal emittance. The effect of tank radiation alone is significant (Run B, Table III) and the conclusion must be drawn that it should have been in the model from the beginning. The coupling afforded by radiation alone, however, is insufficient to explain the test results.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.6 (continued)

2. Natural Convection in the Pressurant Gas - The presence of a large radial acceleration in the tanks (2.3 g's at 55 RPM) and a high pressurant density (100 psi N₂) produces significant convective coefficients between the warm end (NODE Tank 1) and colder tank areas. Convective coefficients were estimated treating the internal geometry as parallel plates with appropriate separation. Both horizontal and vertical plates were calculated reasoning that the tank geometry would produce convective coefficients somewhere between those two extremes. Figure 4 is a plot of the convective coefficients vs. tank delta T. These were added to the model along with the radiation (Run "C" Table III). These results show further improvement in the direction of matching the test data, but not to the degree of Run "A" (complete thermal short of the 3 tank nodes).
3. Mass Transfer (Diffusion) - Diffusion rates for alcohol through nitrogen were calculated to assess the relative importance of evaporation from the fuel puddle and subsequent condensation on colder areas of the tank. Calculated mass transfer rates were found to be negligible.
4. Fuel Sloshing - During the test, the orientation of the tanks was such that a ± 1.0 g oscillatory side loading was applied to the fuel puddle along with the constant 2.3 g radial acceleration normal to the puddle surface. An estimate of slosh natural frequency gave a value of 2 hz. Since the system was spinning at 1 hz, and the unamplified response of the puddle to the ± 1.0 g would include an angle of 30° about the normal axis of the puddle, the proximity of the slosh excitation to the natural frequency suggests that the fuel was probably sloshing all over the inside of the tank during the test. This has been modeled as run "A" Table III.

The conclusion drawn from these preliminary runs, "A" through "C", is that sloshing probably isothermalized the tank during the test although as run "C" suggests, the data would have been nearly the same without sloshing due to radiation and convection. Sloshing will be precluded in space, but the radiation and convection effects were left in the model for later predictions of space temperatures with new tank coating distributions in the cold case. If the natural convection values utilized in the model are excessive, this will tend to make the resulting design conservative. The natural convection was not added to subsequent hot case runs because leaving it out is conservative.

At this stage in the analysis, the G.E. test conditions were added to the model. These changes consisted of the following:

Hamilton
StandardU
DIVISION OF UNITED AIRCRAFT CORPORATION
A_®

3.6 (continued)

1. Changing the radiation sink temperature to -270°F , the measured cold wall temperature plus 30°C to provide a realistic effective value of -215°F .
2. Changing solar flux from 129 w/ft^2 to 118 w/ft^2 with 3% added to account for chamber reflections.
3. Adjusting absorbtance of the vapor deposited gold tank coating to account for the deviation of the G.E. solar lamp spectrum from the solar spectrum. The data below was generated by GSFC from tank coating samples provided by HSD and the G.E. lamp spectrum:

Tank Sample #	GE	Solar
S/N 002	.172	.219
S/N 011	.200	.258

4. Altering the paddle and spacecraft skin cooldown rate to correspond to cutting off the solar source during the 2 hour transient dark period from the GSFC provided cooldown rates which reflected a precession to a 0° spin angle.

COLD CASE COOLDOWN RATES

	<u>60° CRUISE TEMP °F</u>	<u>TEMP. AT END OF 2 HR TRANSIENT</u>
Space	Paddle = 32°F , Skin = 50°F	Paddle = 23°F , Skin = -60°F
Solar Sim Test	Paddle = 32°F , Skin = 50°F	Paddle = -200°F , Skin = -200°F

With these changes, the model was run for both the hot and cold test conditions. The results showed computed cruise temperatures, especially in the hot case, to be significantly below the test results when using the higher of the two sets of absorbtance values in item 3 above. In order to force correlation of the model with the test results, the solar projected area of the tanks was increased by 5% in the cold case and 15% in the hot case. The original and final solar projected areas for the 3 tank nodes are given below:

Node	Tank 1		Tank 2		Tank 3	
	60°	120°	60°	120°	60°	120°
Orig Ap	.547	.5076	.394	.4804	.122	.384
Final Ap	.573	.582	.413	.551	.128	.440

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.6 (continued)

This adjustment can be justified physically in terms of including in the model the additional solar input of reflected sunlight from the spacecraft and paddles. The reflected solar flux was not included in the tank model input originally. A comparison of the adjusted model output with test temperatures is given by Run D, Table III.

3.7 Coating Modification Analysis

Having matched the test data with the adjusted model, the inputs were changed to space conditions:

- 1) Solar constant = 430 BTU/ft² hr (125) w/ft²
- 2) Sink temp. = -460°F
- 3) Tank gold absorbtance from .200 to .258
- 4) Slesh connectors removed
- 5) Natural convection connectors removed for hot case runs (left in for cold case)
- 6) Fuel load thermal mass was changed to 6 lbs of N₂H₄

A nodal diagram of this model configuration is given by Figure 5. A cold case run was made to determine what would happen if the mission were flown with the tanks "as is". The results, Run E, Table III, show that although the propellant (Tank 1) does not fall to as low a temperature in space as in the test, it does fall far below the spec minimum of 45°F and, in fact, would freeze. An obvious solution to this problem would be to eliminate enough of the black paint stripe to raise the cruise temperature and reduce the cooldown rate in the dark transient with the overall constraint of not exceeding specification maximum temperatures during the hot case transient (180° spin angle) condition.

Since physical removal of the black paint stripe is not possible nondestructively, a mystic vapor deposited gold Kapton tape was selected to cover the stripe where necessary. A sample of this tape was sent to GSFC and the emittance and solar absorbtance were measured.

$$\epsilon_n = .02$$

$$\alpha_{\text{solar}} = .215$$

Both the radiative properties and physical appearance of this material are quite close to those of the gold tank coating.

Using the properties above for the gold tape, a series of hot case and cold case runs were made varying the percentage of black stripe area taped over (uniformly). The results are plotted on Figure 6.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

3.7 (continued)

Based on these results, it was decided to tape 56% of the black stripe area. The taping pattern, chosen for simplicity and to avoid wrinkles is shown by Figure 6. The predicted operating temperature extremes for this configuration are given below:

	Temperatures °F		
	Tank 1 (Fuel)	Tank 2	Tank 3
Cold Case Cruise (60° Spin Angle)	99	98	92
Cold Case Transient (0° Spin Angle, 2 hrs)	53	44	43
Hot Case Cruise (120° Spin Angle)	135	138	131
Hot Case Transient (180° Spin Ange, 2 hrs)	145	154	145

As indicated in the transient hot case above, the predicted propellant temperature can be 145°F which is +5°F higher than the VCPS specification S-723-P-19 max. propellant temperature of 140°F. The HS position has been to establish an upper limit of 140°F on hydrazine systems which will be operational in space for two or more years primarily to minimize hydrazine gas evolution. The hydrazine decomposition process occurs at all temperatures but can be accelerated by increasing temperature or by using materials which tend to promote the reaction. In the VCPS the gold nickel braze is more catalytic than any of the other materials used in the system. A test program was conducted by the Rocket Propulsion Laboratory of the Air Force to study the effect of hydrazine gas evolution in the presence of gold, nickel braze material. The results of this study are reported in AFRPL-TR-69-77 entitled "The Catalytic Decomposition of Hydrazine on Gold, Nickel, and a Gold/Nickel Brazing Alloy". From this report it has been concluded that a 140°F maximum hydrazine temperature for three months in the VCPS will produce decomposition at levels acceptable to the VCPS. In addition, short term exposure of temperature as high as 250°F for several one day periods can also be accommodated. Also, the VCPS was passivated with hydrazine at 120°F for 24 hours with no indication of pressure rise. Therefore, the transient (less than 2 hours) hot case temperature of 145°F is not considered a problem based on the above information.




FIGURE 1. TANK STRIPE PLACEMENT

Hamilton
Standard

U
 DIVISION OF UNITED AIRCRAFT CORPORATION
A®




FIGURE 2. STRIPE PROJECTED AREA VS SPIN ANGLE (ONE TANK)

TABLE I
GSFC SUPPLIED DATA

<u>Material Properties</u>	<u>ϵ_n</u>	<u>α_{solar}</u>
Vapor Deposited Aluminum	.04	.12
Black Paint	.87	.96
Vapor Deposited Gold		
(Tank)	.02	.22
Paddles	$\epsilon_H = .82$.71

View Factors from tanks

<u>To:</u>	<u>F_{IJ}</u>	<u>Radiating Area</u>
Paddles	.21	37.3 ft ²
Cylindrical Skin	.055	8.0 ft ²
Conical Skin	.035	5.34 ft ²
Space	.70	-

<u>Item</u>	<u>Cold Cruise 60°</u>	<u>Cold Transient 10°</u>	<u>Hot Cruise 120°</u>	<u>Hot Transient 170°</u>
Solar Projected Area (1 Tank)	.265 ft ²	0	.343 ft ²	-

Temperatures

Cyl. Skin	10°C	-50°C @ 2hrs	5°C	-50°C @ 2 hrs
Lower Conic	-15°C	-30°C @ 2 hrs	3°C	38°C @ 2 hrs
Paddle	0°C	-5°C @ 2 hrs	-2°C	-5°C @ 2 hrs

TABLE II
COMPARISON OF TEST RESULTS
TO PRE-TEST PREDICTIONS

NODE	Hot Case Cruise 120° Spin Angle		Cold Case Cruise 60° Spin Angle		Cold Case Transient 2 hrs sun off	
	Prediction	Test	Prediction	Test	Prediction	Test
Tank 1 (Fuel)	82	84	112	72	67	10
Tank 2	85	-	88	-	-4	-
Tank 3	79	78	32	65	-13	20

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

TABLE III
THERMAL MODEL RESULTS

Run	Case	Temperatures, °F		
		Tank 1	Tank 2	Tank 3
Solar Simulation	Hot Cruise	84	-	78
Test Data	Cold Cruise	72		65
	Cold Trans	10		20
"A" Slosh	Cold Cruise	66	66	66
(Nodes Shorted)	Cold Trans	22	21	21
"B" Tank Internal Radiation	Cold Cruise	77	72	56
	Cold Trans	38	10	9
"C" Radiation + Gas	Cold Cruise	71	68	62
Convection	Cold Trans	29	17	17
"D" Radiation, Convec-	Cold Cruise	73	73	72
tion, Slosh, G.E. Test	Cold Trans	8	8	7
Conditions and Solar	Hot Cruise	84		81
Flux Adjustment				
"E" Run "D" Tanks	Cold Cruise	81	80	73
"As Is" in Space	Cold Trans	28	18	17




FIGURE 3. RAE-B VCPS TANK THERMAL MODEL PRE-TEST VERSION

RAE-B

N₂ GAS AT 100 PSIA & 2.33 G'S

X = HORIZONTAL GAS LAYERS

+ = VERTICAL GAS LAYER




FIGURE 4. ESTIMATED FREE CONVECTION HEAT TRANSFER COEFFICIENT INSIDE TANKS




FIGURE 5. RAE-B VCPS TANK THERMAL MODEL FINAL VERSION


Hamilton
StandardU
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

FIGURE 6. TANK COATING MODIFICATIONS

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

SVHSER 6226

RAE-B VCPS

PROPELLANT LINE THERMAL REPORT

53<

47

Hamilton
StandardU
DIVISION OF UNITED AIRCRAFT CORPORATION
A®1.0 INTRODUCTION AND SUMMARY

This report presents the development and qualification of the RAE-B Velocity Control Propulsion System propellant line thermal configuration. Subsequent to a propellant line low temperature problem experienced during a solar simulation test at G.E., thermal analyses and propellant line development tests were performed. The resulting configuration indicated that significant improvement in line insulation could be attained but increased heater power would also be required. The new line insulation/increased heater power configuration was then incorporated in the VCPS and a thermal vacuum test was performed. Analysis of these test results indicate propellant line temperatures will be within specification under flight conditions.

2.0 DISCUSSION

The solar simulation test conducted on the VCPS at G.E. showed that the thermal design of the propellant lines was inadequate to maintain the propellant line temperatures above freezing.

2.1 Development Program

A development program was initiated where the test data was analyzed and tests of line insulations were performed at the detail level. This program provided the results shown in Table I and the following conclusions:

- a) Line insulation thermal effectiveness could be improved by utilizing loose wrap multilayer insulation with an overlapping seam covered by gold Kapton tape.
- b) The propellant line would require additional heater power even with the best insulation.

2.2 Verification Test

The VCPS propellant line thermal design was modified and the VCPS reassembled by rewiring the line heater to provide 1 watt/line at 12 VDC and reinsulating with loose wrap insulation utilizing gold Kapton tape (configuration #3 on Table I). In addition the existing thermocouples were removed and replaced with GFE thermistors in the locations shown in Table II and Figure 1. The propellant tanks and +Z surface of the hub were covered with aluminized Mylar insulation to control the propellant line end condition in a zero sun angle condition.

A thermal vacuum test was conducted in the Hamilton Standard 10' x 10' vacuum chamber to provide temperature distribution data on the propellant line at zero sun angle, or worst case condition. This data was then reduced, via the VCPS thermal model, to provide the propellant line thermal characteristics for the appropriate VCPS flight conditions.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

2.3 Test Results

The VCPS was operated in three modes during the thermal vacuum test to provide adequate data for analysis and to check the thermal model at more than one point. The three test conditions were steady state with 12 VDC heater input, steady state with 13.8 VDC heater input and 0 VDC heater input for 2 hours. Table III shows the raw data for each test phase. The chamber conditions were monitored throughout the test. Chamber pressure was maintained below 10^{-5} torr and the effective chamber sink temperature is shown in Table III.

The transient (power off) cooldown was performed to obtain an effective thermal mass per unit length characteristic for the lines. The effective cold wall temperature, measured with a suspended blackbody within the chamber, was approximately -190°F while data was being taken. Tank temperatures at the outlets were 50°F or below (they were cooling very slowly throughout the test).

The data analysis involved inputting the test conditions to the propellant line thermal model and "tuning" the insulation properties until the model reproduced the test data, resulting in insulation performance characteristics measured at the system level. Insulation conductance, emittance, and line thermal mass measured in this manner provide the basis for a new set of predictions for space operation. These predictions were made with the thermal model by replacing the test effective cold wall temperature with the space sink (-460°F) and adding solar input.

At both power settings, the minimum temperature occurred at position A-4, the tube clamp near the end of the arm. There appears to be a local heat leak at this point caused by the insulation penetration of the clamp itself, along with instrumentation lead heat leaks from the many wires leaving the blanket at that location. (These leads will be clipped before flight, substantially reducing this heat loss). Minimum line temperature was 41.8°F at 12 volts and 48.5°F at 13.8 volts. The one hour transient cooldown produced an 180° temperature drop (48°F to 30°F) at location A-4 and similar ΔT 's elsewhere. It should be noted that the line temperatures on the other instrumented arm were at least 10°F higher throughout. The more heavily instrumented line is the coldest of the four because it incorporates the fill and drain valve, the four thermostats and does not have the double insulation wrap in as many places as do the three other lines.

2.4 Thermal Model

The propellant line program divides a pair of lines (a tank on each end and the transtage Tee in the middle) into 70 nodes, 35 line nodes and 35 insulation nodes. The program has stored in a data file such data as the heater locations, clamp locations, and locations of Tee's (fill and drain tee and transtage tee) which are treated as heat leaks. A separate data file holds a solar input

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

2.4 (continued)

table for each spin axis angle. The solar input was calculated earlier in the RAE-B program thermal studies. The propellant lines were sketched onto the GSTC shadow photographs to determine the location of dark areas on the lines. Solar projected area outside of shadowed locations was then determined by drawing board projection of the solar vector onto the propellant line axis. This was done in 15° increments throughout the vehicle spin (360°) and the results numerically averaged over one spin to yield a table of solar intensity versus position for each propellant line.

The program is operated on a TYMSHARE Corp. Terminal. This allows rapid manipulation of the model to achieve a desired result.

2.5 Data Correlation and Extrapolation

The program was input for the 12 volt and 13.8 volt steady state conditions. It was found necessary to simulate the heat leak at location A-4 by decreasing the clamp thermal resistance from 500 BTU/°F-hr to 150 BTU/°F-hr. The primary criteria for acceptable correlation was matching the minimum temperature. Table IV shows the temperature distribution (key temperatures) for the test conditions and corresponding analysis results. The insulation properties necessary to produce these calculated distributions are shown also. It should be noted that the 13.8 volt case yields a higher insulation conductance (poorer performance) than does the 12 volt case. A tendency toward this behavior is expected since the conductance of superinsulation increases with insulation temperature. The higher conductance ($C = .029$) was used in the extrapolation of these results to space operation.

A number of transient cooldown runs were made to match the cooldown rate experienced in test. This yielded a thermal mass per inch value of .003 BTU/°F-in for later use in the space transient analysis.

The values of insulation conductance measured in this series of tests are somewhat higher than those measured in the tube element tests shown in Table I. This discrepancy was anticipated owing to the fact that it was much more difficult to apply insulation at the system level than it was to insulate the free piece of propellant line in the tube element test.

The higher insulation conductance was left in the model for conservatism and the solar input and space temperature (-460°F) were added. For cold case cruise (60° spin axis angle), an average power consumption of .64 watts/line (64% duty cycle) will occur with the temperature distribution shown in Table IV. From this temperature distribution, the cold case transient condition was input (1 hour

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

2.5 (continued)

with no solar flux $\sim 0^\circ$ spin axis angle). A line power value of one watt was utilized along with the effective thermal line mass determined in the test. The temperature distribution after the one hour dark period is shown in Table IV. The temperatures are above the specified minimum 45°F .

TABLE I

LINE INSULATION SUMMARY

Configuration	O. D. (in.)	Conductivity (BTU/ft ² -hr.-°F)	€ outside	Power Required Transient SS Dark (watts/line)	Margin
Design Pt.	.75	.02	.05	1/3	.68 None
#1 Original VCPS (Test Sample)	.75	.19	.12	Excessive	-
#2 2nd Generation (Overlap Seam, Gold Kapton Tape)	1.0	.025 (SS) .035 (T)	.053 (SS) .06 (T)	.7	1.0 Slight
#3 3rd Generation (2nd + overwrap 5 layer)	1.35	.011 (SS) .013 (T)	.048 (SS) .06 (T)	.5	.8 Slight <.1

Notation: SS = Steady State

T = Transient

TABLE II

RAE-B VCPS THERMISTOR LOCATION

<u>KEY</u>	A - Propellant Lines	E - Components and Bracket
	B - Tank	F - Spacecraft
	C - Arm and Hub	
	D - Interior Lines	"R" Prefit Existing Thermistor

No.	Location	Code	Old Code (Thermocouple)
1	Line A @ Line/Tank Vert Port	A-1	N/A
2	Line A @ Line/Tank Horz Port	A-2	N/A
3	Line A	A-3	11 A 1
4	Line A	A-4	11 A 2
5	Line A @ Thermostat	A-5	N/A
	Line A @ Tee	RA-1	Flt Hardware
6	Line A	A-6	11 A 4
7	Line A @ Thermostat	A-7	N/A
8	Line A @ Tee	A-8	11 B 1
9	Line B @ Tee	A-9	11 B 2
10	Line B	A-10	11 B 3
11	Tank on Paint Stripe	B-1	9A
12	Tank Equator	B-2	9C
13	Tank in Mount Area	B-3	9B
	Tank Thermistor #1	RB-1	Flt Hardware
	Tank Thermistor #2	RB-2	Flt Hardware
14	Arm	C-1	11C
15	Hub Exterior	C-2	N/A
16	Hub Shelf #1	C-3	11 D 1
17	Hub Shelf #2	C-4	11 D 2
18	Line A Internal	D-1	10-1
19	Line B Internal	D-2	10-2
20	REA #1 on Chamber	E-1	N/A
21	REA #2 on Chamber	E-2	N/A
22	TCV #1	E-3	4
23	Latch Valve	E-4	5
24	Transducer	E-5	7
25	Bracket Near Edge	E-6	8-1
26	Bracket Middle	E-7	N/A
	Bracket Thermistor	RE-1	Flt Hardware
27	Filter	E-8	N/A

Ref: Attached drawing for thermistor locations.

Hamilton
Standard

U
A₉

TABLE III

ACTUAL VCPS TEMPERATURES (°F)

Time	A-1	A-2	A-3	A-4	A-5	A-6	A-7	A-8	A-9	A-10	B-3	C-2	C-4	D-1	D-2	E-5	E-7	E-8	Effective Sink
16 hrs @ 12 VDC																			
22:15	52.2	47.1	46.5	42.1	52.3	56.7	54.9	57.2	66.2	52.5	38.0	39.0	46.7	52.9	48.5	69.0	59.0	56.4	-192°F
22:30	51.2	47.2	46.4	42.2	52.3	56.6	55.0	57.2	66.2	52.5	37.9	38.6	46.4	53.0	48.5	68.7	60.4	55.8	-192°F
22:45	51.7	47.2	46.3	42.0	52.2	56.6	54.9	57.0	66.1	52.2	37.8	38.4	46.2	53.0	48.5	68.9	62.2	56.5	-192°F
23:00	51.6	46.5	46.5	42.1	52.5	56.7	55.1	57.4	66.2	52.5	37.6	38.2	46.0	52.9	48.5	68.8	57.3	55.9	-192°F
23:15	51.0	46.9	46.3	42.0	52.0	56.1	54.7	56.8	65.6	51.9	37.4	38.2	46.2	52.8	48.4	68.8	62.3	56.1	-190°F
23:30	51.4	46.6	46.2	41.9	52.1	56.6	54.7	56.9	65.8	51.8	37.3	38.3	46.2	52.8	48.4	69.0	60.2	56.6	-190°F
23:45	51.1	47.0	46.3	42.0	52.3	56.5	55.0	57.1	66.0	51.9	37.1	38.4	46.2	52.7	48.4	68.7	58.6	55.8	-190°F
24:00	50.7	46.4	46.1	41.8	52.2	56.3	54.7	56.9	65.8	51.7	37.0	37.8	45.8	52.7	48.3	68.8	62.3	56.2	-190°F
5 hrs @ 13.8 VDC																			
5:15	49.8	43.2	53.3	49.0	62.7	67.3	64.3	67.0	77.9	61.6	34.3	34.9	42.6	56.9	51.0	68.5	61.6	56.0	-190°F
5:30	49.5	43.0	53.4	49.0	62.8	67.1	64.4	67.1	77.9	61.7	34.2	36.7	43.9	56.7	50.8	68.1	58.2	55.4	-183°F
5:45	49.5	42.9	53.1	48.8	62.5	67.0	64.1	66.8	77.7	61.5	34.2	37.3	44.9	56.5	50.8	68.3	61.2	55.4	-183°F
6:00	49.2	42.7	53.1	48.9	62.5	66.8	64.3	66.9	77.8	61.8	34.0	37.2	45.0	56.5	50.8	68.0	61.0	55.4	-183°F
6:15	49.2	42.6	53.2	48.7	62.5	67.4	64.2	66.9	77.7	61.7	33.9	36.9	45.1	56.5	50.8	68.0	59.0	56.0	-183°F
6:30	49.0	42.4	53.2	48.7	62.4	66.8	64.2	66.8	77.9	61.7	33.7	36.9	44.5	56.5	50.8	67.9	61.1	55.5	-183°F
6:45	49.1	42.4	53.1	48.6	62.5	67.1	64.1	66.9	78.0	61.6	33.6	37.5	45.0	56.5	50.8	68.1	58.8	55.9	-185°F
7:00	48.8	42.3	53.0	48.5	62.3	66.8	64.1	66.7	77.9	61.7	33.5	37.8	45.4	56.5	50.8	67.9	62.2	55.7	-185°F
Heaters Off																			
7:10	46.2	41.6	52.0	47.8	60.8	62.8	63.5	65.3	76.1	61.0	33.5	37.7	45.4	56.5	49.9	68.0	60.3	56.1	-185°F
7:20	43.3	41.2	48.5	44.6	56.2	58.0	60.1	60.2	70.8	56.9	33.4	37.9	45.5	56.2	49.9	68.2	56.3	54.4	-185°F
7:30	41.9	40.1	45.1	41.4	52.3	54.4	56.2	56.7	66.5	53.3	33.3	38.2	45.7	55.9	49.8	67.3	53.6	54.5	-185°F
7:40	40.8	38.3	41.5	38.0	48.3	50.5	52.6	52.7	62.1	49.2	33.1	38.6	45.9	55.3	49.5	66.8	51.2	53.3	-185°F
7:50	39.9	37.1	38.3	34.9	44.7	47.1	49.2	49.2	58.0	45.4	33.1	38.5	45.9	54.4	48.9	66.2	49.4	51.9	-182°F
8:00	39.0	35.8	35.2	32.1	41.2	43.9	45.9	45.9	54.4	41.9	33.0	38.0	45.6	53.4	48.2	65.6	47.7	50.4	-183°F
8:10	38.5	34.7	32.1	30.1	39.0	41.7	44.3	43.7	51.9	39.6	33.0	37.7	45.3	52.6	47.6	64.1	46.7	48.4	-183°F

TABLE IV

PROPELLANT LINE TEMPERATURE CORRELATION (°F)

Case	Thermistor Location	A-3	A-4 (@ Clamp)	A-5	A-6	A-7	A-8 (@ Transstage Tee)	A-1 (@ Tank)	A-2 (@ Tank)	$\frac{C}{D}$ (BTU/ft ² - hr °F)	Insulation D (in.)	ϵ	Sink Temp. (°F)
12.0 Volts	Test Data	46.1	41.8	52.2	56.3	54.7	56.9	50.7	46.4	-	1.35	-	-190
	Thermal Model	43.0	40.5	49.7	55.1	58.3	57.5	48	48	.020	1.35	.05	-190
13.8 Volts	Test Data	53	48.5	62.3	66.8	64.1	66.7	48.8	42.3	-	1.35	-	-190
	Thermal Model	49.8	47.6	62.0	69	72.5	71.0	42	42	.029	1.35	.05	-190
Space Operation	Cold Cruise 600 spin angle 1 watt nominal	60.3	55.6	55.9	51.6	52.5	52.2	70	70	.029	1.35	.05	-460
	Cold Transient 1 hr @ 0° spin angle, 1 watt	57.8	53.4	58.1	58.6	60.9	59.8	50	50	.029	1.35	.05	-460

6.0 HSD POST DELIVERY ACTIVITIES

DATE

TASK

3/19-3/22/73
GSFC

1. Performed fluid load using H₂O to determine effect on system unbalance caused by fluid distribution in tanks. Results were acceptable within specified requirements.


5/14-5/22/73
KSFC

1. Performed proof pressure test.
2. Performed calibration of VCPS pressure transducer.
3. Performed internal leakage test on VCPS latch valves and thrust chamber valves.
4. Loaded VCPS with N₂H₄ on balance table to verify proper fluid distribution and pressurized with GN₂ for flight.

- ° The above tasks all gave acceptable results within specified requirements.

APPENDIX A


PHOTOGRAPHS




COMPLETED VCPS

A1


64<




INTERIOR OF VCPS HUB



VCPS IN THERMALLY CONDITIONED FIRING FIXTURE
(Sides removed for clarity)



VCPS AND SPACECRAFT AT VIBRATION TEST



VCPS AND SPACECRAFT AT SOLAR SIMULATION TEST

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

SVHSER 6226

APPENDIX B

GSFC MALFUNCTION REPORTS

69<

Bi

GSFC MALFUNCTION REPORT

NO 02908

Project RAE-B		(2) Spacecraft				(3) Operation		(4) Units			
System or Experiment C P S		(6) Date & Time of Malfunction		Yr	Mo	Day	Time	(7) Date of Report	Mo	Day	(8) Criteria
				7	2	3	28	7	2	0	
NAME		IDENTIFICATION NUMBER				SERIAL NUMBER		MANUFACTURER			
(9) Component R E A								Hamilton Standard			
(10) Assembly T C A								Hamilton Standard			
(11) Sub-Assembly H E A T E R T Q A		S V 7 4 8 7 1 1 - 1						Thermal Systems			
(12) Part H E A T E R T Q A		Manufacturers Part Number 7 6 - 3 4 6 4 - 1						Thermal Systems			
(13) Malfunction Occurred During		1 <input checked="" type="checkbox"/> Qualification Test		3 <input type="checkbox"/> Integration Test		7 <input type="checkbox"/> Bench Test		Reliability <i>J. R. Page 3/5/72</i>			
		2 <input type="checkbox"/> Acceptance Test		5 <input type="checkbox"/> Launch Operations		8 <input type="checkbox"/> Post Launch					
(14) Environment When Failed		1 <input type="checkbox"/> Acceleration		3 <input type="checkbox"/> Thermal-Vacuum		5 <input type="checkbox"/> Humidity		7 <input type="checkbox"/> Ambient		A <input type="checkbox"/> RF/EW/C	
		2 <input type="checkbox"/> Shock		4 <input checked="" type="checkbox"/> Temperature		6 <input type="checkbox"/> Vibration		8 <input type="checkbox"/> Acoustic		0 <input type="checkbox"/> Vacuum	
(15) Hardware Level When Failed		1 <input type="checkbox"/> Part		3 <input type="checkbox"/> Assembly		5 <input checked="" type="checkbox"/> System (VCPS)					
		2 <input type="checkbox"/> Sub-Assembly		4 <input type="checkbox"/> Component		6 <input type="checkbox"/> Spacecraft					
6) REFERENCE											
Aircraft Log Book #		Page		Test Procedure SVHS 5619				4.3.4.2.2.E1			
7) Description of the Malfunction: After engine firing heater resistance was 56 ohms vs required value of $74 \pm 5\%$. Resistance from heater element to case was 5000 ohms vs required value of "open circuit". Investigation has been initiated.											
Target closure date is 4/17/72											
Responsible Engineer is Mr. E. K. Moore											
8) Originator: Mr. E. K. Moore Phone: (203) 623-1621-565 Organization: Hamilton Standard											

Do Not Write Below This Line

INSTRUCTIONS

- (1) Originator - Fill in blocks (1) through (18), with all known information, as defined in instructions on the back of this form.
- (2) Distribute copies in accordance with project directions.

70<

GSFC MALFUNCTION REPORT

NO D 0290

(1) Project RAE-B				(2) Spacecraft				(3) Operation				(4) Unit HRS 1 2			
(5) System or Experiment CPS				(6) Date & Time of Malfunction Yr Mo Day Time 7 2 3 2 8 1 2 0 0				(7) Date of Report Mo Day 3 3 0				(8) Criticality YES 1			
NAME				IDENTIFICATION NUMBER				SERIAL NUMBER				MANUFACTURER			
(9) Component REA												Hamilton Standard			
(10) Assembly TCA												Hamilton Standard			
(11) Sub-Assembly HEATER TCA				SV748711-1								Thermal Systems			
(12) Part HEATER TCA				76-3464-1								Thermal Systems			
(13) Malfunction Occurred During				1 <input checked="" type="checkbox"/> Qualification Test 3 <input type="checkbox"/> Integration Test 7 <input type="checkbox"/> Bench Test											
				2 <input type="checkbox"/> Acceptance Test 5 <input type="checkbox"/> Launch Operations 8 <input type="checkbox"/> Post Launch								Reliability			
(14) Environment When Failed				1 <input type="checkbox"/> Acceleration 3 <input type="checkbox"/> Thermal-Vacuum 5 <input type="checkbox"/> Humidity 7 <input type="checkbox"/> Ambient A <input type="checkbox"/> RFI/EMC											
				2 <input type="checkbox"/> Shock 4 <input checked="" type="checkbox"/> Temperature 6 <input type="checkbox"/> Vibration 8 <input type="checkbox"/> Acoustic 0 <input type="checkbox"/> Vacuum											
(15) Hardware Level When Failed				1 <input type="checkbox"/> Part 3 <input type="checkbox"/> Assembly 5 <input checked="" type="checkbox"/> System (WPS) 6 <input type="checkbox"/> Spacecraft											
				2 <input type="checkbox"/> Sub-Assembly 4 <input type="checkbox"/> Component											
(16) REFERENCE															
Spacecraft Log Book #				Page				Test Procedure SWB 5619				Para 4.3.4.2.2.K1			
(17) Description of the Malfunction: After engine firing heater resistance was 56 ohms vs required value of 74 ± 5%. Resistance from heater element to case was 5000 ohms vs required value of "open circuit". Investigation has been initiated. Target closure date is 4/17/72. Responsible Engineer is Mr. E. K. Moore															
(18) Originator: Mr. E. K. Moore Phone: (203) 623-1621-565 Organization: Hamilton Standard															
Do Not Write in This Space															
(19) Cause of the Malfunction: Failure analysis included X-ray, insulation resistance, heater resistance, spectral analysis, conductometric carbon analysis and ignition test. Analysis indicated that organic contamination of the heater wire or MgO insulation, or both, resulted in the presence of elementary carbon in the MgO. This caused a partial electrical short between the heater wires and between the wires and the case.															
Do Not Write in This Space															
(20) Corrective Action Taken: All heaters will be replaced by new heaters manufactured with the inclusion of the following steps.															
A. Heater element supplier to degrease resistance wire in acetone.															
B. Heater element supplier to cut resistance wire to desired length and heat electrically in air: (1) wire unsupported except at ends later removed, (2) heat to maintain approximately 1,700° surface temperature for 2 minutes minimum, (3) prevention of any															
If Corrective Action is Required on Other Units, List Units by Serial No. Continued on next page.															
Do Not Write in This Space															
(21) Failure Analysis Performed?				YES NO 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>				Organization That Performed Failure Analysis Thermal Systems, with Hamilton Standard				Failure Analysis Report Number "Minutes of Meeting held at Thermal Systems" Date 4/11/72			
(22) Action Taken on Failed Unit				1 <input type="checkbox"/> Rework/Repair 2 <input type="checkbox"/> Modified 3 <input checked="" type="checkbox"/> Discarded 4 <input checked="" type="checkbox"/> Replaced 5 <input type="checkbox"/> None				Organization That Performed Rework/Repair N/A				Date			
(23) Is Retest Required?				1 <input type="checkbox"/> Yes 2 <input checked="" type="checkbox"/> No				If Yes, State Retest Requirements							
(24) Retest Results				Satisfactory Unsatisfactory 1 <input type="checkbox"/> 2 <input type="checkbox"/>				Remarks: N/A							
(25) Unit May Be Used For				Flight Test Only 1 <input type="checkbox"/> 2 <input type="checkbox"/>				N/A							
Yr Mo Day Date MR Closed				GSFC Project Approval				GSFC MRRT Approval				Date Contractor Approval 4/16/72			

GSFC MALFUNCTION REPORT

Project							(2) Spacecraft						(3) Operation						(4) Units HR: 000					
System or Experiment								(6) Date & Time of Malfunction				Yr	Mo	Day	Time	(7) Date of Report				Mo	Day	(8) Critical YES NO 1 2		
NAME								IDENTIFICATION NUMBER				SERIAL NUMBER				MANUFACTURER								
(9) Component																								
(10) Assembly																								
(11) Sub-Assembly																								
(12) Part								Manufacturers Part Number																
(13) Malfunction Occurred During								1 <input type="checkbox"/> Qualification Test				3 <input type="checkbox"/> Integration Test				7 <input type="checkbox"/> Bench Test								
								2 <input type="checkbox"/> Acceptance Test				5 <input type="checkbox"/> Launch Operations				8 <input type="checkbox"/> Post Launch								
(14) Environment When Failed								1 <input type="checkbox"/> Acceleration				3 <input type="checkbox"/> Thermal-Vacuum				5 <input type="checkbox"/> Humidity				7 <input type="checkbox"/> Ambient		A <input type="checkbox"/> RFI/EMC		
								2 <input type="checkbox"/> Shock				4 <input type="checkbox"/> Temperature				6 <input type="checkbox"/> Vibration				8 <input type="checkbox"/> Acoustic		0 <input type="checkbox"/> Vacuum		
(15) Hardware Level When Failed								1 <input type="checkbox"/> Part				3 <input type="checkbox"/> Assembly				5 <input type="checkbox"/> System								
								2 <input type="checkbox"/> Sub-Assembly				4 <input type="checkbox"/> Component				6 <input type="checkbox"/> Spacecraft								
6) REFERENCE																								
Spacecraft Log Book # _____ Page _____ Test Procedure _____ Para _____																								
7) Description of the Malfunction:																								
8) Originator:								Phone:				Organization:												
Do Not Write in This Space																								
9) Cause of the Malfunction:																								
Do Not Write in This Space																								
10) Corrective Action Taken: contact of wire and any other heater element component with organic material.																								
C. Thermal Systems shall bake each unterminated heater assembly in air at 1,700°F for a minimum of one hour.																								
Corrective Action is Required on Other Units, List Units by Serial No. S/N 001, 002, 004																								
Do Not Write in This Space																								
(21) Failure Analysis Performed?		YES NO		Organization That Performed Failure Analysis _____																				
		1 <input type="checkbox"/> 2 <input type="checkbox"/>		Failure Analysis Report Number _____ Date _____																				
(22) Action Taken on Failed Unit		1 <input type="checkbox"/> Rework/Repair		2 <input type="checkbox"/> Modified		3 <input type="checkbox"/> Discarded		4 <input type="checkbox"/> Replaced		5 <input type="checkbox"/> None		Date _____												
(23) Is Retest Required?		1 <input type="checkbox"/> Yes		2 <input type="checkbox"/> No		If Yes, State Retest Requirements _____																		
(24) Retest Results		Satisfactory		Unsatisfactory		Remarks: _____																		
		1 <input type="checkbox"/>		2 <input type="checkbox"/>																				
(25) Unit May Be Used For		Flight		Test Only		_____																		
		1 <input type="checkbox"/>		2 <input type="checkbox"/>																				
Yr	Mo	Day	Date MR Closed	GSFC Project Approval				GSFC MRPT Approval				Date	Contractor Approval				Date							
													<i>[Signature]</i> 4/20/72 ✓											
77				B3				Copy 4																

GSFC MALFUNCTION REPORT

NOD. 02

(1) Project RAE-B		(2) Spacecraft		(3) Operation		(4) Mission	
System or Experiment		(6) Date & Time of Malfunction		Yr	Mo	Day	Time
				72	05	09	
		(7) Date of Report		Mo	Day	Yr	
				05	18		
NAME		IDENTIFICATION NUMBER		SERIAL NUMBER		MANUFACTURER	
(2) Component VCPS		SV 748720-1		1000		Hamilton Standard	
(10) Assembly							
(11) Sub-Assembly							
(12) Part		Manufacturers Part Number					
(13) Malfunction Occurred During		1 <input checked="" type="checkbox"/> Qualification Test	3 <input type="checkbox"/> Integration Test	7 <input type="checkbox"/> Bench Test	Reliability: <input checked="" type="checkbox"/> 5/18		
		2 <input type="checkbox"/> Acceptance Test	5 <input type="checkbox"/> Launch Operations	8 <input type="checkbox"/> Post Launch			
(14) Environment When Failed		1 <input type="checkbox"/> Acceleration	3 <input checked="" type="checkbox"/> Thermal-Vacuum	5 <input type="checkbox"/> Humidity	7 <input type="checkbox"/> Ambient	A <input type="checkbox"/> RFI	
		2 <input type="checkbox"/> Shock	4 <input type="checkbox"/> Temperature	6 <input type="checkbox"/> Vibration	8 <input type="checkbox"/> Acoustic	0 <input type="checkbox"/> Vacuum	
(15) Hardware Level When Failed		1 <input type="checkbox"/> Part	3 <input type="checkbox"/> Assembly	5 <input checked="" type="checkbox"/> System (VCPS)			
		2 <input type="checkbox"/> Sub-Assembly	4 <input type="checkbox"/> Component	6 <input type="checkbox"/> Spacecraft			

(16) REFERENCE

Spacecraft Log Book # _____ Page _____ Test Procedure SVHS 5619 Para 4.3.11

(17) Description of the Malfunction: VCPS was undergoing thermal verification testing at G. E., Valley Forge per step 11 of Ref. Quality Test Procedure. At the end of 2 hours, tank temp. was +11°F and line temp. was -13°F. The required temp. is 40°F min. Unit was returned to HS (Winlocks, Ct.) for continuation of Quality Test (authorized by TWX GSFC to HS dated 5/12/72). Target closure date is 7/15/72.

Closure responsibility E. K. Moore

Originator: M. Bonar Phone: (203) 623-1621 x494 Organization: Hamilton Standard

Do Not Write Below This Line

INSTRUCTIONS

(1) Originator - Fill in blocks (1) through (18), with all known information, as defined in instructions on the back of this form.

(2) Distribute copies in accordance with project directions.

GSFC MALFUNCTION REPORT

NO D 02909

Project 243-B		(2) Spacecraft		(3) Operation		(4) Units HRS CYS 1 2	
System or Experiment		(6) Date & Time of Malfunction Yr Mo Day Time 72 7 5 00		(7) Date of Report Mo Day 72 7 13		(8) Critical YES NO 1 2	
NAME		IDENTIFICATION NUMBER		SERIAL NUMBER		MANUFACTURER	
Component		718720-1		1000		Hamilton Standard	
Assembly							
Sub-Assembly							
Part		Manufacturers Part Number					
Malfunction Occurred During		1 <input checked="" type="checkbox"/> Qualification Test 2 <input type="checkbox"/> Acceptance Test		3 <input type="checkbox"/> Integration Test 5 <input type="checkbox"/> Launch Operations		7 <input type="checkbox"/> Bench Test 8 <input type="checkbox"/> Post Launch	
Environment When Failed		1 <input type="checkbox"/> Acceleration 2 <input type="checkbox"/> Shock		3 <input checked="" type="checkbox"/> Thermal-Vacuum 4 <input type="checkbox"/> Temperature		5 <input type="checkbox"/> Humidity 6 <input type="checkbox"/> Vibration	
Hardware Level When Failed		1 <input type="checkbox"/> Part 2 <input type="checkbox"/> Sub-Assembly		3 <input type="checkbox"/> Assembly 4 <input type="checkbox"/> Component		5 <input checked="" type="checkbox"/> System (VCPS) 6 <input type="checkbox"/> Spacecraft	
REFERENCE		Draft Log Book #		Page		Test Procedure	
						SWHS 5619	
						Para 4.3.11	
Description of the Malfunction: was undergoing thermal verification testing at G. L. Valley Propulsion Test Procedure. At the end of 2 hours, tank temp. was +11°F and line temp. was -10°F. The required temp. is -40°F min. Unit was returned to IT (indication, etc.) for continuation of final test (authorized by TX GSFC to ES dated 5/12/72).							
Date of report: 7/13/72							
Signature: L. K. Moore							
Originator:		Phone: 243-1521		Organization: Hamilton Standard			
Not Write in This Space							
Cause of the Malfunction: A failure analysis of the VCPS thermal design was conducted at Hamilton Standard by comparing the reduced data from the thermal verification test to the original thermal model. The thermal model input parameters were varied until the model prediction closely approximated the test results. This analysis yielded the following conclusions: a) the tank temperature distribution and rapid loss of temperature was duplicated by shorting internal tank thermal nodes together b) the tank nodes were shorted during the thermal							
Not Write in This Space							
Verification test via natural connection of the pressurant gas, internal convection and propellant sloshing c) the convection and radiation phenomenon will exist under test condition and should be included in the thermal model d) the thermal properties of the propellant line insulation would have to have been significantly poorer than expected by the thermal model to yield the test results. Tests subsequently performed on line insulation revealed from the VCPS confirmed that the insulation thermal properties were as poor as the VCPS							
Corrective Action is Required on Other Units, List Units by Serial No.							
Not Write in This Space							
Failure Analysis Performed?		YES NO 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Organization That Performed Failure Analysis HSD		Date 31 Aug. 1972	
Action Taken on Failed Unit		1 <input checked="" type="checkbox"/> Rework/Repair 2 <input checked="" type="checkbox"/> Modified 3 <input type="checkbox"/> Discarded 4 <input type="checkbox"/> Replaced 5 <input type="checkbox"/> None		Failure Analysis Report Number ACS-2093-2.3-099		Date Aug. 1972	
Is Retest Required?		1 <input checked="" type="checkbox"/> Yes 2 <input type="checkbox"/> No		If Yes, State Retest Requirements Done - See above report			
Retest Results		Satisfactory Unsatisfactory 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Remarks:			
Unit May Be Used For		Flight Test Only 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>					
Mo	Day	Date MR Closed	GSFC Project Approval		GSFC MRRT Approval		Date
							10/5/72

74<

B5

Copy 4

(1) Project R1E-B				(2) Spacecraft				(3) Operation				(4) U HRS			
(5) System or Experiment				(6) Date & Time of Malfunction Yr. 77 Mo 05 Day 03 Time				(7) Date of Report Mo 05 Day 23				(8) U HRS			
NAME				IDENTIFICATION NUMBER				SERIAL NUMBER				MANUFACTURER			
(9) Component VCPS				37 718 7 3 2 - 2				1000				Hamilton Standard			
(10) Assembly															
(11) Sub-Assembly															
(12) Part				Manufacturers Part Number											
(13) Malfunction Occurred During		1 <input checked="" type="checkbox"/> Qualification Test		3 <input type="checkbox"/> Integration Test		7 <input type="checkbox"/> Bench Test									
		2 <input type="checkbox"/> Acceptance Test		5 <input type="checkbox"/> Launch Operations		8 <input type="checkbox"/> Post Launch								Reliability: 4R 5/10	
(14) Environment When Failed		1 <input type="checkbox"/> Acceleration		3 <input checked="" type="checkbox"/> Thermal-Vacuum		5 <input type="checkbox"/> Humidity		7 <input type="checkbox"/> Ambient				A <input type="checkbox"/> RFI/E			
		2 <input type="checkbox"/> Shock		4 <input type="checkbox"/> Temperature		6 <input type="checkbox"/> Vibration		8 <input type="checkbox"/> Acoustic				0 <input type="checkbox"/> Vacuum			
(15) Hardware Level When Failed		1 <input type="checkbox"/> Part		3 <input type="checkbox"/> Assembly		5 <input checked="" type="checkbox"/> System (VCPS)									
		2 <input type="checkbox"/> Sub-Assembly		4 <input type="checkbox"/> Component		6 <input type="checkbox"/> Spacecraft									

(16) REFERENCE
Spacecraft Log Book # _____ Page _____ Test Procedure **SVH3 5612** Para **4.3.11**

(17) Description of the Malfunction: **VCPS was undergoing thermal verification testing at G. E., Valley Forge per para 11 of Ref. Unit Test Procedure. At the end of 2 hours, tank temp. was 112°F and line temp. was -12°F. The required temp. is 100°F min. Unit was returned to HS (and Locks, Ct.) for continuation of thermal Test (authorized by TWA GSFC to HS dated 5/12/72). Target closure date is 7/15/72.**

Closure responsibility **A. K. Moore**

(18) Originator: **M. Boman, G. E.** Phone: **(203) 623-1521 x104** Organization: **Hamilton Standard**

Do Not Write in This Space

(19) Cause of the Malfunction: (continued)
test results indicated. Hamilton then conducted a series of development tests on various line insulation configurations. It was found that line insulation could be manufactured and assembled with substantially improved thermal characteristics but that it would require additional line heater power even when the best line insulation configuration was used.

Do Not Write in This Space

(20) Corrective Action Taken: Agreement was then reached with NASA to proceed with the following action:
a) determine by analysis any changes to the tank thermal design required to maintain proper flight temperatures b) remove and replace the line insulation with the best available configuration c) replace the thermocouple instrumentation with G.F.E. thermistors d) rewire the propellant line heaters to provide 1 watt heat input to each line e) conduct a thermal vacuum test on the VCPS propellant line, simulating worst case specification with zero sun input. The test results indicated that the line insulation could be manufactured and assembled with substantially improved thermal characteristics but that it would require additional line heater power even when the best line insulation configuration was used.

If Corrective Action is Required on Other Units, List Units by Serial No. (**#20** continued on attached sheet)

Do Not Write in This Space

(21) Failure Analysis Performed?		YES NO 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Organization That Performed Failure Analysis HSD		Failure Analysis Report Number ACS-2093-2.3-099		Date 31 Aug. 1977	
(22) Action Taken on Failed Unit		1 <input checked="" type="checkbox"/> Rework/Repair 2 <input checked="" type="checkbox"/> Modified 3 <input type="checkbox"/> Discarded 4 <input type="checkbox"/> Replaced 5 <input type="checkbox"/> None		Organization That Performed Rework/Repair HSD				Date Aug. 1972	
(23) Is Retest Required?		1 <input checked="" type="checkbox"/> Yes 2 <input type="checkbox"/> No		If Yes, State Retest Requirements Done - See above report					
(24) Retest Results		Satisfactory Unsatisfactory 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Remarks:					
(25) Unit May Be Used For		Flight Test Only 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>							

Yr. Mo. Day Date MR Closed GSFC Project Approval GSFC MRRT Approval Date Contractor Approval **10/5/77**

GSFC MALFUNCTION REPORT

NOD 02909

Project: RAE-B		(2) Spacecraft		(3) Operation		(4) Units HRS CYS 1 2	
System or Experiment		(6) Date & Time of Malfunction Yr Mo Day Time 75 05 09		(7) Date of Report Mo Day 05 18		(8) Critical YES NO 1 2	
NAME		IDENTIFICATION NUMBER		SERIAL NUMBER		MANUFACTURER	
Component CIP 13		97 7 18 17 20 - 1		14000		Hamilton Standard	
Assembly							
Sub-Assembly							
Part		Manufacturers Part Number					
Malfunction Occurred During		1 <input checked="" type="checkbox"/> Qualification Test 2 <input type="checkbox"/> Acceptance Test		3 <input type="checkbox"/> Integration Test 5 <input type="checkbox"/> Launch Operations		7 <input type="checkbox"/> Bench Test 8 <input type="checkbox"/> Post Launch	
Environment When Failed		1 <input type="checkbox"/> Acceleration 2 <input type="checkbox"/> Shock		3 <input checked="" type="checkbox"/> Thermal-Vacuum 4 <input type="checkbox"/> Temperature		5 <input type="checkbox"/> Humidity 6 <input type="checkbox"/> Vibration	
Hardware Level When Failed		1 <input type="checkbox"/> Part 2 <input type="checkbox"/> Sub-Assembly		3 <input type="checkbox"/> Assembly 4 <input type="checkbox"/> Component		5 <input checked="" type="checkbox"/> System (VCPS) 6 <input type="checkbox"/> Spacecraft	
REFERENCE							
Craft Log Book #		Page		Test Procedure		Para	
				SVIS 5519		4.3.11	
Description of the Malfunction: VCPS was undergoing thermal verification testing at G. E. Valley Forge and 11 of 12 thermal test procedures. At the end of 2 hours, tank temp. was 111°F and line temp. was 111°F. The required temp. is 100°F min. Unit was returned to EC (Windsor Works, OH.) for continuation of thermal test (authorized by TWA GSFC to HS dated 5/22/72). Report closure date is 7/15/72.							
Closure responsibility: R. K. Moore							
Originator: R. K. Moore		Phone: 203 523-1521 x104		Organization: Hamilton Standard			
Do Not Write in This Space							
XXXXXXXXXXXX (#20 continued) analysis indicated that the proper temperature range would be maintained if the proper emittance to absorbance ratio is selected. The proper ϵ/α ratio was achieved by covering 56% of the tank black paint strip area with vapor deposited gold ion tape. With the propellant tanks modified in this way, the min 60° cruise temperature is calculated to be 96°F with a 50°F min temp. during the 2 hr. dark transient. VCPS propellant tanks were reinsulated and the line heaters rewired in accordance with E.C. E40500-64. The							
Do Not Write in This Space							
XXXXXXXXXXXX thermal vacuum test was performed and test data analyzed. The minimum temperatures under any flight is calculated to be 51°F. This Malfunction Report is based on the basis of the above action and the acceptance Hamilton Standard Thermal Report 2093-2.3-099.							
Corrective Action is Required on Other Units, List Units by Serial No.							
Do Not Write in This Space							
1) Failure Analysis Performed?		YES NO 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Organization That Performed Failure Analysis HSD		Date: 31 Aug. 1972	
2) Action Taken on Failed Unit		1 <input checked="" type="checkbox"/> Rework/Repair 2 <input checked="" type="checkbox"/> Modified 3 <input type="checkbox"/> Discarded 4 <input type="checkbox"/> Replaced 5 <input type="checkbox"/> None		Organization That Performed Rework/Repair HSD		Date:	
3) Is Retest Required?		1 <input checked="" type="checkbox"/> Yes 2 <input type="checkbox"/> No		If Yes, State Retest Requirements Done - See above report			
4) Retest Results		Satisfactory Unsatisfactory 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>		Remarks:			
5) Unit May Be Used For		Flight Test Only 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/>					
Mo	Day	Date MR Closed	GSFC Project Approval	GSFC MRRT Approval	Date	Contractor Approval	Date
						W. K. Moore	10/5/72

APPENDIX C

VIBRATION REPORT

SLS TEST ENGINEERING
TEST REPORT

FILE CODE TER 2762
DATE _____

PROGRAM RAE-B TEST ITEM SV748720 S/N 1
NAME OF TEST QUAL VIBRATION DATE OF TEST 4/15 - 4/18/72
TEST SPECIFICATION SVHS 5619 TEST PLAN _____
CONCLUSIONS _____

RECOMMENDATIONS (OPTIONAL) _____

OBSERVATIONS (OPTIONAL) INCLUDED HERE ARE ACCELEROMETER
RESPONSE CURVES, LOG SHEETS AND PHOTOS OF ABOVE
VIBRATION TEST.

TOTAL TEST TIME _____
ENDURANCE CYCLES _____
ORIGINAL COPY _____

CC: CHIEF OF RELIAB/CHIEF OF DESIGN _____
TEST ENGINEERING FILE

TEST ENGINEER WESMITH APPROVED/DATE R. Mero 6/20/72
SIGNATURE WESmith
DATE 6/20/72 78< Ciii

Memo File Code RAEB-VCPS-1212

Memorandum to:

Page 1 of 3Program RAE-BTest Item(s) VCPSDate of Test 4-15/4-18-72Serial No.(s) 00001Name of Test QUALIFICATIONSpecification AT-VCPS

Subject:

THE ABOVE ITEM WAS VIBRATED AT HSD
ON RIG 26 IN A LOADED AND PRESSURIZED
CONDITION. THE VCPS WAS MOUNTED ON FIXTURE
SVSK 79594. PORTIONS OF THE TESTING WERE
PERFORMED WITH THE VCPS ONLY AND OTHERS
WERE PERFORMED WITH THE SPACECRAFT MOUNTED
TO THE VCPS.

CONCLUSION:) THE VCPS CAN WITHSTAND
THE SPECIFIED VIBRATION WITH NO SIGNS OF
STRUCTURAL DEGRADATION WHILE LOADED WITH
45±0.5LBS HIGH PURITY WATER, AND PRESSURIZED
TO 260±PSIA GNa.

CON'TTest Engineer S. MEHMED JRSignature Sami Mehmed JrDate of Report 5-12-72Approved Carl J. MeluchDate May 12, 1972

DEVIATIONS:

1) RESPONSE DATA FROM LOCATION [HZ], PRESSURE TRANSDUCER MOUNT, TEST 14 LOOKS VERY QUESTIONABLE AS SHOWN BY TRACE 49. THE ACCELEROMETER AT LOCATION [HZ] WAS NOT DAMAGED OR UNFASTENED, HOWEVER THE SIGNAL SHOWN ON TRACE 49 REPRESENTS NOISE ONLY.

2) TEST 16, TRACE 60 REPRESENTING LOCATION [HZ] MUST BE QUESTIONED SINCE TRACE 49 DOES NOT LOOK REALISTIC. TRACE 60 HOWEVER DOES APPEAR TO REPRESENT A REALISTIC LEVEL

3) TEST N° 16 WAS ACCEPTED BY NASA REPRESENTATIVE, MR M. CALABRESE, AFTER THE FOLLOWING OVERTEST OCCURRED.

(I.O.C. ACCEPTING THE TEST IS INCLUDED IN THE REPORT). SUBJECTED TEST ITEM TO ± 6.2 GPK FROM 23-27HZ AND ± 2.9 GPK AT 82HZ. THE CAUSE WAS DUE TO A MALFUNCTION IN THE ELECTRONIC SWEEP/HOLD CONTROL LOGIC.

4) TEST 10, TRACE 23, LOCATION [BY] DATA WAS NOT SECURED BECAUSE THE ACCELEROMETER LOOSENEED FROM ITS ATTACHMENT POINT.

DEVIATIONS CON'T

5) A REDUCED CONTROL CURVE FOR TEST N° 7, Y AXIS, IS NOT INCLUDED. THE INFORMATION WAS NOT RECORDED FOR THIS TEST BECAUSE THE DATA PATCH CORD WAS NOT PROPERLY CONNECTED TO THE RECORDER INPUT

6) TEST NUMBER 17 AND TEST NUMBER 10 TRACES 24 AND 13 RESPECTIVELY INDICATED TOLERANCE DEVIATIONS AT 60HZ AND 120HZ, THESE DEVIATIONS WERE CAUSED BY 60 HZ NOISE WHICH WAS NOT DETECTED DURING THE TEST.

RESULTS:

1) THE SPACECRAFT C.G. DID NOT EXCEED $\pm 4.5 \text{ GPK}$ DURING TESTING BETWEEN 16 AND 23 HZ AS LIMITED BY THE SPECIFICATION.

2) THE SPACECRAFT C.G DID EXCEED $\pm 4.5 \text{ GPK}$ AS SHOWN ON TRACE 24 TEST 7 ONLY.

3) NO VISIBLE STRUCTURAL DAMAGE WAS DETECTED.

Table of Contents

Test Background	Section I
A) Instrumentation and Calibration List	
B) Block Diagram of Test System	
C) Illustration of Item & Transducer Location	
D) Random Analysis Outline	
X - Axis	Section II
A) Sine Data	
B) Random Data	
Y - Axis	Section III
A) Sine Data	
B) Random Data	
Z - Axis	Section IV
A) Sine Data	
B) Random Data	
Logs	Section V
A) Operator Log	
B) Instrumentation Master & Running Log	
C) Data Reduction Log	

Section I

Test Background

- A) Instrumentation and Calibration List
- B) Block Diagram of Test System
- C) Illustration of Item & Transducer Location
- D) Random Analysis Outline

LABORATORY OPERATIONS ENGINEERING
TEST EQUIPMENT
RIG 26 MB C210

<u>ITEM</u>	<u>MANUFACTURER</u>	<u>ACCURACY</u>	<u>MODEL</u>	<u>S/N</u>
Signal Conditioner	Unholtz-Dickie	±2%	61ORM-3	133
Signal Conditioner	Unholtz-Dickie	±2%	61OR	202
Logarithmic Converter	Moseley	±5%	N165-T2	451
Logarithmic Converter	Moseley	±5%	7561A	825-00944
Exciter Control	MB Electronics	±4%	N575/ 576	142
*Differential AC/ DC Voltmeter	John Fluke	±0.05%	803BR	582
Wide Range Oscillator	Hewlett Packard	±2%	200CDR	229- 45434
Oscilloscope	Hewlett Packard	±5%	130C	3200-1326
*Counter	Anadex	±1 Count	CF200R	2933
Dynamic Analyzer	Spectral Dynamics	Linearity ±3% D.C. Out ±0.25db Filter Sig.±0.25db	SD101A	233
*Spectral Density Voltmeter	Ballantine	±2%	321	866
X-Y Plotter	Moseley	±5%	135	1542
X-Y Plotter	Hewlett Packard	±5%	7030A	823-01313
Dynamic Analyzer	Spectral Dynamics	±0.25db Log D.C.	SD101B	39
Sine Wave Center	Ling Electronics		SCO-100	39

Standard Calibration Period - Entire system 2 months and also item * are 4 months.

TEST EQUIPMENT (cont'd)
RIG 26 MB CP10

<u>ITEM</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>S/N</u>
Galvanometer Amplifier	Honeywell	T66A- 500	6-3373
Attenuator	Hewlett Packard	350A	E11060
Constant Level Output Adapter	Spectral Dynamics	SD11	39
Tape Junction Unit	HSD	B	1
Oscilloscope	Tektronix	RM561-A	009168
Time Base Horiz. Plug-In	Tektronix	2B67	016133
Four Trace Vert. Amp. Plug In	Tektronix	3A74	003197
Spectrum Equalizer	Ling Electronics	SE80D	113
Spectrum Equalizer	Ling Electronics	SE80C	114
Channel Mode Selector	Ling Electronics	CM40B	271
Low Frequency Equalizer	Ling Electronics	5LF-8A	174
Manual Selector Switch	Ling Electronics	SSM-100A	114
Channel Mode Selector	Ling Electronics	CM40B	263
Control Panel	Ling Electronics	CP-10B	170
Driver Amplifier	Ling Electronics	A-10	165
Dual Noise Generator	Ling Electronics	GRN200B	167


C4

TEST EQUIPMENT (cont'd)
RIG 26 ME C210

<u>ITEM</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>S/N</u>
Meter Range Selector	Ling Electronics	MR40B	282
Meter Range Selector	Ling Electronics	MR40B	278
Power Distribution	Ling Electronics	PB10	162
Displacement Limiter	MB Electronics	N20	429
Multiple Level Control	MB Electronics	N661	340
Multiple Channel Amplifier	MB Electronics	N270	401
Equalizer By-Pass	MB Electronics	N322	586
Control Panel	MB Electronics	N619	344
Amplitude Protector Control	MB Electronics	N56	481
Null Meter Panel	MB Electronics	N152	315
Power Supply	MB Electronics	N138	168
Amplifier	MB Electronics	5140	302
Exciter	MB Electronics	C210	251
Low Pass Filter	MB Electronics	N171	360
Power Supply	Ling Electronics	APS102	32
Power Supply	Ling Electronics	APS10A	165
Power Supply	Ling Electronics	APS1130	113
Power Supply	Ling Electronics	APS103	27
Spectrum Analyzer	Ling Electronics	SA100	162CAB-A
Spectrum Analyzer	Ling Electronics	SA100	162CAB-B

TEST EQUIPMENT
RIG 26 MB C210 (cont'd)

<u>ITEM</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>S/N</u>
Master Schedule Selector	MB Electronics	N230	397
Signal Selector	MB Electronics	N151-T1	587
Signal Selector	MB Electronics	N151-T1	616
Tape Recorder	Ampex	FR1200	122-0301
Visicorder	Honeywell	1508	15-2098
Galvanometer Amplifier	Honeywell	T66A-500	6-3383
Signal Selector	MB Electronics	N151-T1	586
Waveform Synthesizer	Exact	20	375
Power Supply	MB Electronics	N141	135
Transducer Excitation	ENDEVCO	SR1000EP	MB01
Multiple Channel Scanner	MB Electronics	N280-T2	403
Power Selector	MB Electronics	N320	215
Power Amplifier	MB Electronics	N290	467
Peak Notch Equalizer	MB Electronics	N20	722
Master Control Panel	MB Electronics	N240	579
Variable Gain Amplifier	MB Electronics	N310	434
X-Y Recorder Input Selector	MB Electronics	N74	317



TYPICAL TEST SETUP

C8

88<

Handwritten signature or mark.


Laboratory Operations Engineering

TEST EQUIPMENT

Item	Manufacturer	Accuracy	Model	S/N	Calibrated	
Accelerometer	Endevco	$\pm 2\%$	2226	NB62	3-20-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TD40	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TE83	3-20-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TD44	3-20-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TG75	3-20-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	WR11	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TD45	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TD48	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2226	TG74	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	XM21	4-10-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	YK20	4-10-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	XN32	4-10-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	XJ29	4-10-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	RN81	3-23-72	A
Accelerometer	Endevco	$\pm 2\%$	2222	WF75	4-10-72	A
Accelerometer	Endevco	$\pm 2\%$	2215	VG57	3-9-72	A
Accelerometer	Endevco	$\pm 2\%$	2215	VH49	3-9-72	
Accelerometer	Endevco	$\pm 2\%$	2215	WH97	3-9-72	
Accelerometer	Endevco	$\pm 2\%$	2215	VH46	3-9-72	

Standard calibration period is 2 months.


A = Used for this test.




TYPICAL TEST SETUP




SS10367-6




C10





Fixture	-	SVSK79594
Test Type	-	Evaluation
Test Date	-	4-13-72
Axis	-	Y




C12












C16











C20


101<





C22

103<



SSD VIBRATION GENERATING SYSTEM RIG 26 / MB C-210

RANDOM VIBRATION ANALYSIS

METHOD B

The power spectrum density analyzer is a SD301B REAL TIME ANALYZER and a SD302A ENSEMBLE AVERAGER whose calibration for each test is based on a calibrated signal supplied from equipment listed in the instrumentation section.

1. ANALYZER PARAMETERS

<u>Analysis Range</u> <u>Upper Limits (Hz)</u>	<u>Bandwidth (Hz)</u> <u>(3db Filter)</u>	<u>*Resolution</u> <u>(Hz)</u>	<u>Effective (Noise)</u> <u>Bandwidth (Hz)</u>
20,000	60	40	64
10,000	30	20	32
5,000	15	10	16
2,000	6	4	6.4
500	1.5	1	1.6
100	0.30	0.2	0.32
50	0.15	0.1	0.16
10	0.03	0.02	0.032

*Spacing of filter location.

2. DEGREES OF FREEDOM

For real time analysis the bandwidth resolution is the reciprocal of the analysis period ($BT = 1$).

$$N = 2 \times B \times T_x \text{ (No. of Ensembles)}$$

$$N = 2 \times \text{No. of Ensembles}$$

No. of Ensembles available:

1, 2, 4, 8, 16, 32, 64 (normally used unless specified),
128, 256, 512, 1024.


Section II

X - Axis

A) Sine Data

B) Random Data


RIG # 26	OPERATOR P. Jordan	WITNESS	WITNESS	TEST NO. 7
TEST ENGINEER S. Mehmed	CHECKED BY GEIB	PROJECT RAE-B	DATE 4-14-72	TIME 1120



INPUT LEVEL EXCIT. AXIS 1.0		SENSING AXIS X	
ACCEL S/N TD40		X	
ACCEL SENSITIVITY 2.805		MV RMS GP COL GP	
FILTER 10-100-200		HZ B.W.	
FILTER CROSSOVER @ 70-700		HZ	
SWEEP RATE 4.0		OCT/MIN	
TAPER REEL NO. 012294		LIVE FROM TAPE <input checked="" type="checkbox"/>	
COMPR. SPEED Var.		DB/SEC.	
CHG. @ - HZ TO		DB/SEC.	
CHG. @ - HZ TO		DB/SEC.	
NON OPERATING TEMP. 74°F		CONTROL <input checked="" type="checkbox"/>	
RESPONSE <input type="checkbox"/>		LOCATION	
SPECIAL CONDITIONS Bare Fixture Scan			
REPORT NO. MASTER AG 1774			

FREQ. RANGE & DIRECTION S-2K HZ	ITEM SVSK79594	CODE VCPS-FIXT	SERIAL NO. SVSK79594	SPEC. A7-VCPS	PARA. 4.3.7	AMEND. -
ACTION SHEET NO. -	TYPE OF TEST Accept Test	NAME OF TEST BARE	NAME OF TEST S. Mehmed			

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	JOJOIN	MICKET	16	7 42
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
MEHMED	GEIB	RAE-B	4-14-72	1120



INPUT LEVEL	EXCIT. AXIS
1	1
ACCEL S/N	SENSING AXIS
TD46	X
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
	2.805
FILTER	
10/100/200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO. SWEEP RATE	
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	<input checked="" type="checkbox"/> CONTROL
TEMP. 74	<input type="checkbox"/> RESPONSE
LOCATION	
AIX AIX	
SPECIAL CONDITIONS	
HOOK-UP #3	
MASTER PG 1774	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SVSK79594	-	-	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7	-	BARE	SINUSOIDAL SCAN


SINE VIBRATION TEST

RIG	26	OPERATOR	WODDIN	PROJECT	RAE-B	PLOTTED BY	MICKET	TRACE NO.	18	TEST NO.	7
TEST ENGINEER	MEHMED	CHECKED BY	GEIB			DATE	4-14-72	TIME	1120		

INPUT LEVEL	EXCIT. AXIS
1	8
ACCEL S/N	SENSING AXIS
7044	X
ACCEL SENSITIVITY	
—	MV RMS
2.773	GP
	COL
	GP
FILTER	
10/100/200	HZ B.W.
FILTER CROSSOVER	
@ 70 - 700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 OF	RESPONSE
LOCATION	
A2X	A2X

HOOK-UP #3
SPECIAL CONDITIONS
MASTER PG 1774

REPORT NO.




FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000 Hz	515K79594	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
			RAE-B	

SINE VIBRATION TEST

Standard A[®]

HSF 1633 A 269

RIG	26	OPERATOR	WDDOIN	PROJECT	RAE-B	PLOTTED BY	MICKET	TRACE NO.	20	TEST NO.	7
TEST ENGINEER	MEHMED	CHECKED BY	GEIB			DATE	4-14-72	TIME	1120		




INPUT LEVEL	EXCIT. AXIS
1	X
ACCEL S/N	SENSING AXIS
VR11	X
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
	2.956
FILTER	
	10/100/200
FILTER CROSSOVER	HZ B.W.
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012394	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	- HZ TO - DB/SEC
CHG@	- HZ TO - DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
A4X	A4X
	HOOK-UP #3
	SPECIAL CONDITIONS
	MASTER PG 1774

REPORT NO.

FREQ. RANGE & DIRECTION	5-2000HZ	ITEM	SVSK	CODE		SERIAL NO.		TYPE OF TEST	FIXTURE SURVEY
SPECIFICATION	AT-VCPS	PARA.	4.3.7	AMEND.		PHASE	BALE	NAME OF TEST	SINUSOIDAL SCAN

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PROJECT	RAE-B	PLOTTED BY	MICKET	TRACE NO.	21	TEST NO.	7
TEST ENGINEER	MEHMED.	CHECKED BY	GEIB			DATE	4-14-72	TIME			1120



INPUT LEVEL	EXCIT. AXIS
+	X
ACCEL S/N	SENSING AXIS
VG-57	X
ACCEL SENSITIVITY	
10.886	
	MV RMS
	GP
	COL
	GP
FILTER	
10/100/200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER/EEL NO.	SWEEP RATE
013294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 OF	RESPONSE
LOCATION	
ASX	ASX

SPECIAL CONDITIONS
HOOK-UP #3
MASTER # 1774

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SVSK7594			FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
			RAE	


**Hamilton
Standard**

SINE VIBRATION TEST

HSF 1633 A 2/69


RIG	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	DDOIN	GEI'B	MICKET	15	7
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME	
MEHMED	GEI'B	RAE-B			

INPUT LEVEL + 1	EXCIT. AXIS X
ACCEL S/N NB62	SENSING AXIS Z
ACCEL SENSITIVITY	
MV RMS —	
GP 2.698	
COL —	
GP —	
FILTER	
10/100/200 HZ B.W.	
FILTER CROSSOVER	
@ 70 - 700	HZ
TAPEREEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR DB/SEC	
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO — DB/SEC	
NON- OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
A1Z A1Z	
BOOK-UP # 3	
SPECIAL CONDITIONS	
MASTER PG. 1774	



SINE VIBRATION TEST

RIG	26	OPERATOR	JDDOIN	PROJECT	RAE-B	PLOTTED BY	MICKET	TRACE NO.	19	TEST NO.	75
TEST ENGINEER	MEHMED	CHECKED BY	GEIB					DATE	4-14-72	TIME	1120



INPUT LEVEL EXCIT. AXIS	1	8	X
ACCEL S/N	7675	SENSING AXIS	7675
ACCEL SENSITIVITY	—	MV RMS	—
	2.791	GP	—
		COL	—
		GP	—
FILTER	10/100/200	HZ B.W.	—
FILTER Crossover	70 - 700	HZ	—
TAPE REEL NO.	012294	SWEEP RATE	4 OCT/MIN
COMPR. SPEED	VAR	DB/SEC	—
CHG@	—	HZ TO	DB/SEC
CHG@	—	HZ TO	DB/SEC
NON-OPERATING	<input type="checkbox"/>	CONTROL	—
TEMP.	74	°F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	A3Z	A3Z	—
SPECIAL CONDITIONS			
BOOK-UP #3			
MASTER PG-1774			

REPORT NO.	
------------	--


FREQ. RANGE & DIRECTION	5-2000HZ	ITEM	SVSK	CODE	—	SERIAL NO.	—	TYPE OF TEST	FIXTURE SURVEY
SPECIFICATION	AT-VCPS	PARA.	4.3.7	AMEND.	—	PHASE	FIXTURE	NAME OF TEST	SINUSOIDAL SCAN

SINE VIBRATION TEST

HSF-1639.1 2/69


RIG NO. 26	OPERATOR JO DOIN	WITNESS 4-15-72	TEST NO. 2
TEST ENGINEER MEHMED	CHECKED BY GEIB	PROJECT RAE-B	DATE 4-15-72
		WITNESS A. W. Carthy	TIME 1410

INPUT LEVEL 1	EXCIT. AXIS X
ACCEL S/N 7040	SENSING AXIS X
ACCEL SENSITIVITY 2.805	MV RMS GP
	GP GP
FILTER 100-200	HZ B.W. 100-200
FILTER CROSSOVER 700	HZ 700
SWEEP RATE 4	OCT/MIN 4
TAPEREEL NO. 012295	LIVE FROM TAPE <input checked="" type="checkbox"/>
COMPR. SPEED VAR	DB/SEC. VAR
CHG. @ - HZ TO VAR	DB/SEC. VAR
CHG. @ - HZ TO VAR	DB/SEC. VAR
NON OPERATING <input checked="" type="checkbox"/>	CONTROL <input checked="" type="checkbox"/>
TEMP. 74 °F	RESPONSE <input type="checkbox"/>
LOCATION AIX	
SPECIAL CONDITIONS. HOOK-UP #1	
ITEM LOADED AND PRESSURIZED.	
REPORT NO.	



FREQ. RANGE & DIRECTION 200-2000 Hz VCPS	ITEM VCPS	CODE SV 748720-1	SERIAL NO. SH 00001	SPEC. AT-VCPS	PARA. 4.3.7	AMEND. —
ACTION SHEET NO.	ATA NO.	NAME OF TEST FI XTURE / VCPS SURVEY LOW / FUEL CILINDERS				
SCAN						

RIG	26	MEHMED	OPERATOR	JODDIN	WITNESS	* A. McCarthy 4/15/74	WITNESS	
TEST ENGINEER	GEIB		CHECKED BY	RAE-B	PROJECT		DATE	4-15-72
							TIME	1420
							TEST NO.	3




INPUT LEVEL	7.5	EXCIT. AXIS	X
ACCEL S/N	TD40	SENSING AXIS	X
ACCEL SENSITIVITY	2.805	MV RMS	GP
		GP	GP
FILTER	-100-200	HZ B.W.	
FILTER Crossover	700	HZ	
SWEEP RATE	4.0	OCT/MIN	
TAPER REEL NO.	012295	LIVE FROM TAPE	
COMPR. SPEED	Var	DB/SEC.	
CHG. @	~	HZ TO ~	DB/SEC.
CHG. @	~	HZ TO ~	DB/SEC.
NON OPERATING	<input checked="" type="checkbox"/>	CONTROL	
TEMP.	73	°F	RESPONSE
LOCATION	AIX'		
SPECIAL CONDITIONS			
Hook-up #1			
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY			
VCPS LOADED		PRESSURIZED	

FREQ. RANGE & DIRECTION	200-2000 Hz	ITEM	VCPS	CODE SV	748720-1	SERIAL NO.	00001	SPEC.	AT-VCPS	PARA.	4.3.7.5	AMEND.	NOTE 2
ACTION SHEET NO.	-	ATA NO.	-	TYPE OF TEST		QUAL - VCPS ONLY		NAME OF TEST		SINUSOIDAL VIBRATION			

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	JODOIN	JODOIN	1	3
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
MEH MED	GEIB	RAE-B	4-15-72	1420




INPUT LEVEL	EXCIT. AXIS
± 7.5	X
ACCEL S/N	SENSING AXIS
TD40	X
ACCEL SENSITIVITY	
—	MV RMS
2.805	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER Crossover	
@ 700	HZ
TAPE REEL NO.	SWEEP RATE
012395	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	CONTROL
TEMP. 73 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
AIX'	
HOOX-UP #1	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	
THIS PORTION	
OF THE TEST	
PERFORMED WITH	
THE VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000HZ	NCS	SV	00001	QUAL -
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST

HSF 1633 A 2/69


RIG 26	OPERATOR JODOIN	PROJECT RAE-B	PLOTTED BY JODOIN	TRACE NO. 3	TEST NO. 3
TEST ENGINEER MEHMED	CHECKED BY GEIB		DATE 4-15-72	TIME 1420	



INPUT LEVEL 7.5	EXCIT. AXIS X
ACCEL S/N XM21	SENSING AXIS X
ACCEL SENSITIVITY 1.370	
MV RMS GP	
COL GP	
GP	
FILTER 100/200	
HZ B.W. 700	
TAPER EEL NO. SWEEP RATE 012295 4	
OCT/MIN	
COMPR. SPEED VAR	
DB/SEC	
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING TEMP. 73	CONTROL <input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE
LOCATION DX	
REA MOUNT H00K-UP #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION 200-2000 HZ	ITEM VCPS	CODE SV 748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION 200-2000 HZ	PARA. VCPS	AMEND.	PHASE VCPS	NAME OF TEST


RIG	26	OPERATOR	JODDIN'	PLOTTED BY	JODDIN	TRACE NO.	4	TEST NO.	3
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-15-72	TIME	1420



INPUT LEVEL ± 7.5	EXCIT. AXIS X
ACCEL S/N WF75	SENSING AXIS X
ACCEL SENSITIVITY MV RMS GP COL GP 1.051	
FILTER 100/200 HZ B.W. FILTER CROSSOVER @ 700 HZ TAPE REEL NO. SWEEP RATE 012295 4 OCT/MIN COMPR. SPEED YAR DB/SEC CHG@ - HZ TO - DB/SEC CHG@ - HZ TO - DB/SEC	
NON-OPERATING TEMP. 73 °F	CONTROL <input type="checkbox"/> RESPONSE <input checked="" type="checkbox"/>
LOCATION EX	
TANK MOUNT HOOK-UP #/ SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200-2000Hz	VCP'S	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCP'S	4.3.7.5	NOTE 2	VCP'S ONLY	SINUSOIDAL VIBRATION

RIG	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODOIN	RAE-B	JODOIN	2	3
TEST ENGINEER	CHECKED BY		DATE		TIME
MEHME	GEI/B		4-15-72		1420



INPUT LEVEL	EXCIT. AXIS	
7.5	X	
ACCEL S/N	SENSING AXIS	
7E83	Y	
ACCEL SENSITIVITY		
	MV RMS	
	GP	
	COL	
	GP	
2.722		
FILTER		
100/200	HZ B.W.	
FILTER CROSSOVER		
@ 700	HZ	
TAPE REEL NO.	SWEEP RATE	
012295	4 OCT/MIN	
COMPR. SPEED		
VAR	DB/SEC	
CHG@ - HZ TO -	DB/SEC	
CHG@ - HZ TO -	DB/SEC	
NON-OPERATING	CONTROL	
TEMP. 73 °F	RESPONSE	
LOCATION		
AIY		
SPECIAL CONDITIONS		
VCPS LOADED		
AND PRESSURIZED		
THIS PORTION OF THE TEST PERFORMED WITH VCPS ONLY		
REPORT NO.		

FREQ. RANGE & DIRECTION	ITEM	CODE	SV	SERIAL NO.	TYPE OF TEST
200-2000Hz	VCPS	748720-1	00001	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST	


SINE VIBRATION TEST

Standard A[®]

Standard

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	9	TEST NO.	3
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-R	DATE	4-15-72	TIME	1420




INPUT LEVEL	EXCIT. AXIS	± 7.5	X
ACCEL S/N	SENSING AXIS	WR11	Y
ACCEL SENSITIVITY	MV RMS	3.016	
	GP		
	COL		
	GP		
FILTER	HZ B.W.	100/200	
FILTER Crossover	HZ	700	
TAPER REEL NO.	SWEEP RATE	012295	4 OCT/MIN
COMPR. SPEED	VAR		DB/SEC
CHG@	- HZ TO -		DB/SEC
CHG@	- HZ TO -		DB/SEC
NON-OPERATING	CONTROL		
TEMP. 73 °F	RESPONSE		
LOCATION	BY		
	HUB		
	HOOK-UP #1		
	SPECIAL CONDITIONS		
	VCPS LOADED AND PRESSURIZED		
	THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY		
	REPORT NO.		

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000Hz	VCPS	SV	748720-1	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.1.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	MEHMET	RAE-13	JODDIN	6	3
CHECKED BY			DATE	TIME		
GEIB			4-15-72	1420		




INPUT LEVEL	EXCIT. AXIS
+ 7.5	X
ACCEL S/N	SENSING AXIS
YK20	Y
ACCEL SENSITIVITY	
1.523	MV RMS
	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 73 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
REA MOUNT	
HOCK-UP #1	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH VCPS ONLY	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SY	SERIAL NO.	FREQUENCY HZ	TYPE OF TEST
200-2000 HZ	VCPS	748720-1		00001	100	QUAL
SPECIFICATION	PARA.	AMEND.		PHASE		NAME OF TEST

SINE VIBRATION TEST

RIG	OPERATOR	TEST ENGINEER	CHECKED BY	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODOIN	MEHMEB	GEIB	RAE-B	JODOIN	7	3
				DATE	TIME		
				4-15-72	1420		




INPUT LEVEL	EXCIT. AXIS
7.5	X
ACCEL S/N	SENSING AXIS
XV32	Y
ACCEL SENSITIVITY	
1.261	MV RMS
	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER Crossover	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 73 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
EY	
TANK MOUNT	
HOOK-UP #1	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	
THIS PORTION	
OF THE TEST	
PERFORMED WITH	
VCPS ONLY	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION


HSF 1633 A 2/69

RIG	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	RAE-8	JODDIN	5	3
TEST ENGINEER	CHECKED BY			DATE	TIME
MEHMET	GEIB			4-15-72	1420



FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000HZ	VCPS	SV	748720-1	QUAL
SPECIFICATION	PARA.	AMND.	PHASE	NAME OF TEST

RIG	TEST ENGINEER	OPERATOR	WITNESS	WITNESS	TEST NO.
26	MEHMET	MICKET/00000IN	—	M. Quinlan	11
		CHECKED BY	PROJECT	DATE	TIME
		GEIB	RAE-B	4-18-72	0715




INPUT LEVEL	EXCIT. AXIS	1.5	X
ACCEL S/N	SENSING AXIS	TD40	X
ACCEL SENSITIVITY	MV RMS	—	GP
	GP	2.80S	COL
	GP		GP
FILTER	10-100-	HZ B.W.	
FILTER Crossover	@ 70-	HZ	
Sweep Rate	4	OCT/MIN	
TAPER REEL NO.	<input checked="" type="checkbox"/> LIVE		
012295	<input type="checkbox"/> FROM TAPE		
COMPR. SPEED	VAR	DB/SEC.	
CHG. @	- HZ TO - DB/SEC.		
CHG. @	- HZ TO - DB/SEC.		
NON OPERATING	<input checked="" type="checkbox"/> CONTROL		
TEMP. 74	<input type="checkbox"/> RESPONSE		
LOCATION	AIX'		
HOOK-UP #1			
SPECIAL CONDITIONS			
VCPS 10000 + PRESENTED			
H4 #1			
SPEC MODIFIED			
BETWEEN 5-14/72			
BY MIKE CALABRESE			
PROJECT WAS			
COGNIZANT			
REPORT NO.			

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	SPEC.	PARA.	AMEND.
5-2000Hz	VCPS	748720-1	00001	AT-VCPS	43.7.5	NOTE 1 & 3
ACTION SHEET NO.	ATA NO.	TYPE OF TEST	NAME OF TEST			
—	—	QUAL	SINUSOIDAL VIB			

HSF 1633 A 469


RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	JODOIN	JODOIN	30	11
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
MEHMET	GEIB	RAE-B	4-18-72	0715



INPUT LEVEL	EXCIT. AXIS
± 1.5	X
ACCEL S/N	SENSING AXIS
7040	X
ACCEL SENSITIVITY	
—	MV RMS
—	GP
2.805	COL
—	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ —	HZ TO — DB/SEC
CHG@ —	HZ TO — DB/SEC
NON-OPERATING	<input checked="" type="checkbox"/> CONTROL
TEMP. 74 °F	<input type="checkbox"/> RESPONSE
LOCATION	
AIX	
HOOK-UP #1	
SPECIAL CONDITIONS	
SPECIFICATION MODIFIED BETWEEN 5-14 HZ.	
COMPLETE PACKAGE.	
VCPS LOADED AND PRESSURIZED.	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-200 HZ	RAE-B	SV	748720-1	QUAL
SPECIFICATION	AMEND.	PHASE	VCPS	NAME OF TEST

RIG	26	OPERATOR	JO DOIN	PLOTTED BY	JO DOIN	TRACE NO.	39	TEST NO.	11
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-18-72	TIME	0715




INPUT LEVEL	EXCIT. AXIS	± 1.5	X
ACCEL S/N	SENSING AXIS	TD 44	X
ACCEL SENSITIVITY		3.035	
	MV RMS		
	GP		
	COL		
	GP		
FILTER		10/100	HZ B.W.
FILTER Crossover		70	HZ
TAPER REEL NO.	SWEEP RATE	012295	4 OCT/MIN
COMPR. SPEED		VAR	DB/SEC
CHG@	- HZ TO -		DB/SEC
CHG@	- HZ TO -		DB/SEC
NON-OPERATING	CONTROL		
TEMP. 74 °F	RESPONSE		
LOCATION		3X	
		HUB	
		HOOK-UP #1	
		SPECIAL CONDITIONS	
		SPECIFICATION MODIFIED	
		BETWEEN 5-14HZ	
		COMPLETE PACKAGE	
		VCPS LOADED AND	
		PRESSURIZED	
		REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM-B	CODE SV	SERIAL NO.	TYPE OF TEST
5-200 HZ	RAE-B	748720-1	00001	QUAL
SPECIFICATION	VCPS	AMEND.	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 1 & 3	AND SPACECRAFT	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODOIN	PLOTTED BY	JODOIN	TRACE NO.	34	TEST NO.	11
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	RAED	DATE	4-18-72	TIME	0715




INPUT LEVEL	EXCIT. AXIS
± 1.5	X
ACCEL S/N	SENSING AXIS
7045	X
ACCEL SENSITIVITY	
—	MV RMS
—	GP
2.650	COL
—	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ —	HZ TO — DB/SEC
CHG@ —	HZ TO — DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
CX	
SPACECRAFT C.G.	
HOOK-UP #1	
SPECIAL CONDITIONS	
SPECIFICATION MODIFIED	
BETWEEN 5-14 Hz	
COMPLETE PACKAGE	
VCPS LOADED AND PRESSURIZED	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
5-2000 Hz	RAED	748720-1	00001	QUAL
SPECIFICATION	VCPS	AMEND.	PHASE VCPS	NAME OF TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDOIN	PROJECT	RAED	TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PLOTTED BY	JODDOIN	TRACE NO.	32	TEST NO.	11
										DATE	4-18-72	TIME	0715		




INPUT LEVEL	EXCIT. AXIS	
+ 1.5	X	
ACCEL S/N	SENSING AXIS	
XM21	X	
ACCEL SENSITIVITY		
	MV RMS	
	GP	
	COL	
	GP	
	1.370	
FILTER		
10/100	HZ B.W.	
FILTER Crossover		
@ 70	HZ	
TAPER REEL NO.	SWEEP RATE	
012295	4	OCT/MIN
COMPR. SPEED		
VAR	DB/SEC	
CHG@ -	HZ TO -	DB/SEC
CHG@ -	HZ TO -	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL	
TEMP. 74	<input checked="" type="checkbox"/> RESPONSE	
LOCATION	DX	
REA MOUNT HOOK-UP#1		
SPECIAL CONDITIONS SPECIFICATION MODIFIED BETWEEN 5-14HZ		
COMPLETE PACKAGE. VCPS LOADED AND PRESSURIZED.		
REPORT NO.		

FREQ. RANGE & DIRECTION	ITEM-0	CODE SV	SERIAL NO.	TYPE OF TEST
5-2000HZ	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 1 & 3	AND SPACECRAFT	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	33	TEST NO.	11
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	DAF-B	DATE	4-18-72	TIME	0715




INPUT LEVEL + 1.5	EXCIT. AXIS X
ACCEL S/N WF75	SENSING AXIS X
ACCEL SENSITIVITY 1.051	MV RMS GP COL GP
FILTER 10/100	HZ B.W.
FILTER Crossover @ 70	HZ
TAPER REEL NO. 012295	SWEEP RATE 4 OCT/MIN
COMPR. SPEED VAR	DB/SEC
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING TEMP. 74 °F	CONTROL <input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE
LOCATION EX	
TANK MOUNT HOOK-UP #1 SPECIAL CONDITIONS SPECIFICATION MODIFIED BETWEEN S-14H	
COMPLETE PACKAGE. VCPS LOADED AND PRESSURIZED.	

REPORT NO.

FREQ. RANGE & DIRECTION 5-200 HZ	ITEM DAF-B	CODE SV 748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION	PARA.	AMEND.	PHASE VIB PC	NAME OF TEST

RIG	OPERATOR	TEST ENGINEER	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	MEHMET	MEHMET	RAE-B	JODDIN	31	11
CHECKED BY			DATE	TIME		
G E I B			4-18-72	0715		



INPUT LEVEL	EXCIT. AXIS	ACCEL S/N	SENSING AXIS
+ 1.5	X		
ACCEL S/N	7E83	Y	
ACCEL SENSITIVITY	MV RMS		
	GP	GP	
	2.722	GP	
FILTER	10/100	HZ B.W.	
FILTER Crossover	70	HZ	
TAPER REEL NO.	SWEEP RATE		
012295	4	OCT/MIN	
COMPR. SPEED	VAR	DB/SEC	
CHG@	— HZ TO —	DB/SEC	
CHG@	— HZ TO —	DB/SEC	
NON-OPERATING	<input type="checkbox"/> CONTROL		
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE		
LOCATION	AIY		
HOOK-UP #1			
SPECIAL CONDITIONS			
SPECIFICATION MODIFIED BETWEEN 5-14HZ			
COMPLETE PACKAGE			
VCPS LOADED AND PRESSURIZED			
REPORT NO.			


FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-200HZ	RAE-B	SV	00001	QUAL
SPECIFICATION	VCPS	AMEND.	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 1 & 3	AND SPACECRAFT	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	TEST ENGINEER	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
MEHMET	26	JODOIN	RAED	JODOIN	40	11
					DATE	TIME
					4-18-72	0715

INPUT LEVEL	EXCIT. AXIS
+ 1.5	X
ACCEL S/N	SENSING AXIS
WR11	Y
ACCEL SENSITIVITY	
3.016	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 OF	RESPONSE
LOCATION	
BY	
HUB	
HOOK-UP #1	
SPECIAL CONDITIONS	
SPECIFICATION MODIFIED	
BETWEEN 5-14HZ	
COMPLETE PKG.	
VCPS LOADED AND	
PRESSURIZED	
REPORT NO.	




FREQ. RANGE & DIRECTION	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SY	00001	QUAL
SPECIFICATION	AMEND.	PHASE	NAME OF TEST
PARA.		V.C.P.C	

SINE VIBRATION TEST

Standard A®

HSF 1633A 2/69

RIG	OPERATOR	TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-R	PLOTTED BY	JODOIN	TRACE NO.	35	TEST NO.	11
								DATE	4-18-72			TIME	0715




INPUT LEVEL	EXCIT. AXIS	± 1.5	X
ACCEL S/N	SENSING AXIS	TD48	Y
ACCEL SENSITIVITY			
	MV RMS		
	GP		
	COL		
	GP		
		2.788	
FILTER		10/100	HZ B.W.
FILTER Crossover		@ 70	HZ
TAPER REEL NO.	SWEEP RATE	012295	4 OCT/MIN
COMPR. SPEED		VAR	DB/SEC
CHG@	HZ TO	DB/SEC	
CHG@	HZ TO	DB/SEC	
NON-OPERATING	CONTROL	<input type="checkbox"/>	
TEMP. 74	RESPONSE	<input checked="" type="checkbox"/>	
LOCATION		CY	
		SPACECRAFT C.G.	
		HOOK-UP #1	
		SPECIAL CONDITIONS	
		SPECIFICATION MODIFIED	
		BETWEEN 5-1447	
		COMPLETE PKG	
		VCPS LOADED AND	
		PRESSURIZED	
		REPORT NO.	

FREQ. RANGE & DIRECTION	5-2000HZ	CODE SV	748720-1	SERIAL NO.	00001	TYPE OF TEST	QUAL
SPECIFICATION	AT-VCPS	AMEND.	NOTE 1 & 3	PHASE VCPS	AND SPACECRAFT	NAME OF TEST	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	26	OPERATOR	JODOIN	PROJECT	JODOIN	PLOTTED BY	JODOIN	TRACE NO.	37	TEST NO.	11
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	WELB	DATE	4-18-72	TIME	0715		



INPUT LEVEL	EXCIT. AXIS	± 1.5	X
ACCEL S/N	SENSING AXIS	Y/K20	Y
ACCEL SENSITIVITY	MV RMS	1.523	
	GP		
	COL		
	GP		
FILTER	10/100	HZ B.W.	
FILTER CROSSOVER	@ 70	HZ	
TAPE REEL NO.	SWEEP RATE	012295	4 OCT/MIN
COMPR. SPEED	VAR		DB/SEC
CHG@	HZ TO		DB/SEC
CHG@	HZ TO		DB/SEC
NON-OPERATING	CONTROL		
TEMP. 74 °F	RESPONSE		
LOCATION	DY		
REA MOUNT			
HOOK-UP #1			
SPECIAL CONDITIONS			
SPECIFICATION MODIFIED			
BETWEEN 5-14HZ			
COMPLETE PKG			
VCPS LOADED			
AND PRESSURIZED			
REPORT NO.			


FREQ. RANGE & DIRECTION	5-200 HZ	CODE SV	748720-1	SERIAL NO.	00001	TYPE OF TEST	QUAL
SPECIFICATION		AMEND.		PHASE	VCPS	NAME OF TEST	

SINE VIBRATION TEST

Standard A®

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	33	TEST NO.	11
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT		DATE	4-18-72	TIME	0715




INPUT LEVEL	± 1.5	EXCIT. AXIS	X
ACCEL S/N	XN32	SENSING AXIS	Y
ACCEL SENSITIVITY	1.261	MV RMS	
		GP	
		COL	
		GP	
FILTER	10/100	HZ B.W.	
FILTER Crossover	@ -70	HZ	
TAPER REEL NO.	012295	SWEEP RATE	4 OCT/MIN
COMPR. SPEED	VAR	DB/SEC	
CHG@	-	HZ TO	DB/SEC
CHG@	-	HZ TO	DB/SEC
NON-OPERATING		CONTROL	<input type="checkbox"/>
TEMP.	74 °F	RESPONSE	<input checked="" type="checkbox"/>
LOCATION	EY		
TANK MOUNT	HOO-K-UP #1		
SPECIAL CONDITIONS	SPECIFICATION MODIFIED BETWEEN 5-14HZ		
COMPLETE PKG.	VCPS LOADED AND PRESSURIZED		
REPORT NO.			

FREQ. RANGE & DIRECTION	ITEM-C	CODE SV	SERIAL NO.	TYPE OF TEST
5-200HZ	VCPS	748720-1	00001	1.26GPK QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 3	VCPS	SINUSOIDAL VIBRATION
			AND SPACECRAFT	

1.0

C55 106<

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	36	TEST NO.	11
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	PLB	DATE	4-18-72	TIME	0715



INPUT LEVEL	EXCIT. AXIS
+ 1.5	X
ACCEL S/N	SENSING AXIS
NB62	Z
ACCEL SENSITIVITY	
3.052	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPE REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION	
AIZ	
SPECIAL CONDITIONS	
SPECIFICATION MODIFIED BETWEEN 5-14 Hz	
COMPLETE PKG	
VCPS LOADED AND PRESSURIZED	

FREQ. RANGE & DIRECTION	CODE SV	SERIAL NO.	TYPE OF TEST
5-2000 Hz	748720-1	00001	QUAL
SPECIFICATION	AMEND.	PHASE VCPS	NAME OF TEST

RANDOM VIBRATION TEST ANALYSIS METHOD A


PLOTTED BY MICKET	CHECKED BY GEIB	TEST ENGINEER MEHMED	RIG NO. 26	WITNESS M. C. Rine L.
PROJECT RAE-B	ITEM VCP S	CODE SV748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPEC. AT-VCP S	PARA. 4.3.7.5	PHASE COMPLETE PKG RANDOM VIB	ATA NO. —	DATE 4-18-72
ACTION SHEET NO. —				
TEST NO. 10				

Nominal Input Level

EXCITATION ALONG AXIS X	GRMS INPUT 9.2	NON-OPERATING	TEMP. 74 °F	PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	DURATION OF TEST 2.0 MIN.	ACCEL. SERIAL NO. TD40	ACCEL. SENSITIVITY — MV RMS / GP	ACCEL. SENSING X	ACCEL. LOCATION AIX'	TAPER REEL NO. HOO-KUP #1	SPECIAL CONDITIONS VCPS LOADED	REPORT NO.
										012295	EXPRESSORIZED	Note #1 + 4 ATedels

PAGE NO.
FREQUENCY HZ

RIG 26	OPERATOR B. M.	PLOTTED BY S. M.	TRACE NO. 13	TEST NO. 10
TEST ENGINEER S. M.		CHECKED BY T. G.	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER T040	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY MV RMS 2.805 GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 11.23 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input checked="" type="checkbox"/> CONTROL <input type="checkbox"/> RESPONSE	
PICKUP LOCATION AIX	
Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4, 3, 7, 5	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	PAGE NO.


**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**
HSF-1635 B

REPORT NO.


RIG 26	OPERATOR MICKET	PLOTTED BY MEHMED	TRACE NO. 22	TEST NO. 10
TEST ENGINEER MEHMED.		CHECKED BY GEIB	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER TD44	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY 3.035 MV RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 	
TIME CONSTANT - SEC 	
ANAL. CALIBRATION 108.26 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION Bx HUB HOOK-UP #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SY 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. NOTE 1 & 4	PHASE VCPS AND SPACECRAFT	PAGE NO.

RIG 26	OPERATOR B. M.	PLOTTED BY S. M.	TRACE NO. 17	TEST NO. 10
TEST ENGINEER S. M.		CHECKED BY T. G.	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER 7045	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY —	MV RMS GP
2.650	COL GP
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN —	
TIME CONSTANT - SEC —	
ANAL. CALIBRATION 1.398 g^2 HZ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION CX	
SPACECRAFT C.G. Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	PAGE NO.


Hamilton
Standard

U
A
DIVISION OF UNITED AIRCRAFT CORPORATION

RANDOM VIBRATION TEST
ANALYSIS METHOD B
HSF-1635 B

REPORT NO.

RIG 26	OPERATOR B.M.	PLOTTED BY S.M.	TRACE NO. 15	TEST NO. 10
TEST ENGINEER S.M.	CHECKED BY T.G.	DATE 4-18-72	TIME 0650	




INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER XM21	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY MV RMS GP 1.370 COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 47.08 g^2 F.S. HZ	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 OF
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION DX REA MOUNT HOOK-UP #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. NOTE 154	PHASE AND SPACECRAFT VCPS	RANDOM PAGE NO.

142<

061

RIG 26	OPERATOR B. M.	PLOTTED BY S. M.	TRACE NO. 16	TEST NO. 10
TEST ENGINEER S. M.		CHECKED BY T. G.	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER WF75	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY — MV RMS GP 1.051 COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN —	
TIME CONSTANT - SEC —	
ANAL. CALIBRATION 80.01 g^2 F.S. HZ	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION EX TANK MOUNT Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 746720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. 1 & 4	NOTE VCPS AND SPACECRAFT	PAGE NO.

**Hamilton
Standard**


**U
A[®]**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.


RIG 26	OPERATOR B.M	PLOTTED BY S.M	TRACE NO. 14	TEST NO. 10
TEST ENGINEER S.M		CHECKED BY T.G	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER TE 83	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY MV RMS 2.722 GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN. 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 11.92 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION AIY	
Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	RANDOM —
				PAGE NO.

RIG 26	OPERATOR B. M.	PLOTTED BY S. M.	TRACE NO. 18	TEST NO. 10
TEST ENGINEER S. M.		CHECKED BY T. G.	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER TD48	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 2.788 MV RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 1.263 g^2 F.S. HZ	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 OF
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION CY	
SPACECRAFT C.G. HOOK UP #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 74872-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. 154	PHASE VCPS AND SPACECRAFT	PAGE NO.


Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A₀

RANDOM VIBRATION TEST
ANALYSIS METHOD B
HSF-1635 B

REPORT NO.

RIG 26	OPERATOR B.M.	PLOTTED BY S.M.	TRACE NO. 20	TEST NO. 10
TEST ENGINEER S.M.	CHECKED BY T.G.	DATE 4-18-72	TIME 0650	




INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER YK20	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 1.523 MV RMS	
GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 429.9 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION DY REA MOUNT Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SY 74872-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. 154 NOTE	PHASE VCPS AND SPACECRAFT	PAGE NO.

146<

HSF-1635 B

RIG 26	OPERATOR B. M	PLOTTED BY S. M	TRACE NO. 21	TEST NO. 10
TEST ENGINEER S. M		CHECKED BY T. G	DATE 4-18-72	TIME 0650

SPECTRAL DENSITY G^2/Hz 

INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER XN32	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 1.261 MV RMS GP	COL GP
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN —	
TIME CONSTANT - SEC —	
ANAL. CALIBRATION 627.1 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION EY TANK MOUNT Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SY 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. 1 & 4	NOTE VCPS AND SPACECRAFT	PAGE NO.

**Hamilton
Standard**


U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.

RIG 26	OPERATOR B. M	PLOTTED BY S. M	TRACE NO. 19	TEST NO. 10
TEST ENGINEER S. M		CHECKED BY T. G.	DATE 4-18-72	TIME 0650



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS X	
ACCEL SERIAL NUMBER NB62	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 3.052	MV RMS GP COL GP
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN. 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 107.06 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION A12	
Hook-up #1	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7.5	AMEND. 1 & 4	PHASE VCPS AND SPACECRAFT	PAGE NO. —

148<

067


Section III

Y - Axis

A) Sine Data

B) Random Data

RIG #26	OPERATOR P. Jodoin	WITNESS —	TEST NO. 5
TEST ENGINEER S. Mehnert	CHECKED BY GEIB	PROJECT RAE-B	DATE 4-13-72
			TIME 1540




INPUT LEVEL EXCIT. AXIS 1.0	ACCEL S/N TE83	ACCEL SENSITIVITY —	ACCEL SENSITIVITY MV RMS GP COL. GP
2722			
FILTER 10-100-200	FILTER CROSSOVER @ 70.700	SWEPT RATE 4.0	QCT/MIN LIVE FROM TAPE
			COMPR. SPEED Var
			DB/SEC. CHG. @ ~ HZ TO ~ DB/SEC.
			CHG. @ ~ HZ TO ~ DB/SEC.
			NON OPERATING <input checked="" type="checkbox"/> CONTROL
			TEMP. 74 °F RESPONSE
			LOCATION
SPECIAL CONDITIONS A1Y Hook-up #2 Bare Fixture MASTER PG-1774			
REPORT NO.			

FREQ. RANGE & DIRECTION 5-2K Hz	ITEM SVSK79594	CODE VCP S-FIXT	SERIAL NO. SVSK79594	SPEC. AT-VCPS	PARA. 4.3.7	AMEND.
ACTION SHEET NO.	ATA NO.	TYPE OF TEST Accept Test	NAME OF TEST Sine Scan			

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG 26	OPERATOR JODDIN	TEST ENGINEER MEHMER	PLOTTED BY MICKET	TRACE NO. 10	TEST NO. CH3
CHECKED BY GEIB			PROJECT RAE-B	DATE 4-13-72	TIME 1540



INPUT LEVEL +	EXCIT. AXIS Y
ACCEL S/N TE83	SENSING AXIS Y
ACCEL SENSITIVITY	
MV RMS	
GP	
COL	
GP	
2.1722	
FILTER	
10-100-200 HZ B.W.	
FILTER Crossover	
70-700 HZ	
TAPER REEL NO. SWEEP RATE	
012294 4 OCT/MIN	
COMPR. SPEED	
VAR DB/SEC	
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING	
CONTROL	
TEMP. 74 °F	
RESPONSE	
LOCATION	
A1Y A1Y	

SPECIAL CONDITIONS
HOCK-UP #2
7WAY FROM SHAWER
HEAD. REFERENCE LOG
SHEET 1774.


REPORT NO. MASTER # 1774

FREQ. RANGE & DIRECTION 5-2000 HZ	ITEM JYK79594	CODE —	SERIAL NO. —	TYPE OF TEST FIXTURE SURVEY	NAME OF TEST RAE
SPECIFICATION		AMEND.	PHASE	DATE	

SINE VIBRATION TEST

Standard **A[®]** DIVISION OF UNITED AIRCRAFT

TRIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	11	TEST NO.	5
TEST ENGINEER	MEHMET	CHECKED BY	G-EIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1540



INPUT LEVEL + 1	EXCIT. AXIS Y
ACCEL.'S/N T044	SENSING AXIS Y
ACCEL SENSITIVITY	
MV RMS GP	
COL GP	
2.773	
FILTER	
10 ~ 100 ~ 200 HZ B.W.	
FILTER CROSSOVER	
@ 70 ~ 700 HZ	
TAPEREEL NO. SWEEP RATE	
012294	4 OCT/MIN
COMPR. SPEED	
VAR DB/SEC	
CHG@ ~ HZ TO ~ DB/SEC	
CHG@ ~ HZ TO ~ DB/SEC	
NON-OPERATING	
TEMP. 74 °F	
LOCATION A3Y	
CONTROL <input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
A2Y	
hook-up #2	
SPECIAL CONDITIONS	
CLOSEST TO DRIVER	

REPORT NO.


MASTER PG 1774

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	FREQUENCY Hz	TYPE OF TEST
5-2000 Hz	SYSC 79594	—	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.			
AT-1CPS	4 3.7	—	—	—	FIXTURE SURVEY

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PROJECT	RAE-B	TRACE NO.	13	TEST NO.	5
TEST ENGINEER	MEHMED	CHECKED BY	GEIB		RAE-B	DATE	4-13-72	TIME	1540



INPUT LEVEL	EXCIT. AXIS	+	1	Y
ACCEL S/N	SENSING AXIS	WR11	Y	
ACCEL SENSITIVITY				
	MV RMS			
	GP			
	COL			
	GP			
	2.956			
FILTER				
	10-100-200			
FILTER Crossover				
@ 70-700				
TAPER REEL NO.	SWEEP RATE			
012294	4			
COMPR. SPEED				
YAR				
DB/SEC				
5000g@				
HZ TO				
DB/SEC				
CHG@				
HZ TO				
DB/SEC				
NON-OPERATING				
TEMP. 74				
°F				
CONTROL				
RESPONSE				
LOCATION				
A41				
A4Y				
SPECIAL CONDITIONS				
100K-01#2				

MASTER # 1774

REPORT NO.


FREQ. RANGE & DIRECTION	5-2000 Hz	ITEM	SYSC 735H	CODE		SERIAL NO.		TYPE OF TEST	FIXTURE SURVEY
SPECIFICATION		PARA.		AMEND.		PHASE	RAE	NAME OF TEST	

SINE VIBRATION TEST

Standard A[®]

HSF 1633 A 2/69

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	NICKET	14	5 ch 7
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
MEHMED	GEIB	RAE-B	4-19-72	1540



INPUT LEVEL	EXCIT. AXIS
±	Y
ACCEL S/N	SENSING AXIS
VG-57	Y
ACCEL SENSITIVITY	
10.886	MV RMS
—	GP
—	COL
—	GP
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
YAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
ASV ASY	
Hook-up #2	
SPECIAL CONDITIONS	
MASTER AC 1774	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000 Hz	SVSK 79594	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7	—	BASE	SINUSOIDAL SCAN


SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	8	TEST NO.	5
TEST ENGINEER	MEHRER	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1540
					RAE-B				

INPUT LEVEL	EXCIT. AXIS	1	Y
ACCEL S/N	SENSING AXIS	NB62	Z
ACCEL SENSITIVITY			
MV RMS			
GP			
COL			
GP			
2.698			
FILTER			
10-100-100	HZ B.W.		
FILTER CROSSOVER			
@ 70-700	HZ		
TAPER REEL NO.	SWEEP RATE		
012294	4	OCT/MIN	
COMPR. SPEED			
VAR	DB/SEC		
CHG@	HZ TO		
CHG@	HZ TO		
NON-OPERATING	CONTROL		
TEMP 75 °F	RESPONSE		
LOCATION			
A1Z	A1Z		
SPECIAL CONDITIONS			
Hook-Up #2			


REPORT NO.	
MASTER AG 1714	



FREQ. RANGE & DIRECTION	5-2000 Hz	ITEM	SUSK 79594	CODE		TYPE OF TEST	FIXTURE SURVEY
SPECIFICATION		PARA.		AMEND.		NAME OF TEST	

HSF 1633 A 2/69

RIG 26	OPERATOR JODDIN	PROJECT RAE-B	TRACE NO. 7	TEST NO. ch 2
TEST ENGINEER MEHMED	CHECKED BY GEIB		DATE 4-13-72	TIME 1540



INPUT LEVEL + 1	EXCIT. AXIS Y
ACCEL S/N 7040	SENSING AXIS X
ACCEL SENSITIVITY MV RMS GP COL GP 2.805	
FILTER 10-100-200 HZ B.W. FILTER CROSSOVER	
@ 70-700 HZ	
TAPER REEL NO. SWEEP RATE	
02294 4 OCT/MIN	
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO — DB/SEC	
CHG@ — HZ TO — DB/SEC	
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION AIX	
SPECIAL CONDITIONS Hook-up #2	
MASTER 161774	
REPORT NO.	

FREQ. RANGE & DIRECTION 5-2000 HZ	ITEM SYSK 7954	CODE —	SERIAL NO. —	TYPE OF TEST FIXTURE SURVEY
SPECIFICATION AT-VCPS	PARA. 4.3.7	AMEND. —	PHASE BASE	NAME OF TEST SINUSOIDAL SCAN


HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PROJECT	RAE-B	PLOTTED BY	MICKET	TRACE NO.	12	TEST NO.	5
TEST ENGINEER	MEHMED	CHECKED BY	GEIB		RAE-B	DATE	4-13-72	TIME	1540		

INPUT LEVEL	EXCIT. AXIS
1	Y
ACCEL S/N	SENSING AXIS
TG-75	Z
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.791	
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC


NON-OPERATING	CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
A3Z	A3Z
	hook-up #2
SPECIAL CONDITIONS	
	MASTER 86 1774

REPORT NO.



FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000 HZ	SVSK 79594			FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
			BAKE	

RIG	TEST ENGINEER	OPERATOR	WITNESS	WITNESS	TEST NO.
26	S. Mehmed Jr.	P. Jodoin	A. McCarthy	—	5
	CHECKED BY	PROJECT			TIME
	GEIB	RAE-B			1545
					DATE
					4-15-72




INPUT LEVEL	EXCIT. AXIS	TEST NO.
7.5	Y	5
ACCEL S/N	SENSING AXIS	TIME
TE83	Y	1545
ACCEL SENSITIVITY		
—	MV RMS	
2.722	GP	
	COL	
	GP	
FILTER	— 100-200	HZ B.W.
FILTER CROSSOVER		
@ — 70V		HZ
SWEEP RATE	4.0	OCT/MIN
TAPER REEL NO.	01225	LIVE FROM TAPE
COMPR. SPEED	Var	DB/SEC.
CHG. @	HZ TO —	DB/SEC.
CHG. @	HZ TO —	DB/SEC.
NON OPERATING	<input checked="" type="checkbox"/> CONTROL	
TEMP. 74 °F	<input type="checkbox"/> RESPONSE	
LOCATION		
	Ally	
SPECIAL CONDITIONS		
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY		
VCPS LOADED		
PRESSURIZED		

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	SPEC.	PARA.	AMEND.
200-2000Hz	VCPS	748720-1	00001	AT-VCPS	4.3.7.5	NOTE 2
ACTION SHEET NO.	ATA NO.	TYPE OF TEST	NAME OF TEST			
—	—	Qual-VCPS only	SINUSOIDAL VIBRATION			

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	MEHMED	RAE-B	JODDIN	11	5
CHECKED BY			DATE	TIME		
GEIB			4-15-72	1545		



INPUT LEVEL	EXCIT. AXIS
7.5	Y
ACCEL S/N	SENSING AXIS
TE83	Y
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.805	
FILTER	
100/200	HZ B.W.
FILTER Crossover	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
AIY	
HOOK-UP #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
TRACE REWIND TO CERTIFY LEVEL.	
REPORT NO.	


FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	SV	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST

SINE VIBRATION TEST

Standard A[®]

HSF 1633 A 2/69


RIG	26	OPERATOR	JODOIN	PROJECT	RAE-B	PLOTTED BY	JODOIN	TRACE NO.	18	TEST NO.	5
TEST ENGINEER	MEHMED	CHECKED BY	GEIB					DATE	4-15-72	TIME	1545



INPUT LEVEL	EXCIT. AXIS	
± 7.5	Y	
ACCEL S/N	SENSING AXIS	
WR11	Y	
ACCEL SENSITIVITY		
3.016	MV RMS	
	GP	
	COL	
	GP	
FILTER		
100/200	HZ B.W.	
FILTER CROSSOVER		
@ 700	HZ	
TAPER REEL NO.	SWEEP RATE	
0/2295	4 OCT/MIN	
COMPR. SPEED		
VAR	DB/SEC	
CHG@ -	HZ TO - DB/SEC	
CHG@ -	HZ TO - DB/SEC	
NON-OPERATING	<input type="checkbox"/> CONTROL	
TEMP. 75	<input checked="" type="checkbox"/> RESPONSE	
LOCATION	BY	
HUB		
HOOK-UP #2		
SPECIAL CONDITIONS		
VCPS LOADED AND PRESSURIZED		
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY		
REPORT NO.		

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	SV	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3, 7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

RIG	TEST ENGINEER	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	MEHMET	JODDIN	RAE-P	JODDIN	12	5
CHECKED BY			DATE			
GEIB			4-15-72			
			TIME			
			1545			



INPUT LEVEL	EXCIT. AXIS
7.5	Y
ACCEL S/N	SENSING AXIS
YK20	Y
ACCEL SENSITIVITY	
—	MV RMS
1.596	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER Crossover	
@ 700	HZ
TAPE REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
DY	
REA MOUNT	
HOOK-UP #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
REPORT NO.	


FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000Hz VCPS	748720-1	SV	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST

SINE VIBRATION TEST

Standard A[®]

HSF 1633 A 2/69

RIG	26	OPERATOR	JODOIN	PLOTTED BY	JODOIN	TRACE NO.	13	TEST NO.	5
TEST ENGINEER	MEHIVED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-15-72	TIME	1545




INPUT LEVEL	EXCIT. AXIS
+ 7.5	Y
ACCEL S/N	SENSING AXIS
XN32	Y
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
1.297	
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 75	RESPONSE
LOCATION	
EX	
TANK MOUNT	
HOOK-UP #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200-2000 HZ	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	RAE-13	JODDIN	10	5
TEST ENGINEER	CHECKED BY		DATE	TIME	
MEHMED	GEIB		4-15-72	1545	




INPUT LEVEL	EXCIT. AXIS
± 7.5 g	Y
ACCEL S/N	SENSING AXIS
TD40	X
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.805	
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
AIX	
Hook-up #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	SV	748720-1	QUAL
SPECIFICATION	PARA	AMEND.	PHASE	NAME OF TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	17	TEST NO.	5
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-15-72	TIME	1545




INPUT LEVEL EXCIT. AXIS	± 7.5	Y
ACCEL S/N	TD44	X
ACCEL SENSITIVITY	3.035	MV RMS
GP	—	GP
COL	—	GP
GP	—	GP
FILTER	100/200	HZ B.W.
FILTER CROSSOVER	@ 700	HZ
TAPER REEL NO.	012295	SWEEP RATE
COMPR. SPEED	4	OCT/MIN
CHG@	VAR	DB/SEC
CHG@	— HZ TO —	DB/SEC
CHG@	— HZ TO —	DB/SEC
NON-OPERATING	<input type="checkbox"/>	CONTROL
TEMP.	75	°F
RESPONSE	<input checked="" type="checkbox"/>	RESPONSE
LOCATION	BX	
SPECIAL CONDITIONS	HUB	
VCPS LOADED AND PRESSURIZED	HOOK-UP #2	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY		

FREQ. RANGE & DIRECTION	200-2000 HZ	ITEM	VCPS	CODE	SY	748720-1	SERIAL NO.	00001	TYPE OF TEST	QUAL
SPECIFICATION	AT-VCPS	PARA.	4.3.7.5	AMEND.	NOTE 2	VCPS ONLY	NAME OF TEST	SINUSOIDAL VIBRATION		

HSF 1633 A 2/69

RIG	TEST ENGINEER	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	MEHMET	JODDIN	GEIB	JODDIN	15	5
				DATE	TIME	
				4-15-72	1545	



INPUT LEVEL	EXCIT. AXIS	ACCEL S/N	SENSING AXIS
± 7.5	Y		
ACCEL S/N	XM21	X	
ACCEL SENSITIVITY	1.325	MV RMS	
		GP	COL
		GP	GP
FILTER	100/200	HZ B.W.	
FILTER CROSSOVER	700	HZ	
TAPEREEL NO.	0/2295	SWEEP RATE	
COMPR. SPEED	VAR	OCT/MIN	
CHG@	— HZ TO —	DB/SEC	
CHG@	— HZ TO —	DB/SEC	
NON-OPERATING	TEMP. 75 °F	CONTROL RESPONSE	
LOCATION		DX	
REA MOUNT		HOOK-UP # 2	
SPECIAL CONDITIONS		VCPS LOADED AND PRESURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY		REPORT NO.	


FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	SV	748720-1	QUAL
SPECIFICATION	PARA	AMEND	PHASE	NAME OF TEST

SINE VIBRATION TEST

Standard A[®]

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	CHECKED BY	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
				NAF-5		16	9
						DATE	TIME
						4-15-72	1545




INPUT LEVEL ± 7.5	EXCIT. AXIS Y
ACCEL S/N	SENSING AXIS
ACCEL SENSITIVITY MV RMS GP COL GP	
FILTER 100/200 HZ B.W.	
FILTER CROSSOVER @ 700 HZ	
TAPER REEL NO. SWEEP RATE 012295 4 OCT/MIN	
COMPR. SPEED VAR DB/SEC	
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION EX TANK MOUNT HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM VCPS	CODE	SERIAL NO.	TYPE OF TEST
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST

SINE VIBRATION TEST

HSF 1633 A. 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	14	TEST NO.	5
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	VALD	DATE	4-15-72	TIME	1545




INPUT LEVEL	EXCIT. AXIS	ACCEL S/N	SENSING AXIS
+ 7.5	Y	NB62	Z
ACCEL SENSITIVITY	MV RMS	GP	GP
3.052			
FILTER	100/200	HZ R.W.	
FILTER CROSSOVER	700	HZ	
TAPER REEL NO.	SWEEP RATE		
012295	4	OCT/MIN	
COMPR. SPEED	YAR	DB/SEC	
CHG@	HZ TO	DB/SEC	
CHG@	HZ TO	DB/SEC	
NON-OPERATING	CONTROL		
TEMP. 75	OF	RESPONSE	
LOCATION	A1Z		
HOOK-UP # 2			
SPECIAL CONDITIONS			
VCPS LOADED AND PRESSURIZED			
THIS PORTION OF THE TEST PERFORMED WITH THE VCPS ONLY			
REPORT NO.			

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200 - 2000 HZ	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG 26	OPERATOR JODOIN	PLOTTED BY JODOIN	TRACE NO. 29	TEST NO. 7
TEST ENGINEER MEHMET	CHECKED BY GEIB	PROJECT PA	DATE 4-17-72	TIME 1145




INPUT LEVEL ± 3	EXCIT. AXIS Y
ACCEL S/N V/R11	SENSING AXIS Y
ACCEL SENSITIVITY 3.016	MV RMS GP COL GP
FILTER 10/100	HZ B.W. HZ
FILTER CROSSOVER @ 70	TAPER REEL NO. SWEEP RATE 012295 4 OCT/MIN
COMPR. SPEED VAR	DB/SEC CHG@ — HZ TO — DB/SEC CHG@ — HZ TO — DB/SEC
NON-OPERATING TEMP. 75 °F	CONTROL RESPONSE
LOCATION BY	HUB HOOK-UP #2
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

FREQ. RANGE & DIRECTION 5-200HZ	ITEM PA-13	CODE SV 748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION	AMEND.	PHASE	NAME OF TEST	REPORT NO.

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	24	TEST NO.	7
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-17-72	TIME	1145



INPUT LEVEL	EXCIT. AXIS
3	Y
ACCEL S/N	SENSING AXIS
TD48	Y
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.65	
FILTER	10/100 HZ B.W.
FILTER Crossover	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
	CY
	SPACECRAFT Q.G.
	HOOK-UP #2
	SPECIAL CONDITIONS
	VCPS LOADED AND PRESSURIZED.

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SV	SERIAL NO.	TYPE OF TEST
5-2000HZ	RAE-B	748720-1		00001	QUAL
SPECIFICATION	PARA.	AMEND. NOTE	PHASE	NAME OF TEST	
AT-VCPS	4.3.7.5	1 & 3	VCPS	SINUSOIDAL VIBRATION	

PAGE NO.

c89


170

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	TEST NO.
26	JODOIN	MEHMED	7
CHECKED BY		DATE	TIME
GEIB		4-17-72	1145
PROJECT			
RAE-B			
PLOTTED BY			
JODOIN			

INPUT LEVEL	EXCIT. AXIS
± 3	Y
ACCEL S/N	SENSING AXIS
YK20	Y
ACCEL SENSITIVITY	
—	MV RMS
1.596	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION	
0Y	
REA MOUNT	
Hook-up #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	

REPORT NO.




FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-200HZ	VCPS	SV	748720-1	QUAL
SPECIFICATION	AMEND	PHASE	VCPS	NAME OF TEST

SINE VIBRATION TEST

Standard A®

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PROJECT	00001	TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PLOTTED BY	JODDIN	TRACE NO.	22	TEST NO.	7
										DATE	4-17-72	TIME	1145		




INPUT LEVEL	EXCIT. AXIS
± 3	Y
ACCEL S/N	SENSING AXIS
XN32	Y
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
	1.297
FILTER	10/100
	HZ B.W.
FILTER Crossover	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	— HZ TO — DB/SEC
CHG@	— HZ TO — DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	EY
TANK MOUNT	
HOOK-UP #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED.	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
5-200Hz	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND. NOTE	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	1 & 3	AND SPACECRAFT	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	26	OPERATOR	JODOIN	PROJECT	RAE-B	PLOTTED BY	JODOIN	TRACE NO.	25	TEST NO.	7
TEST ENGINEER	ME	CHECKED BY	GEIB					DATE	4-17-72	TIME	1145




INPUT LEVEL	EXCIT. AXIS
+	Y
ACCEL S/N	SENSING AXIS
NB62	Z
ACCEL SENSITIVITY	
3.052	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER Crossover	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION	A1Z
Hook-up #2	
SPECIAL CONDITIONS	
VAPS LOADED AND PRESSURIZED.	

REPORT NO.

FREQ. RANGE & DIRECTION	CODE SV	SERIAL NO.	TYPE OF TEST
S-200HZ	748720-1	00001	QUAL
SPECIFICATION	AMEND.	PHASE	NAME OF TEST
PARA		W-100	

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	19	TEST NO.	7
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-17-72	TIME	1145




INPUT LEVEL	EXCIT. AXIS
3	Y
ACCEL S/N	SENSING AXIS
TD40	X
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GF
	2.805
FILTER	
	10/100 HZ B.W.
FILTER Crossover	
	70 HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	— HZ TO — DB/SEC
CHG@	— HZ TO — DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
	AIX'
	HOOK-UP # 2
	SPECIAL CONDITIONS
	VCPS LOADED AND PRESSURIZED.

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM E-B	CODE SV	SERIAL NO.	TYPE OF TEST
5-200 Hz	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND. No	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	153	AND SPACECRAFT	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	TEST ENGINEER	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	MEHMET	JODDIN	RAE-B	JODDIN	28	7
CHECKED BY				DATE	TIME	
				2-10-72	1145	




INPUT LEVEL	EXCIT. AXIS
3	Y
ACCEL S/N	SENSING AXIS
TD44	X
ACCEL SENSITIVITY	
3.035	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 75°F	RESPONSE
LOCATION	

Bx
HUB
HOOK-UP #2
SPECIAL CONDITIONS
VCP'S LOADED
AND PRESSURIZED.

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
5-2000 Hz	RAE-B	748720-1	00001	QUAL
SPECIFICATION	VCPS	AMEND.	PHASE VCPS	NAME OF TEST

RIG	26	OPERATOR	JODOIN	PLOTTED BY	JODOIN	TRACE NO.	7	TEST NO.	
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	Y-2-B	DATE	4-17-72	TIME	1145



INPUT LEVEL	EXCIT. AXIS	
3	Y	
ACCEL S/N	SENSING AXIS	
TD45	X	
ACCEL SENSITIVITY		
	MV RMS	
	GP	
	COL	
	GP	
2.650		
FILTER		
10/100	HZ B.W.	
FILTER Crossover		
@ 70	HZ	
TAPER REEL NO.	SWEEP RATE	
012295	4	OCT/MIN
COMPR. SPEED		
VAR	DB/SEC	
CHG@ - HZ TO -	DB/SEC	
CHG@ - HZ TO -	DB/SEC	
NON-OPERATING	<input type="checkbox"/> CONTROL	
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE	
LOCATION CX		
SPACECRAFT C.G.		
Hook-Up #2		
SPECIAL CONDITIONS		
VCPS LOADED		
AND PRESSURIZED		


REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
5-200Hz	VCPS	748720-1	00001	QUAL
AT-VCPS	PARA.	AMEND. NOTE	PHASE VCPS	NAME OF TEST
	4.3.7.5	1 & 3	AND SPACECRAFT	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG 26	OPERATOR JODOIN	PLOTTED BY JODOIN	TRACE NO. 1	TEST NO. 1
TEST ENGINEER MEHMET	CHECKED BY GEIB	PROJECT RAE-D	DATE 4-17-72	TIME 1145




INPUT LEVEL 3	EXCIT. AXIS Y
ACCEL S/N XY21	SENSING AXIS X
ACCEL SENSITIVITY 1.325	MV RMS
GP	GP
COL	GP
FILTER 10/100	HZ B.W.
FILTER Crossover 70	HZ
TAPER ELNO. SWEEP RATE 012295	4 OCT/MIN
COMPR. SPEED VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING <input type="checkbox"/>	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION DX	
REA MOUNT	
Hook-up #2	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED.	

REPORT NO.

FREQ. RANGE & DIRECTION 5-200 Hz	ITEM RAE-D	CODE SV 748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION VCPS	PARA	AMEND.	PHASE	NAME OF TEST

177<
1.0
C96
0.1

RIG	26	OPERATOR	JOLOIN	PLOTTED BY	JOLOIN	TRACE NO.	27	TEST NO.	7
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	1633A	DATE	4-17-72	TIME	1145



INPUT LEVEL	EXCIT. AXIS
+	Y
ACCEL S/N	SENSING AXIS
W/F 75	X
ACCEL SENSITIVITY	
1.001	MV RMS
	GP.
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER Crossover	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012295	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION	EX
TANK MOUNT	
HOOK-UP #2	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED.	

REPORT NO.


FREQ. RANGE & DIRECTION	ITEM #	SERIAL NO.	TYPE OF TEST
5-200HZ	13	00001	QUAL
SPECIFICATION	PARA.	AMEND	NAME OF TEST
AT-VCPS	4.3, 7.5	NOTE 1/3	SINUSOIDAL VIBRATION

RANDOM VIBRATION TEST ANALYSIS METHOD A

HSF-1634A

PLOTTED BY P. J. Jodoin	CHECKED BY MEH MED	TEST ENGINEER T. Geib	RIG NO. 26	WITNESS W. J. Jodoin 4-7-72
PROJECT RAE-13	ITEM VCPS with Space Craft	CODE SV748720-1	SERIAL NO. 00001	TYPE OF TEST Qual
SPEC. AT-VCPS	PARA. 4.3.7	PHASE Rand - complete	ATA NO. —	DATE 4-17-72
			ACTION SHEET NO. —	TEST NO. 9

SPECTRAL DENSITY G^2/Hz



EXCITATION ALONG Y	AXIS
GRMS INPUT 9.2	
NON-OPERATING	
TEMP. 74	°F
PERIOD OF TEST START END	
DURATION OF TEST 2.0	MIN.
ACCEL. SERIAL NO. 1E83	
ACCEL. SENSITIVITY —	MV RMS GP
—	COL GP
2.722	
ACCEL. SENSING Y	AXIS
ACCEL. LOCATION AIR	
TAPER REEL NO. 012295	
SPECIAL CONDITIONS VCPS Loaded & Pressurized SPACECRAFT INSTALLED.	
NOTE 1 & 4	

REPORT NO.

C98

179<

PAGE NO.

**Hamilton
Standard**


**U
A[®]**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.


RIG 26	OPERATOR P. J.	PLOTTED BY T. G.	TRACE NO. 2A	TEST NO. 9
TEST ENGINEER T. G.		CHECKED BY MEHME D	DATE 4/17/72	TIME 1700



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER TE83	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 2,722 MV RMS GP COL GP	
ANAL FILTER - HZ B.W. 6 8 12	
SWEEP SPEED - OCT/MIN 1 2 3	
TIME CONSTANT - SEC 1 2 3	
ANAL. CALIBRATION 12,2 8² HZ F.S.	
PERIOD OF TEST <input type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input checked="" type="checkbox"/> CONTROL <input type="checkbox"/> RESPONSE	
PICKUP LOCATION A1Y	
HOOK-UP #2	
SPECIAL CONDITIONS PLOTTED 1/MINUTE INTO RUN.	
VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5619	PARA. 4.317	AMEND. NOTE 154	PHASE COMPLETE PKG	PAGE NO.

RIG 26	OPERATOR P. J	PLOTTED BY T. G	TRACE NO. 12	TEST NO. 9
TEST ENGINEER S. M		CHECKED BY S. M	DATE 4-17-72	TIME 1700



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER WR11	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 3.016 MV/RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 17.54 $\frac{1}{\text{HZ}}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION BY HUB HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM RAE-B	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE COMPLETE PKG	RANDOM —
PAGE NO.				

**Hamilton
Standard**


**U
A_®**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.


RIG 26	OPERATOR P.J.	PLOTTED BY T.G.	TRACE NO. 6	TEST NO. 9
TEST ENGINEER T.G.		CHECKED BY MEHMED	DATE 4/17/72	TIME 1700



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER TD 48	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY MV RMS 2.788 GP 2.78 COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 	
TIME CONSTANT - SEC 	
ANAL. CALIBRATION 1.27 g^2 F.S. HZ	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION CY	
HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE & V 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5619	PARA. 4.3.7	AMEND. NOTE 154	PHASE COMPLETE PKG	PAGE NO.

RIG 26	OPERATOR P.J.	PLOTTED BY T.G.	TRACE NO. 3	TEST NO. 9
TEST ENGINEER T.G.		CHECKED BY MEHMED		DATE 4/17/72
				TIME 1700



INPUT LEVEL 9.2		GRMS
EXCITATION AXIS Y		
ACCEL SERIAL NUMBER YK20		
ACCEL SENSING AXIS Y		
ACCEL SENSITIVITY 1.096		MV RMS GP COL GP
ANAL FILTER - HZ B.W. 6		
SWEEP SPEED - OCT/MIN 6		
TIME CONSTANT - SEC 6		
ANAL. CALIBRATION 3.87 $\frac{g^2}{Hz}$ F.S.		
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END		
DURATION 2.0 MIN		
NON OPERATING	TEMP. 74 °F	
TAPE REEL NO. 012295		
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE		
PICKUP LOCATION Dy		
HOOK-UP #2		
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED		

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5619	PARA. 4.3.7	AMEND. NOTE 15-1	PHASE COMPLETE PKG	PAGE NO.


**Hamilton
Standard**

**U
A**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**
HSF-1635 B

REPORT NO.

RIG 26	OPERATOR P.J.	PLOTTED BY T.G.	TRACE NO. 4	TEST NO. 9
TEST ENGINEER T.G.		CHECKED BY MEHMED	DATE 4/17/72	TIME 1700




INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER XN32	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 1.297 MV RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 	
TIME CONSTANT - SEC 	
ANAL. CALIBRATION 52.5 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION Ey	
HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5611	PARA. 4,3,7	AMEND. NOTE 154	PHASE COMPLETE — PKG	PAGE NO.

184<

C103

RIG 26	OPERATOR P. J	PLOTTED BY T. G	TRACE NO. 7	TEST NO. 9
TEST ENGINEER T. G.		CHECKED BY MEHMED	DATE 4/17/72	TIME 1700



INPUT LEVEL 9.2	GRM
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER NB62	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 3.052	MV RMS
GP	
COL	
GP	
ANAL FILTER - HZ B.W.	
SWEEP SPEED - OCT/MT	
TIME CONSTANT - SEC	
ANAL. CALIBRATION 17.2	$\frac{g^2}{Hz}$ F.S.
PERIOD OF TEST <input checked="" type="checkbox"/> START <input checked="" type="checkbox"/> END	
DURATION 2.0	MIN
NON OPERATING	TEMP. 74
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION A12	
HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5619	PARA. 4.3.7	AMEND. NOTE 154	PHASE COMPLETE PKG	PAGE NO.

Hamilton
Standard


U
A®
DIVISION OF UNITED AIRCRAFT CORPORATION

RANDOM VIBRATION TEST
ANALYSIS METHOD B

HSF-1635 B

REPORT NO.


RIG 26	OPERATOR P.J.	PLOTTED BY T.G.	TRACE NO. 1	TEST NO. 9
TEST ENGINEER T.G.		CHECKED BY MEHMED	DATE 4/17/72	TIME 1700



INPUT LEVEL 9.2 GRMS
EXCITATION AXIS Y
ACCEL SERIAL NUMBER TD40
ACCEL SENSING AXIS X
ACCEL SENSITIVITY — MV RMS 2.805 GP COL GP
ANAL FILTER - HZ B.W. 6
SWEEP SPEED - OCT/MIN —
TIME CONSTANT - SEC —
ANAL. CALIBRATION 1.25 g^2 F.S. HZ
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END
DURATION 2.0 MIN
NON OPERATING <input type="checkbox"/> TEMP. 74 °F
TAPE REEL NO. 012295
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE
PICKUP LOCATION Aix'
Hook-up #2
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QURL
SPEC. AT-VCPS SVHS 5619	PARA. 4,3,7	AMEND. NOTE 154	PHASE COMPLETE — PKG	PAGE NO.


RIG 26	OPERATOR P.J.	PLOTTED BY T.G.	TRACE NO. 5	TEST NO. 9
TEST ENGINEER T.G.		CHECKED BY MEHMED	DATE 4/17/72	TIME 1700



INPUT LEVEL 9.2 GRM		
EXCITATION AXIS Y		
ACCEL SERIAL NUMBER TD45		
ACCEL SENSING AXIS		
ACCEL SENSITIVITY MV RMS 2.650 GP COL GP		
ANAL FILTER - HZ B.W. 6.10 20 50		
SWEEP SPEED - OCT/MIN 0.7 0.2 0.3		
TIME CONSTANT - SEC 2.5 1.25 0.5		
ANAL. CALIBRATION 1.41 g^2 F.S. HZ		
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END		
DURATION 2.0 MIN		
NON OPERATING	TEMP. 74 °F	
TAPE REEL NO. 012295		
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE		
PICKUP LOCATION CX		
HOOK-UP #2		
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED		

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS SVHS 5619	PARA. 4,3,7	AMEND. NOTE 1 & 4	PHASE COMPLETE PKG	PAGE NO.


RIG 26	OPERATOR P. J	PLOTTED BY T. G	TRACE NO. 11	TEST NO. 9
TEST ENGINEER S. M		CHECKED BY S. M	DATE 4-17-72	TIME 1700



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER TD44	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY 3.035 MV RMS	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN.	
TIME CONSTANT - SEC	
ANAL. CALIBRATION 17.32 8 ² F.S. HZ	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION BX HUB HOOK-UP #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE sy 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE COMPLETE PKG	PAGE NO.

RIG 26	OPERATOR P. J.	PLOTTED BY T.G.	TRACE NO. 9	TEST NO. 9
TEST ENGINEER S.M.		CHECKED BY S.M.	DATE 4-17-72	TIME 1700



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER YK20	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY 1.523 MV RMS	
GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/M 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 68.78 g^2 F.S. HZ	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION DX REA MOUNT Hook-up #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV	SERIAL NUMBER 748720-1 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE COMPLETE PKG	PAGE NO.

Hamilton
Standard


U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

RANDOM VIBRATION TEST
ANALYSIS METHOD B

HSF-1635 B

REPORT NO.

RIG 26	OPERATOR P. J.	PLOTTED BY T. G.	TRACE NO. 10	TEST NO. 9
TEST ENGINEER S. M.		CHECKED BY S. M.	DATE 4-17-72	TIME 1700



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Y	
ACCEL SERIAL NUMBER XN32	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY 1.261	MV RMS
GP	GP
COL	GP
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN. 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 100.3 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012295	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION EX	
TANK MOUNT	
Hook-up #2	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV	SERIAL NUMBER 748720-1	TYPE OF TEST 00001	QUAL QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE	PHASE COMPLETE	RANDOM PKG	PAGE NO.


Section IV

Z - Axis

A) Sine Data

B) Random Data

PAGE NO.




FREQ. RANGE & DIRECTION		ITEM	CODE	SERIAL NO.	SPEC.	PARA.	AMEND.
S-21C HZ		SVSK79594	—	SVSK79594	AT-VCPS	4.3.7.-	—
ACTION SHEET NO.		ATA NO.	TYPE OF TEST	NAME OF TEST			
—		—	Accept Test	BARE PICTURE		Sine Scan	

INPUT LEVEL	EXCIT. AXIS
1.0	Z
ACCEL S/N	SENSING AXIS
NR62	Z
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.698	
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
SWEEP RATE	
4.0	OCT/MIN
TAPER REEL NO.	LIVE
01294	FROM
COMPR. SPEED	TAPE
Var.	DB/SEC.
CHG.@ ~ HZ TO ~	DB/SEC.
CHG.@ ~ HZ TO ~	DB/SEC.
NON OPERATING	<input checked="" type="checkbox"/> CONTROL
TEMP. 75 °F	<input type="checkbox"/> RESPONSE
LOCATION	
AIRZ Hook-up #1 SPECIAL CONDITIONS Bare Fixture SVSK79594 MASTER # 1774	
REPORT NO.	

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	CHECKED BY	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
26	JODDIN	MEHMED	GEIB	RAE-B	MICKET	1	3
					DATE	TIME	
					4-13-72	1000	




INPUT LEVEL	EXCIT. AXIS
+	z
ACCEL S/N	SENSING AXIS
NB62	z
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.698	
FILTER	
10-100-200	HZ B.W.
FILTER Crossover	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP 75 °F	RESPONSE
LOCATION	
A 12	A 12
Hook-up #1	
SPECIAL CONDITIONS	
BARE FIXTURE	

REPORT NO.
MASTER 16-1774

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SVSK 79594			FIXTURE SURVEY

RIG	OPERATOR	TEST ENGINEER	TEST NO.
26	JODOIN	MEHMED	3
CHECKED BY		DATE	TIME
GEIB		4-13-72	1000
PROJECT		TRACE NO.	
RAE-B		4	
PLOTTED BY		TEST NO.	
MICKET		3	




INPUT LEVEL	EXCIT. AXIS
1	Z
ACCEL S/N	SENSING AXIS
1044	Z
ACCEL SENSITIVITY	
—	MV RMS
2.773	GP
	COL
	GP
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
ACE A2Z	
HOCK-UP #1	
SPECIAL CONDITIONS	
BARE FIXTURE	
REPORT NO.	
MASTER AC 1774	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SVSK79594	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7	—	BARE FIXTURE	SINUSOIDAL SCAN

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	5	TEST NO.	3
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1000



INPUT LEVEL	EXCIT. AXIS
1	Z
ACCEL S/N	SENSING AXIS
TG75	Z
ACCEL SENSITIVITY	
—	MV RMS
2.791	GP
	COL
	GP
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
CQMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC

NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
A3Z A3Z	
Hook-up #1	


SPECIAL CONDITIONS
BARE FIXTURE

REPORT NO.
MASTER #6-1774

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000 Hz	SVSK79594	—	—	FIXTURE SURVEY

TRACE NO. 6	TEST NO. 3
DATE 4-13-72	TIME 1000

INPUT LEVEL + / 8	EXCIT. AXIS Z
ACCEL S/N WR11	SENSING AXIS Z
ACCEL SENSITIVITY — MV RMS 2.956 GP COL GP	
FILTER 10-100-200 HZ B.W. FILTER Crossover @ 70-700 HZ TAPER REEL NO. SWEEP RATE 012294 4 OCT/MIN COMPR. SPEED VAR DB/SEC CHG@ — HZ TO — DB/SEC CHG@ — HZ TO — DB/SEC	
NON-OPERATING TEMP. 75 °F	<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE
LOCATION A4Z A4Z Hook-up #1 SPECIAL CONDITIONS BARE FIXTURE	
REPORT NO. MASTER 16-1774	




FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
53000HZ	SVSK TFS94	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
A T-VCPS	4.3.7	—	FIXTURE	SINUSOIDAL SCAN

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	7	TEST NO.	3
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1000




INPUT LEVEL	EXCIT. AXIS
+	Z
ACCEL S/N	SENSING AXIS
VG57	Z
ACCEL SENSITIVITY	
10:886	MV RMS
	GP
	COL
	GP
FILTER	
10-100-200	HZ B.W.
FILTER CROSSOVER	
@ 70-700	HZ
TAPER REEL NO.	SWEEP RATE
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75	<input checked="" type="checkbox"/> RESPONSE

LOCATION	A5Z
SPECIAL CONDITIONS	HOCK-UP#1
	DARE FIXTURE

REPORT NO.	MASTER 861774
------------	---------------

FREQ. RANGE & DIRECTION	5-2000HZ	ITEM	SVSK 79594	CODE		SERIAL NO.		TYPE OF TEST	FIXTURE SURVEY
SPECIFICATION		AMEND		PHASE		NAME OF TEST			

RIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	3	TEST NO.	42
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1000




INPUT LEVEL	EXCIT. AXIS
+	1
ACCEL S/N	SENSING AXIS
TD40	X
ACCEL SENSITIVITY	
	MV RMS
	GP
	COL
	GP
2.805	
FILTER	
10-100-200 HZ B.W.	
FILTER Crossover	
@ 70-700 HZ	
TAPER REEL NO. SWEEP RATE	
012294 4 OCT/MIN	
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO — DB/SEC	
CHG@ — HZ TO — DB/SEC	
NON-OPERATING	CONTROL
TEMP. 75 °F	RESPONSE
LOCATION	
AIX	
Hook-up #1	
SPECIAL CONDITIONS	
AIX BARE FIXTURE	
REPORT NO.	
MASTER #1774	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000HZ	SVSK79594	—	—	FIXTURE SURVEY
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7	—	BARE FIXTURE	SINUSOIDAL SCAN

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	MICKET	TRACE NO.	3	TEST NO.	3
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE-B	DATE	4-13-72	TIME	1000




INPUT LEVEL	EXCIT. AXIS
± 1	8 Z
ACCEL S/N	SENSING AXIS
TE83	Y
ACCEL SENSITIVITY	
—	MV RMS
2.722	GP
	COL
	GP
FILTER	
10-100-200	HZ B.W.
FILTER Crossover	
@ 70-700	HZ
TAPER REEL NO. SWEEP RATE	
012294	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 75 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
AIY	
Hook-up #1	
SPECIAL CONDITIONS	
BARE FIXTURE	

REPORT NO.
MASTER # 1774

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
5-2000 Hz	SNK79594	—	—	FIXTURE SURVEY

RIG # 26	OPERATOR P. Jodoin	WITNESS —	TEST NO. 13
TEST ENGINEER T. Grib	CHECKED BY MEHMET	PROJECT RAE-B	DATE 4-18-72
			TIME 1650




INPUT LEVEL 1.0	EXCIT. AXIS Z
ACCEL S/N ND62	SENSING AXIS Z
ACCEL SENSITIVITY —	MV RMS GP COL GP
2.698	
FILTER 100-200	HZ B.W.
FILTER Crossover @ 700	HZ
SWEEP RATE 4	OCT/MIN
TAPER REEL NO. 02296	LIVE FROM TAPE
COMPR. SPEED V2V	DB/SEC.
CHG. @ —	HZ TO DB/SEC.
CHG. @ —	HZ TO DB/SEC.
NON OPERATING TEMP. 74°F	CONTROL RESPONSE
LOCATION V A12	
SPECIAL CONDITIONS VCPS ONLY Loaded & Pressurized	
REPORT NO.	

FREQ. RANGE & DIRECTION 200-2000	ITEM VCPS	CODE SV 248720-1	SERIAL NO. 00001	SPEC. AT-VCPS	PARA. 4.3.7	AMEND. —
ACTION SHEET NO. —	ATA NO. —	TYPE OF TEST Q08L	NAME OF TEST SIE. SCAR	ITEM/FIXTURE		

HSF-1633, 1 2/69


RIG	26	OPERATOR	JOHN N	WITNESS	Mr. Gureh	TEST NO.	14
TEST ENGINEER	GE1B	CHECKED BY	M. L. MEO	PROJECT	RAE-B	DATE	4-18-72
						TIME	1705



INPUT LEVEL	10	EXCIT. AXIS	Z
ACCEL S/N	NB62	SENSING AXIS	Z
ACCEL SENSITIVITY		MV RMS	
	2.698	GP	
		COL	
		GP	
FILTER			
	100-200	HZ B.W.	
FILTER CROSSOVER			
@	700	HZ	
SWEEP RATE	4	OCT/MIN	
TAPER REEL NO.	012296	LIVE FROM TAPE	<input checked="" type="checkbox"/>
COMPR. SPEED	VAR	DB/SEC.	
CHG. @	~HZ TO	DB/SEC.	
CHG. @	~HZ TO	DB/SEC.	
NON OPERATING	<input checked="" type="checkbox"/>	CONTROL	
TEMP.	74	°F	<input checked="" type="checkbox"/>
LOCATION	AIZ		
SPECIAL CONDITIONS	VCPS ONLY		
VCPS LOADED AND PRESSURIZED			
SEE NOTE 2 OF AT-VCPS			
REPORT NO.			

FREQ. RANGE & DIRECTION	200-2KHZ	ITEM	VCPS	CODE SV	748720-1	SERIAL NO.	00001	SPEC.	AT-VCPS	PARA.	43.7.5	AMEND.	NOTE 2
ACTION SHEET NO.		ATA NO.		TYPE OF TEST	Q11A1	NAME OF TEST	CYCLICAL VIBRATION						

TRIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	P. J.	P. J.	41	14
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
S. M.	T. G.	RAE-B	4-16-72	1705




INPUT LEVEL ± 10	EXCIT. AXIS Z
ACCEL S/N NB62	SENSING AXIS Z
ACCEL SENSITIVITY — MV RMS GP 2.698 COL GP	
FILTER 100/200 HZ B.W.	
FILTER CROSSOVER @ 700 HZ	
TAPER REEL NO. 012496	SWEEP RATE 4 OCT/MIN
COMPR. SPEED VAR DB/SEC	
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON- OPERATING TEMP. 74 °F	<input checked="" type="checkbox"/> CONTROL <input type="checkbox"/> RESPONSE
LOCATION A1Z	
Hook-up #3 SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	
REPORT NO.	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPs	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPs	4.3.7.5	NOTE 2	ONLY VCPs	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	P. J.	PLOTTED BY	P. J.	TRACE NO.	42	TEST NO.	14
TEST ENGINEER	S. M.	CHECKED BY	T. G.	PROJECT	RAE-B	DATE	4-18-72	TIME	1705




INPUT LEVEL	EXCIT. AXIS	10	Z
ACCEL S/N	SENSING AXIS	TG75	Z
ACCEL SENSITIVITY	MV RMS		
	GP		
	COL		
	GP		
FILTER			
	100/200	HZ B.W.	
FILTER CROSSOVER			
@	700	HZ	
TAPER REEL NO.	SWEEP RATE		
012296	4	OCT/MIN	
COMPR. SPEED			
VAR	DB/SEC		
CHG@	HZ TO	DB/SEC	
CHG@	HZ TO	DB/SEC	
NON-OPERATING	CONTROL		
TEMP. 74 °F	RESPONSE		
LOCATION	BZ		
HUB			
HOOK-UP #3			
SPECIAL CONDITIONS			
VCPS LOADED			
AND PRESSURIZED			

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	FREQUENCY HZ	TYPE OF TEST	NAME OF TEST
200-2000 HZ	VCPS	748720-1	00001		QUAL	
SPECIFICATION	AMEND					

PAGE NO.

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
36	P. J.	P. J.	43	14
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
S. M.	T. G.	RAE-D	4-18-72	1705




INPUT LEVEL	EXCIT. AXIS
+ 10	Z
ACCEL S/N	SENSING AXIS
XM21	Z
ACCEL SENSITIVITY	
—	MV RMS
1.370	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012296	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ —	HZ TO — DB/SEC
CHG@ —	HZ TO — DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION DZ	
REA MOUNT	
HOOK-UP # 3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

RIG 26	OPERATOR P. J.	PROJECT RAL-D	TEST ENGINEER S.M.	PLOTTED BY P. J.	TRACE NO. 44	TEST NO. 14
CHECKED BY T. G.				DATE 4-18-72	TIME 1705	



INPUT LEVEL ± 10	EXCIT. AXIS Z
ACCEL S/N YK20	SENSING AXIS
ACCEL SENSITIVITY	
MV RMS	GP
1.596	COL
	GP
FILTER 100/200 HZ B.W.	
FILTER CROSSOVER	
@ 700	HZ
TAPE REEL NO. SWEEP RATE	
012296	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION EZ	
TANK MOUNT	
HOOK-UP #3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

REPORT NO.

TYPE OF TEST

QUAL

SERIAL NO.

00001

CODE SV

748720-1


ITEM

VCPS

FREQ. RANGE & DIRECTION

200-2000Hz

RIG	26	OPERATOR	P. J.	PLOTTED BY	P. J.	TRACE NO.	47	TEST NO.	14
TEST ENGINEER	S. M.	CHECKED BY	J. G.	PROJECT	4-18-72	DATE	4-18-72	TIME	1705



INPUT LEVEL	EXCIT. AXIS
+	10
ACCEL S/N	SENSING AXIS
WF 75	Z
ACCEL SENSITIVITY	
1.001	MV RMS
	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012296	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74	RESPONSE
LOCATION FZ	
LATCH VALVE MT	
HOOK-UP #3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	


REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4-3.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

RIG 26	OPERATOR P. J.	PROJECT P.E.D.	PLOTTED BY P.D.	TRACE NO. 48	TEST NO. 14
TEST ENGINEER S.M.	CHECKED BY T.G.		DATE 4-18-72	TIME 1705	


INPUT LEVEL + 10	EXCIT. AXIS Z
ACCEL S/N XN32	SENSING AXIS Z
ACCEL SENSITIVITY 1.261	MV RMS GP
	GP
	GP
FILTER 100/200	HZ B.W.
FILTER CROSSOVER @ 700	HZ
TAPE REEL NO. 012296	SWEEP RATE 4 OCT/MIN
COMPR. SPEED VAR	DB/SEC
CHG@ —	HZ TO — DB/SEC
CHG@ —	HZ TO — DB/SEC
NON-OPERATING TEMP 74	CONTROL RESPONSE
LOCATION GZ	
JUNCTION BOX MOUNT HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	



FREQ. RANGE & DIRECTION 200-2000 HZ	ITEM VCPS	CODE SV	SERIAL NO. 00001	TYPE OF TEST QUAL	NAME OF TEST

REPORT NO.

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	P. J.	P. J.	49	14
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
S. M.	T. G.	RAE-D	4-18-72	1705



INPUT LEVEL	EXCIT. AXIS
± 10	Z
ACCEL S/N	SENSING AXIS
XJ29	Z
ACCEL SENSITIVITY	
1.636	MV RMS
	GP
	COL
	GP
FILTER	
100/200	HZ B.W.
FILTER Crossover	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012296	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	— HZ TO — DB/SEC
CHG@	— HZ TO — DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74 °F	<input type="checkbox"/> RESPONSE
LOCATION	HZ
PRESSURE REDUCER MT	
HOOK-UP # 3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED.	


REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST
200-2000 HZ	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE	NAME OF TEST
AT-VCPS	4-3.7.5	NOTE 2	VCPS ONLY	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	P. J.	PLOTTED BY	P. J.	TRACE NO.	46	TEST NO.	14
TEST ENGINEER	S.M.	CHECKED BY	T.G.	PROJECT	RAE-B	DATE	4-18-72	TIME	1705



INPUT LEVEL	EXCIT. AXIS
+ 10	Z
ACCEL S/N	SENSING AXIS
TE83	Y
ACCEL SENSITIVITY	
2.979	MV RMS
	GP
	COL
	GP
FILTER	
150/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPER REEL NO.	SWEEP RATE
012296	4 OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74 °F	<input checked="" type="checkbox"/> RESPONSE
LOCATION	AIY


Hook-up #3
SPECIAL CONDITIONS
VCPS LOADED
AND PRESSURIZED.

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200-2000 Hz	VCPS	748720-1	00001	QUAL

RIG	TEST ENGINEER	OPERATOR	WITNESS	WITNESS	TEST NO.
26	T.G.	P.J.	—	Mr. G. J. L.	16
		CHECKED BY	PROJECT	DATE	TIME
		MEHMED	RAE-B	4-19	0930


INPUT LEVEL	EXCIT. AXIS
6.8	Z
ACCEL S/N	SENSING AXIS
ND62	Z
ACCEL SENSITIVITY	
—	MV RMS
—	GP
—	COL
—	GP
2698	
FILTER	
10-100	HZ B.W.
FILTER CROSSOVER	
@ 76	HZ
SWEEP RATE 30CT/MIN	14-23HZ
4.0	OCT/MIN
TAPER REEL NO.	LIVE
012296	FROM TAPE
COMPR. SPEED	
Var.	DB/SEC.
CHG. @	HZ TO DB/SEC.
CHG. @	HZ TO DB/SEC.
NON OPERATING	<input checked="" type="checkbox"/> CONTROL
TEMP. 74	of RESPONSE
LOCATION	A / Z
SPECIAL CONDITIONS	VCPS WITH SPACECRAFT
	VCPS LOADED AND PRESSURIZED
	REPORT NO.



FREQ. RANGE & DIRECTION	ITEM	CODESV	SERIAL NO.	SPEC.	PARA.	AMEND.
5-200 HZ	VCPS	748720-1	00001	AT-VCPS	4.3.7.5	—
ACTION SHEET NO.	ATA NO.	TYPE OF TEST	NAME OF TEST			
—	—	QUAL	Sine Scan - COMPLETE PKG.			

SINE VIBRATION TEST

RIG	TEST ENGINEER	OPERATOR	PROJECT	PLOTTED BY	TRACE NO.	TEST NO.
ZG	MEHMET	JODDIN	GEIB	JODDIN	50	16
CHECKED BY				DATE	TIME	
				4-19-72	0930	




INPUT LEVEL	EXCIT. AXIS
+ 6.8	Z
ACCEL S/N	SENSING AXIS
NB62	Z
ACCEL SENSITIVITY	
	MV RMS
	GP
2.698	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012296	(3) 1/23 Hz
COMPR. SPEED	
4	OCT/MIN
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION	
A1Z	
Hook-up #3	
SPECIAL CONDITIONS	
VCPS LOADED AND PRESSURIZED	

FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	TYPE OF TEST	REPORT NO.
5-200HZ	RAE-B	SV	748720-1	QUAL	

RIG	OPERATOR	PLOTTED BY	TRACE NO.	TEST NO.
26	P. J.	P. J.	45	14
TEST ENGINEER	CHECKED BY	PROJECT	DATE	TIME
S. M.	T. G.	RAE-B	4-18-72	1705

INPUT LEVEL ± 10	EXCIT. AXIS Z
ACCEL S/N TD40	SENSING AXIS X
ACCEL SENSITIVITY	
3.005	MV RMS
—	GP
—	COL
—	GP
FILTER	
100/200	HZ B.W.
FILTER CROSSOVER	
@ 700	HZ
TAPEREEL NO. SWEEP RATE	
012296	4 OCT/MIN
COMPR. SPEED	
VAR DB/SEC	
CHG@ — HZ TO —	DB/SEC
—	
CHG@ — HZ TO —	DB/SEC
—	
NON-OPERATING	
TEMP. 74 °F	<input type="checkbox"/> CONTROL
	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
A1X	
HOOK-UP # 3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

REPORT NO.



FREQ. RANGE & DIRECTION		ITEM	CODE SV	SERIAL NO.	TYPE OF TEST
200-2000 Hz		V CPS	748720-1	00001	QUAL
SPECIFICATION		PARA.	AMEND.	PHASE	NAME OF TEST
4T-1/CPS		4.3.7.5	NOTE 2	ONLY V CPS	SINUSOIDAL VIBRATION

NO TOLERANCE REQUIRED
1 G. FUTURE SCAN TO
INSURE PROPER MOUNTING
AND EQUIPMENT OPERATION

Nonlinear Input Device

INPUT LEVEL / 1	EXCIT. AXIS Z
ACCEL S/N NBG2	SENSING AXIS Z
ACCEL. SENSITIVITY 2.698	MV RMS GP
	COL GP


FILTER 10/100/ [REDACTED] HZ B.W.	
FILTER CROSSOVER [REDACTED] HZ	
SWEEP RATE 3.0 OCT/100 17-2348 4.0 OCT/MIN	
TAPER REEL NO. 012296	<input checked="" type="checkbox"/> LIVE <input type="checkbox"/> FROM TAPE
COMPR. SPEED	
YAR DB/SEC.	
CHG. @	HZ TO DB/SEC.
CHG. @	HZ TO DB/SEC.

NON OPERATING TEMP. 75 OF	<input checked="" type="checkbox"/> CONTROL <input type="checkbox"/> RESPONSE
LOCATION A1Z	

SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED. SPACECRAFT MOUNTED.	REPORT NO.
--	------------

FREQUENCY Hz		FREQUENCY Hz		FREQUENCY Hz		
FREQ. RANGE & DIRECTION	ITEM	CODE	SERIAL NO.	SPEC.	PARA.	AMEND.
5-200 Hz	VCPS	SV 7487201	00001	AT-VCPS	4.3.7.5	NOTE 1
ACTION SHEET NO.	ATA NO.	TYPE OF TEST		NAME OF TEST SINUSOIDAL VIBRATION		

RIG	OPERATOR	TEST ENGINEER	PLOTTED BY	TRACE NO.	TEST NO.
26	JODOIN	MEHMET	JODOIN	51	16
CHECKED BY	PROJECT	DATE	TIME		
GEIB		4-19-72	0930		



INPUT LEVEL	EXCIT. AXIS	
± 6.8	Z	
ACCEL S/N	SENSING AXIS	
7675	Z	
ACCEL SENSITIVITY		
	MV RMS	
	GP	
2.791	COL	
	GP	
FILTER		
12/100	HZ BW.	
FILTER CROSSOVER		
70	HZ	
TAPER REEL NO.	SWEEP RATE	
012296	5/73/2	
COMPR. SPEED		
VAR	DB/SEC	
CHG@	HZ TO	DB/SEC
CHG@	HZ TO	DB/SEC
NON-OPERATING	CONTROL	
TEMP. 74 °F	RESPONSE	
LOCATION		
BZ		
HUB		
HOOK-UP #3		
SPECIAL CONDITIONS		
VCPS LOADED AND PRESSURIZED		
REPORT NO.		

FREQ. RANGE & DIRECTION	ITEM-D	CODE SV	FREQUENCY HZ	TYPE OF TEST
5-2000HZ	VCPS	748720-1	00001	QUAL
SPECIFICATION	PARA.	AMEND.	PHASE VCPS	NAME OF TEST
AT-VCPS	4.3.7.5	NOTE 1	AND SPACECRAFT	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

Hamilton Standard


SINE VIBRATION TEST

DIVISION OF UNITED AIRCRAFT CORPORATION


TRIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	52	TEST NO.	16
TEST ENGINEER	MEHMED	CHECKED BY	GEIG	PROJECT	100-1	DATE	4-19-72	TIME	0930

INPUT LEVEL	EXCIT. AXIS
± 6.8	Z
ACCEL S/N	SENSING AXIS
ACCEL SENSITIVITY	
MV RMS	
GP	
COL	
GP	
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012296	317-342
COMPR. SPEED	4 OCT/MIN
VAR	DB/SEC
CHG@ — HZ TO —	DB/SEC
CHG@ — HZ TO —	DB/SEC
NON-OPERATING TEMP. 74 °F	<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE
LOCATION DZ	
REA MOUNT	
HOOK-UP #3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

REPORT NO.



RIG 26	OPERATOR JODOIN	PLOTTED BY JODOIN	TRACE NO. 53	TEST NO. 16
TEST ENGINEER MEHMED	CHECKED BY GEIB	PROJECT RAE-B	DATE 4-19-72	TIME 0930




INPUT LEVEL ± 6.8	EXCIT. AXIS Z
ACCEL S/N YK20	SENSING AXIS Z
ACCEL SENSITIVITY 1.596	
MV RMS GP COL GP	
FILTER 10/100	
HZ B.W. 10/100	
FILTER Crossover 70	
TAPER REEL NO. SWEEP RATE 012296 4	
OCT/MIN 4	
COMPR. SPEED VAR	
DB/SEC DB/SEC	
CHG@ - HZ TO - DB/SEC	
CHG@ - HZ TO - DB/SEC	
NON-OPERATING TEMP 74 °F	CONTROL RESPONSE
LOCATION FZ TANK MOUNT HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	
REPORT NO.	

FREQ. RANGE & DIRECTION 5-200HZ	ITEM RAE-B	CODE SV 748720-1	SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION AT-VCPS	PARAM. 4.3.7.5	AMEND. NOTE 1	PHASE VCPS AND SPACECRAFT	NAME OF TEST SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	OPERATOR	TEST NO.
26	JODDIN	58
TEST ENGINEER	CHECKED BY	DATE
MEHMED	GEIB	4-19-72
	PROJECT	TIME
	174E-13	0930




INPUT LEVEL	EXCIT. AXIS
± 6.8	Z
ACCEL S/N	SENSING AXIS
WF 75	Z
ACCEL SENSITIVITY	
1.001	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER CROSSOVER	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
012296	3.17-25 Hz
COMPR. SPEED	4 OCT/MIN
VAR	DB/SEC
CHG@ -	HZ TO DB/SEC
CHG@ -	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION FZ	
LATCH VALVE	
MOUNT HOOKUP #3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM-5	CODE SV	SERIAL NO.	TYPE OF TEST
5-200 Hz	VCPS	748720-1	00001	QUAL

RIG 26	OPERATOR JODDOIN	PLOTTED BY JODDOIN	TRACE NO. 59	TEST NO. 16
TEST ENGINEER MEHMED	CHECKED BY GEIB	PROJECT VIB	DATE 4-19-72	TIME 0930




INPUT LEVEL + 6.8	EXCIT. AXIS Z
ACCEL S/N XN32	SENSING AXIS Z
ACCEL SENSITIVITY 1.261 MV RMS	
GP COL GP	
FILTER 10/100 HZ B.W.	
FILTER CROSSOVER @ 70 HZ	
TAPER REEL NO. 02296	SWEEP RATE 31-17-23 Hz
COMPR. SPEED VAR DB/SEC	
CHG@ - HZ TO -	DB/SEC
CHG@ - HZ TO -	DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION GZ	
JUNCTION BOX MOUNT HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	
REPORT NO.	

FREQ. RANGE & DIRECTION 5-200 Hz	ITEM # VCPS	CODE SV 748720-1	FREQUENCY HZ SERIAL NO. 00001	TYPE OF TEST QUAL
SPECIFICATION AT-VCPS	PARAM. 4.3.7.5	AMEND. NOTE 1	PHASE VCPS AND SPACE CRAFT	NAME OF TEST SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JDDOIN	PLOTTED BY	JDDOIN	TRACE NO.	60	TEST NO.	16
TEST ENGINEER	MEHMED	CHECKED BY	GEIB	PROJECT	RAE	DATE	4-19-72	TIME	0930




INPUT LEVEL	± 6.8	EXCIT. AXIS	Z
ACCEL S/N	XJ29	SENSING AXIS	Z
ACCEL SENSITIVITY	1.636	MV RMS	
		GP	
		COL	
		GP	
FILTER	10/100	HZ B.W.	
FILTER Crossover	@ 70	HZ	
TAPER REEL NO.	012296	SWEEP RATE	(3)-17-23H
COMPR. SPEED	VAR	DB/SEC	
CHG@	—	HZ TO	DB/SEC
CHG@	—	HZ TO	DB/SEC
NON-OPERATING	<input type="checkbox"/>	CONTROL	
TEMP.	74	°F	RESPONSE
LOCATION	HZ		
PRESSURE	XDUCER		
SPECIAL CONDITIONS	HOOK-UP # 3		
VCPS LOADED			
AND PRESSURIZED.			

REPORT NO.

?

FREQ. RANGE & DIRECTION	5-200HZ	ITEM D	RAE.D	CODE	SV	748720-1	SERIAL NO.	00001	TYPE OF TEST	QUAL
-------------------------	---------	--------	-------	------	----	----------	------------	-------	--------------	------

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	56	TEST NO.	16
TEST ENGINEER	MEHMET	CHECKED BY	GEIB	PROJECT	WAVE	DATE	4-19-72	TIME	0930




INPUT LEVEL	± 6.8	EXCIT. AXIS	Z
ACCEL S/N	TD40	SENSING AXIS	X
ACCEL SENSITIVITY	3.005	MV RMS	
		GP	
		COL	
		GP	
FILTER	10/100	HZ B.W.	
FILTER CROSSOVER	@ 70	HZ	
TAPER REEL NO.	012296	SWEEP RATE	(3) 17-23/8
COMPR. SPEED	VAR	DB/SEC	
CHG@	—	HZ TO	DB/SEC
CHG@	—	HZ TO	DB/SEC
NON-OPERATING		CONTROL	<input type="checkbox"/>
TEMP. 74		RESPONSE	<input checked="" type="checkbox"/>
LOCATION	AIX		
HOOK-UP # 3			
SPECIAL CONDITIONS			
VCPS LOADED AND PRESSURIZED.			
REPORT NO.			

FREQ. RANGE & DIRECTION	5-200HZ VCPS	CODE SV	748720-1	SERIAL NO.	00001	TYPE OF TEST	QUAL
SPECIFICATION	AT-VCPS	AMEND.	NOTE 1	PHASE VCPS AND SPACECRAFT		NAME OF TEST	SINUSOIDAL VIBRATION

HSF 1633 A 2/69

RIG	OPERATOR	TEST ENGINEER	MEHMET	PLOTTED BY	JODDIN	TRACE NO.	54	TEST NO.	16
CHECKED BY				PROJECT	WRE-D	DATE	4-14-72	TIME	0930




INPUT LEVEL	EXCIT. AXIS	ACCEL S/N	SENSING AXIS
+	6.8	7045	Z
ACCEL SENSITIVITY		MV RMS	
—		GP	
2.650		COL	
—		GP	
FILTER		HZ B.W.	
10/100		—	
FILTER CROSSOVER		HZ	
@ 70		—	
TAPER REEL NO.		SWEEP RATE	
0/2296		(3) 17-23 Hz	
COMPR. SPEED		OCT/MIN	
VAR		4	
CHG@		DB/SEC	
—		—	
CHG@		DB/SEC	
—		—	
NON-OPERATING		CONTROL	
TEMP. 74 °F		<input checked="" type="checkbox"/> RESPONSE	
LOCATION		—	

CX
SPACECRAFT C.G.
HOOK-UP #3
SPECIAL CONDITIONS
VCPS LOADED
AND PRESSURIZED

REPORT NO.

FREQ. RANGE & DIRECTION	ITEM-D	CODE SV	SERIAL NO.	TYPE OF TEST
5-200Hz	WRE-D	748720-1	00001	QUAL

RIG	OPERATOR	TEST ENGINEER	TEST NO.
26	JODDIN	MEHMET	16
CHECKED BY	PROJECT	DATE	TIME
GEIB	PALE	4-19-72	0930



INPUT LEVEL	EXCIT. AXIS
± 6.8	Z
ACCEL S/N	SENSING AXIS
TE83	Y
ACCEL SENSITIVITY	
2.979	MV RMS
	GP
	COL
	GP
FILTER	
10/100	HZ B.W.
FILTER Crossover	
70	HZ
TAPER REEL NO.	SWEEP RATE
012296	OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@	HZ TO DB/SEC
CHG@	HZ TO DB/SEC
NON-OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION	
A1Y	
Hook-Up # 3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	


REPORT NO.

FREQ. RANGE & DIRECTION	CODE SV	SERIAL NO.	TYPE OF TEST
AT-VCPS	748720-1	00001	QUAL
SPECIFICATION	AMEND.	PHASE VCPS	NAME OF TEST
4.3.7.5	NOTE 1	AND SPACE CRAFT	SINUSOIDAL VIBRATION

SINE VIBRATION TEST

HSF 1633 A 2/69

RIG	26	OPERATOR	JODDIN	PLOTTED BY	JODDIN	TRACE NO.	53	TEST NO.	16
TEST ENGINEER	MEHMED	CHECKED BY	SEIB	PROJECT	REEL	DATE	4-19-72	TIME	0930



INPUT LEVEL	EXCIT. AXIS
+ 6.8	Z
ACCEL S/N	SENSING AXIS
TD48	Y
ACCEL SENSITIVITY	
—	MV RMS
—	GP
2.788	COL
—	GP
FILTER	
10/100	HZ B.W.
FILTER Crossover	
@ 70	HZ
TAPER REEL NO.	SWEEP RATE
0/2296	OCT/MIN
COMPR. SPEED	
VAR	DB/SEC
CHG@ —	HZ TO — DB/SEC
CHG@ —	HZ TO — DB/SEC
NON-OPERATING	<input type="checkbox"/> CONTROL
TEMP. 74	<input checked="" type="checkbox"/> RESPONSE
LOCATION	
CY	
SPACECRAFT C.G.	
HOOBUP # 3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

FREQ. RANGE & DIRECTION	ITEM-B	CODE SV	SERIAL NO.	TYPE OF TEST
5-2000Hz	VCPS	748720-1	00001	QUAL
AMEND	AMEND	AMEND	AMEND	AMEND

PAGE NO. 1

PLOTTED BY <i>MICKET</i>	CHECKED BY <i>GE 113</i>	TEST ENGINEER <i>MR. MEHMED</i>	RIG NO. <i>26</i>	WITNESS <i>14-1972</i>
PROJECT <i>RAE B</i>	ITEM <i>RAE/VCPs</i>	CODE SV <i>748720-1</i>	SERIAL NO. <i>00001</i>	TYPE OF TEST <i>QUAL</i>
SPEC. <i>AT-VCPs</i>	PARA. <i>4.3.7</i>	PHASE <i>RAND</i>	ATA NO. <i>—</i>	DATE <i>4/19/72</i>
ACTION SHEET NO. <i>—</i>			TEST NO. <i>17</i>	

EXCITATION ALONG <i>Z</i>	AXIS
GRMS INPUT <i>9.2</i>	
NON-OPERATING	
TEMP. <i>77</i>	°F
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION OF TEST <i>2.0</i>	MIN.
ACCEL. SERIAL NO. <i>NB 62</i>	
ACCEL. SENSITIVITY <i>—</i>	MV RMS GP
<i>2.698</i>	COL GP
ACCEL. SENSING <i>Z</i>	AXIS
ACCEL. LOCATION <i>A12</i>	
TAPER REEL NO. <i>012296</i>	
SPECIAL CONDITIONS <i>QUAL Level 1</i> <i>COMP. PKG.</i> <i>ITEM P Resonance</i>	
REPORT NO.	

SPECTRAL DENSITY G²/HZ

C143

224<

01

PAGE NO.

VAR
BW

10 100 150

500

1000


1500

2000

FREQUENCY HZ

25 CPS BANDWIDTH

RIG 26	OPERATOR E.M.	PLOTTED BY S.M.	TRACE NO. 24	TEST NO. 17
TEST ENGINEER S.M.		CHECKED BY T.G.		DATE 4-19-72
				TIME 1015



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER NB62	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY MV RMS 2.698 GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 12.14 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °
TAPE REEL NO. 012296	
<input checked="" type="checkbox"/> CONTROL <input type="checkbox"/> RESPONSE	
PICKUP LOCATION A1Z	
HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 74872-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. 154	PHASE VCPS AND SPACECRAFT	PAGE NO. —

**Hamilton
Standard**


**U
A**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.

RIG 26	OPERATOR B.M.	PLOTTED BY S.M.	TRACE NO. 25	TEST NO. 17
TEST ENGINEER S.M.	CHECKED BY T.G.	DATE 4-9-72	TIME 1015	




INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER TG75	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 2.791 MV RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN. 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 11.34 g^2 F.S. HZ	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION B_z HUB HOOK-UP # 3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL	
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 1 & 4	PHASE VCPS	RANDOM —	PAGE NO.

226<

C145


RIG 26	OPERATOR B.M.	PLOTTED BY S.M.	TRACE NO. 26	TEST NO. 17
TEST ENGINEER S.M.		CHECKED BY T.G.	DATE 4-19-72	TIME 1015



INPUT LEVEL 9.2 GRM	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER XM21	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY MV RMS 1.370 GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 1	
TIME CONSTANT - SEC 1	
ANAL. CALIBRATION 47.08 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION DZ REA MOUNT Hook-up #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 15'4	PHASE VCPS AND SPACECRAFT	PAGE NO.


RIG 26	OPERATOR B. M	PLOTTED BY S. M	TRACE NO. 27	TEST NO. 17
TEST ENGINEER S. M		CHECKED BY T. G.		DATE 4-19-72
				TIME 1015



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER Y120	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 1.596 MY RMS GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 34.69 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION EZ	
TANK MOUNT	
HOOKUP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	PAGE NO.

RIG 26	OPERATOR MICKET	PLOTTED BY S.M.	TRACE NO. 32	TEST NO. 17
TEST ENGINEER S.M.		CHECKED BY T.G.	DATE 4-19-72	TIME 1015



INPUT LEVEL 9.2 GRI	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER WF75	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 1.001 MV RMS	GP COL GP
ANAL FILTER - HZ B.V. 6	
SWEEP SPEED - OCT/M 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 995.2 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 M	
NON OPERATING	TEMP. 74
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPON	
PICKUP LOCATION FZ	
LATCH VALVE MT	
HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM RAE-B	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 134	PHASE VCPS AND SPACECRAFT —	PAGE NO.

**Hamilton
Standard**


**U
A**
DIVISION OF UNITED AIRCRAFT CORPORATION

**RANDOM VIBRATION TEST
ANALYSIS METHOD B**

HSF-1635 B

REPORT NO.


RIG 26	OPERATOR B.M.	PLOTTED BY S.M.	TRACE NO. 33	TEST NO. 17
TEST ENGINEER S.M.		CHECKED BY T.G.		DATE 4-19-72
TIME 1015				



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER XN32	
ACCEL SENSING AXIS Z	
ACCEL SENSITIVITY 1.261	MV RMS
GP —	
COL —	
GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN —	
TIME CONSTANT - SEC —	
ANAL. CALIBRATION 627.1 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION GZ JUNCTION BOX MT HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED.	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL	
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE AND VCPS SPACECRAFT	RANDOM —	PAGE NO.


RIG 26	OPERATOR MICKET	PLOTTED BY S.M	TRACE NO. 34	TEST NO. 17
TEST ENGINEER S.M		CHECKED BY T.G	DATE 4-19-72	TIME 1015



INPUT LEVEL 9.2		GR
EXCITATION AXIS Z		
ACCEL SERIAL NUMBER XJ29		
ACCEL SENSING AXIS Z		
ACCEL SENSITIVITY 1.636		MV RMS
—		GP
—		COL
—		GP
ANAL FILTER - HZ B.V. 6		
SWEEP SPEED - OCT/M —		
TIME CONSTANT - SEC —		
ANAL. CALIBRATION 59.6 $\frac{g^2}{Hz}$ F.S.		
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END		
DURATION 2.0 M		
NON OPERATING	TEMP. 74	
TAPE REEL NO. 012296		
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE		
PICKUP LOCATION HZ		
PRESSURE TRANSDUC		
HOOK-UP #3		
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED		

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	PAGE NO. —

RIG 26	OPERATOR MICKET	PLOTTED BY S.M.	TRACE NO. 31	TEST NO. 17
TEST ENGINEER S.M.		CHECKED BY T.G.	DATE 4-19-72	TIME 1015




INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER TE 83	
ACCEL SENSING AXIS Y	
ACCEL SENSITIVITY 2.979 MV RMS	
GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 112.3 $\frac{g^2}{Hz}$ F.S.	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION AIY	
HOOK-UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND 1E4	NOTE VCPS AND SPACECRAFT	PAGE NO.

[REPORT NO.


RIG 26	OPERATOR B M	PLOTTED BY S. M	TRACE NO. 29	TEST NO. 17
TEST ENGINEER S. M		CHECKED BY T. G	DATE 4-19-72	TIME 1015



INPUT LEVEL	
9.2 GR	
EXCITATION AXIS	
Z	
ACCEL SERIAL NUMBER	
TD48	
ACCEL SENSING AXIS	
Y	
ACCEL SENSITIVITY	
MV RMS	
GP	
COL	
GP	
2.788	
ANAL FILTER - HZ B.V.	
6	
SWEEP SPEED - OCT/M	
TIME CONSTANT - SEC	
ANAL. CALIBRATION	
11.37 g^2 F.S.	
HZ	
PERIOD OF TEST	
<input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION	
2.0 M	
NON OPERATING	TEMP.
	74
TAPE REEL NO.	
012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION	
CY	
SPACECRAFT C.G.	
Hook-up #3	
SPECIAL CONDITIONS	
VCPS LOADED	
AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	FREQUENCY - MHz 10.000	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. 154	NOTE PHASE VCPS AND SPACECRAFT	RANDOM —	PAGE NO. 1


RIG 26	OPERATOR E.M.	PLOTTED BY E.M.	TRACE NO. 30	TEST NO. 17
TEST ENGINEER S.Y.		CHECKED BY T.G.	DATE 4-19-72	TIME 1015



INPUT LEVEL 9.2 GRMS	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER 7D40	
ACCEL SENSING AXIS X	
ACCEL SENSITIVITY 3.005 MV RMS	
GP COL GP	
ANAL FILTER - HZ B.W. 6	
SWEEP SPEED - OCT/MIN. 6	
TIME CONSTANT - SEC 6	
ANAL. CALIBRATION 110.4 8 ² F.S. HZ	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 MIN	
NON OPERATING	TEMP. 74 °F
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION AIX'	
Hook-up #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. NOTE 154	PHASE VCPS AND SPACECRAFT	PAGE NO.

RIG 26	OPERATOR MICKET	PLOTTED BY S.M	TRACE NO. 28	TEST NO. 17
TEST ENGINEER S.M		CHECKED BY T.G.	DATE 4-19-72	TIME 1015



INPUT LEVEL 9.2 GR	
EXCITATION AXIS Z	
ACCEL SERIAL NUMBER TD45	
ACCEL SENSING AXIS	
ACCEL SENSITIVITY MV RM 2.650 GP COL GP	
ANAL FILTER - HZ B. 6	
SWEEP SPEED - OCT/1	
TIME CONSTANT - SEC	
ANAL. CALIBRATION 12.58 $\frac{g^2}{Hz}$ F.S	
PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION 2.0 M	
NON OPERATING	TEMP. 74
TAPE REEL NO. 012296	
<input type="checkbox"/> CONTROL <input checked="" type="checkbox"/> RESPONSE	
PICKUP LOCATION CX	
SPACECRAFT C.G	
HOOK UP #3	
SPECIAL CONDITIONS VCPS LOADED AND PRESSURIZED	

PROJECT RAE-B	ITEM VCPS	CODE SV 748720-1	SERIAL NUMBER 00001	TYPE OF TEST QUAL
SPEC. AT-VCPS	PARA. 4.3.7	AMEND. N=7F 15.4	PHASE VCPS AND SPACECRAFT	RANDOM —
				PAGE NO.

Section V

Logs

- A) Operator Log
- B) Instrumentation Master & Running Log
- C) Data Reduction Log



**Hamilton, Standard,
Windsor Locks, Connecticut 06096**

SPACE & LIFE SYSTEMS LABORATORY

LOG OF TEST

 $\text{O}_2/\text{min.}$

TYPE OF TEST	TEST NO.	TEST DATE	TEST RESULT	TESTER
1	1	1/1/19	1	1
2	2	2/1/19	2	2
3	3	3/1/19	3	3
4	4	4/1/19	4	4
5	5	5/1/19	5	5
6	6	6/1/19	6	6
7	7	7/1/19	7	7
8	8	8/1/19	8	8
9	9	9/1/19	9	9
10	10	10/1/19	10	10
11	11	11/1/19	11	11
12	12	12/1/19	12	12
13	13	13/1/19	13	13
14	14	14/1/19	14	14
15	15	15/1/19	15	15
16	16	16/1/19	16	16
17	17	17/1/19	17	17
18	18	18/1/19	18	18
19	19	19/1/19	19	19
20	20	20/1/19	20	20
21	21	21/1/19	21	21
22	22	22/1/19	22	22
23	23	23/1/19	23	23
24	24	24/1/19	24	24
25	25	25/1/19	25	25
26	26	26/1/19	26	26
27	27	27/1/19	27	27
28	28	28/1/19	28	28
29	29	29/1/19	29	29
30	30	30/1/19	30	30
31	31	31/1/19	31	31
32	32	32/1/19	32	32
33	33	33/1/19	33	33
34	34	34/1/19	34	34
35	35	35/1/19	35	35
36	36	36/1/19	36	36
37	37	37/1/19	37	37
38	38	38/1/19	38	38
39	39	39/1/19	39	39
40	40	40/1/19	40	40
41	41	41/1/19	41	41
42	42	42/1/19	42	42
43	43	43/1/19	43	43
44	44	44/1/19	44	44
45	45	45/1/19	45	45
46	46	46/1/19	46	46
47	47	47/1/19	47	47
48	48	48/1/19	48	48
49	49	49/1/19	49	49
50	50	50/1/19	50	50
51	51	51/1/19	51	51
52	52	52/1/19	52	52
53	53	53/1/19	53	53
54	54	54/1/19	54	54
55	55	55/1/19	55	55
56	56	56/1/19	56	56
57	57	57/1/19	57	57
58	58	58/1/19	58	58
59	59	59/1/19	59	59
60	60	60/1/19	60	60
61	61	61/1/19	61	61
62	62	62/1/19	62	62
63	63	63/1/19	63	63
64	64	64/1/19	64	64
65	65	65/1/19	65	65
66	66	66/1/19	66	66
67	67	67/1/19	67	67
68	68	68/1/19	68	68
69	69	69/1/19	69	69
70	70	70/1/19	70	70
71	71	71/1/19	71	71
72	72	72/1/19	72	72
73	73	73/1/19	73	73
74	74	74/1/19	74	74
75	75	75/1/19	75	75
76	76	76/1/19	76	76
77	77	77/1/19	77	77
78	78	78/1/19	78	78
79	79			

Vib. Acc. I-Test

TEST ENGINEER

S. Mehmed

NAME OF RIG

२७
५

PROJECT & ENG. ORDER NO.

RAF-13

SHEET 1.

DATE: 12-72

30

SHEET 1.

DATE: 12-72

TEST PLAN NO. AT-VCPS

MODEL NO. RAE-B VCP2

PART NO. SVSK 79495

SERIAL NO.

OPERATORS P Jodoin

Run #	Time Start	Axis	mode	G's Peak	Scan Rate	Bare Fixture	Scan
3	1000	Z	Sine	1.0	4.0	Bare Fixture	Scan
4	1515	Y	Sine	1.0	4.0	Bare Fixture	Scan
5	1540	Y	Sine	1.0	4.0	Bare Fixture	Scan
4-14	1010	X	Sine	1.0	4.0	"	"
7	1120	X	Sine	1.0	4.0	"	"

REMARKS:

3648

Run #	Time Start	Axis	mode	G's Peak	Scan Rate	TP	G Rms	Time in min
2	1410	X	Sine	1.0	4.0	43.7		
3	1420	X	Sine	7.5	4.0	43.7		
5	1545	Y	Sine	7.5	4.0	43.7		
7	1145	Y	Sine	3.0	4.0	43.7		
9	1700	Y	Rand	9.2	-	43.7	9.2	2.0 *
10	0650	X	RAND	-	-	43.7	9.2	2.0 * H ₀ #1
11	0715	X	Sine	1.5	4.0	43.7	-	H ₀ #1
13	1650	Z	Sine	1.0	4.0	43.7		H ₀ #3
14	1705	Z	Sine	10.0	4.0	43.75		H ₀ #3
15	0905	Z	Sine	1.0	4.0			H ₀ #3
16	0930	Z	Sine	6.8	4.0	43.75		H ₀ #3
17	1015	Z	RAND	-	-	43.75	9.2	2.0 H ₀ #3

200-2000 Hz VQPS ONLY
200-2000 Hz VQPS ONLY
5-200 Hz COMPLETE PKG.
← Witnessed: 4-17-72
interviewed Mr. [Signature] 4-19-72

REMARKS.

* Random, Complete PKG.

3647

VIBRATION TEST LOG

PROJECT **RAE-B**
TEST TITLE **Qual**

ITEM **VCPS**

S/N **00001**
ENGINEER **MEHMET**

DATE **4/15/72**

MASTER PAGE NO. **1775**
LOG PAGE NO. **1998**
OPERATOR **Jordan/Mickel**

RUN NO	TIME	TEST CODE	PREAMPLIFIER SETTINGS												VIB AXIS	INPUT LEVEL	SCAN RATE GCT/MIN	COMP SPEED	CONTROL FILTER	TAPE		VIS-CORDER SPEED	RFG	REMARKS					
			1	2	3	4	5	6	7	8	9	10	11	12						SPEED	TIME MIN								
4-15-72 01	0930	CAI	1000	1000	1000	1000	1000	1000	100	100	100	100		100	-	-	-	-	-	15	1.0	-	26	1.0 VPK CAL @ 200 HZ CH # 1 TO 6 HU #1 200 MV RAS @ 200 HZ CH # 7 TO 12					
1	2	1410	RUN	10	3	10	10	-	-	50	20	20	50	A	50	X	1G	4.0	VAR	10/100/200	1	1.0	-		ITEM/FIXTURE SCAN 200-2000 HZ HOOK-UP #1 PRESSURE RECORDED ON SANDBORN. VCPS ONLY				
2	3	1420	RUN	30	10	100	30	-	-	100	50	50	100	C	50	X	7.5G	4.0	VAR	10/100/200	P	1.0	-		QUAL LEVEL * HIGH RESPONSE ON CHAN #4 & 10. VCPS ONLY				
5	4	1500	CAL	1000	1000	1000	1000	1000	1000	-	-	-	-	G	-	-	-	-	-		1.0	-			1.0 VPK CAL @ 200 HZ FOR CHANNEL N# 3 AND 4 HOOK-UP N# 2				
1	5	1545	RUN	10	30	100	30	-	-	100	50	50	100	G	50	Y	7.5G	4.0	VAR	10/100/200	1.0	1.0	-		HOOK-UP N# 2 QUAL LEVEL 200-2000 HZ VCPS ONLY				
4-17-72 6	0910	CAI	1000	1000	1000	1000	1000	1000	-	-	-	-		1	-	-	-	-	-	MED	1.3	-			1.0 VPK CAL @ 200 HZ CH # 1 TO 6 FOR ALL CHANNELS RESONANCE SEARCH HU #2				
6A		RESONANCE RUN	10	10/3	30	30	10	10/3/10	30	20	20	50	A	50	Y	2.10G TO 1.40G	MANUAL	VAR	10	BAND	9.5	-							
7	1145	RUN	10	10	30	30	10	10	50	20	20	50		50	Y	3.0	4.0	VAR	10/100/200		2.0	-			5/200 HZ QUAL LEVEL HU #2 CNTRL CH #2 COMPLETE PKG. ITEM PRESSURIZED				
9	1700	Run	10	30	10	30	10	10	50/20	50/20	50/20	50/20		50/20	Y	9.16 GRMS	-	-	-		3.0	-			Complete PKG, Item Pressurized Random Qual Run HU #2				
8A		Run	100	30	100	100	100	100	100	50	50	100		100		2.5 GRMS	-	-	-		11.0	-			Complete PKG. Item Pressurized Equalizing HU #2				
10	0650	RUN	30	30	30	30	10	10	50	50	50	50		50	X	9.16	-	-	-		2.0	-			COMPLETE PKG ITEM PRESSURIZED. EQUALIZATION TIME NOT NOTED. HU #1				
4-18-72 11	0715	RUN	10	10	30	30	10	10	50	20	20	50		50	X	1.5	4.0	VAR	10/100/200		1.0	-			COMPLETE PKG ITEM PRESSURIZED QUAL SINCE HU #1				
12	1015	CAI	1000	1000	1000	1000	1000	1000	100	100	100	100		100	FOR Z	1.0 VPK 1-6 200 MV RAS 7-12	-	OUT	OUT		2.0	-			1.0 VPK @ 200 HZ CH # 1 TO 6 HU #2 200 MV RAS @ 200 HZ CH # 7 TO 12				
13		CAI	-	-	-	-	-	-	-	-	-	-		-	VOID N/R	200 MV RAS CH # 12	-	-	OUT			-			200 MV RAS @ 200 HZ FOR ALL CHANGE ON CH # 12 HU #3				
13	1650	RUN	3	3/10	3/10	3/10	-	-	50	50	50	50		50	Z	1.0g PK	4.0	VAR	10/100/200		1.0	0.2"/SEC			VCPS ONLY HU #3 PRESSURIZED				
14	1705	RUN	30	100	100	100	10	-	50	50	50	50		50	Z	10.9g PK	4.0	VAR	10/100/200		1.0	0.4"/SEC			VCPS ONLY HU #3 PRESSURIZED				
4-18-72 15	0905	Run	10	10	10	10	10	10	20	20	20	20		20	Z	1.0 G PK	4.0	VAR	10/100		2.0	.4"/SEC							
NEXT			SHEET #1998																									26	5/200 HZ ITEM/FIXTURE SCAN HU #3 COMP PKG. ITEM PRESSURIZED
			CHANGED ATTEN TO 20 @ 1/MIN.																										

VIBRATION TEST LOG

MASTER PAGE NO 1774

PROJECT RAE-B

ITEM VCPS

S/N

CODE

DATE 4-13-72

LOG PAGE NO. 1997

TEST TITLE Acceptance Test

ENGINEER S. Mehmed

OPERATOR P. Jodoin

[illegible]

DATE 4-13-72

MASTER VIBRATION LOG

MASTER PAGE NO 177

PROJECT RAE-B

ITEM VCPS

S/N

CODE

WPIA52-102-124A RIG 26

LOG PAGE NO. 1997

TEST TITLE ACCEPTANCE TEST

ENGINEER S. Mehmed

OPERATOR P. Jodoin

CH. NO.	MEASUREMENT			TRANSDUCER				FULL SCALE EQUIVALENT	VISICORDER		JUNCTION UNIT		RECORD AMP		PREAMP		LP. FILTER	TABLE		REMARKS	Armature	
	VARIABLE	UD/EF	LOC.	TYPE	S/N	EXCITE VOLTS	SENS		TRACE	G/INCH	SIGNAL ATTEN. CONDITIONER	S/N	TYPE	S/N	TYPE	S/N		HOOK UP #2 Y AXIS	HOOK UP #3 X AXIS			
1	Accel	Ca	A1Z	2226	NB62	CHARGE	2.698		1	10	10	1										
2	"	Ca	A1X	2226	TD40		2.805		2	10	10	2										
3	"	Ca	A1Y	2226	TE83		2.722		3	10	10	3										
4	"	Ca	A2Z	2226	TD44		2.773		4	10	10	4										
5	"	Ca	A3Z	2226	TG75		2.791		5	10	10	5										
6	"	Ca	A4Z	2226	WR11		2.956	H91 #1	6	10	10	6										
7	"	EF	A5Z	2215	VG57	VOLTS	10.886						TP-A 59	TP-A 20	OUT							
8																						
9																						
10																						
11	AC COLA																					
12																						

1	Accel	Ca	A1Z	2226	NB62		2.698		1	10	ATH.											
2	"	Ca	A1X	2226	TD40		2.805		2	10	10											
3	"	Ca	A1Y	2226	TE83		2.722		3	10	10											
4	"	Ca	A2Z	2226	TD44		2.773		4	10	10											
5	"	Ca	A3Z	2226	TG75		2.791		5	10	10											
6	"	Ca	A4Z	2226	WR11		2.956	CHANGED TO Y AXIS RUN #5	6	10	10											
7	Accel	EF	A5Z	2215	VG57	VOLTS	10.886	H91 #2														
8																						
9																						
10																						
11	AC COLA																					
12																						

1	Accel	Ca	A1Z	2226	NB62		2.698		1	10	ATH.											
2	"	Ca	A1X	2226	TD40		2.805	CHANGED TO A1X	2	10	10											
3	"	Ca	A1Y	2226	TE83		2.722		3	10	10											
4	"	Ca	A2Z	2226	TD44		2.773		4	10	10											
5	"	Ca	A3Z	2226	TG75		2.791		5	10	10											
6	"	Ca	A4Z	2226	WR11		2.956	H91 #3	6	10	10											
7	Accel	EF	A5Z	2226	VG57	VOLTS	10.886															
8																						
9																						
10																						
11	AC COLA																					
12																						

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".


Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top. A note says: "Sketch TEST HOOKUP".

Sketch of a circular armature with 12 points labeled A1Z through A12Z. A scribe line is drawn around the perimeter. A hook up #2 is indicated at the bottom. A hook up #3 is indicated at the top.



#6 CHANGED A1X TO THIS LOCATION, CALLED A1X'

DATE 4/15/72

MASTER VIBRATION LOG

MASTER PAGE NO 1773

PROJECT RAE-B

ITEM VCP5

S/N 00001 SV7487201 CODE

WPIA-51-103-101A RIG 26

LOG PAGE NO. 1998

TEST TITLE Qual

ENGINEER MR. MEHMED

OPERATOR JODDIA/MICLET

CH. NO.	MEASUREMENT				TRANSDUCER			FULL SCALE EQUIVALENT CAL ATT	VISICORDER		JUNCTION UNIT		RECORD AMP		PREAMP		LP. FILTER	REMARKS
	VARIABLE	UD/EF	LOC	TYPE	S/N	SENS VOLTS	CHARGE SENS		TRACE	G/INCH	SIGNAL CONDITIONER	S/N	TYPE	S/N	TYPE	S/N		
1	ACCEL	CA1	A1X'	2226	TD40	-	2.805	10	1	10								
2	"	CA2	A1Y	2226	TE83	-	2.722	10	2	10								
3	"	CA3	DX	2222	XM21	-	1.370	10	3	10								
4	"	CA4	EX	2222	WF75	-	1.051	10	4	10								
5	"	CA5	CX	2226	TD45	-	2.650	10	5	10								
6	"	CA6	CY**	2226	TE74	-	2.718	10	6	10	** CHANGE TO TD48, SENS 2.785 P/PK							
7	"	EF7	A1Z	2226	NB62	3.052	-	1										
8	"	EF8	DY	2222	YK20	1.523	-											
9	"	EF9	EY	2222	XN32	1.261	-											
10	ACCEL	EF10	BX	2226	TD44	3.035	-	50	7	10.0								
11	AC COLA			AC COLA			-			AC COLA								
12	ACCEL	EF11	BY	2226	WR11	3.016	-											
1	ACCEL	CA1	A1X'	2226	TD40		2.805	10	1	10								
2	"	CA2	A1Y	2226	TE83		2.722	10	2	10								
3	"	CA3	DX	2222	YK20		1.596	10	3	10								
	"	CA4	EY	2222	XN32		1.297	10	4	10								
	"	CA5	CX	2226	TD45		2.650	HU 10	5	10								
6*	"	CA6	CY	2226	TE74		2.718	#2 10	6	10	* CHANGED TO TD48 CHARGE SENS = 2.788 P/PK STARTING WITH RUN 6							
7	"	EF7	A1Z	2226	NB62	3.052												
8	"	EF8	DX	2222	XM21	1.325												
9	"	EF9	EX	2222	WF75	1.001												
10	ACCEL	EF10	BX	2226	TD44	3.035												
11	AC COLA			AC COLA														
12	ACCEL	EF11	BY	2226	WR11	3.016		20	7	10.0								
1	ACCEL	CA1	A1Z	2226	NB62	-	2.698	10	1	10								
2	ACCEL	CA2	BZ	2226	TE75	-	2.791	10	2	10								
3	ACCEL	CA3	DZ	2222	XM21	-	1.370	10	3	10								
4	ACCEL	CA4	EZ	2222	YK20	-	1.596	10	4	10								
5	ACCEL	CA5	CX	2226	TD45	-	2.650	HU 10	5	10								
6	ACCEL	CA6	CY	2226	TD48	-	2.788	10	6	10								
7	ACCEL	EF7	A1X'	2226	TD40	3.005	-	3	-	-								
8	ACCEL	EF8	A1Y	2226	TE83	2.979	-	-	-	-								
9	ACCEL	EF9	FZ	2222	WF75	1.001	-	10	7	10								
10	ACCEL	EF10	GZ	2222	XN32	1.261	-	10	8	10								
11	AC	COLA																
12	ACCEL	EF12	HZ	2222	XJ29	1.636	-	10	9	10	CHANGED TO RN81 STARTING W/RUN 13 *							
								20	9	100	RN81 VISI CAL DATA Loc HZ							

SKETCH TEST HOOKUP

REFERENCE PHOTO'S

* CHANGED TO TD48
CHARGE SENS = 2.788 P/PK
STARTING WITH RUN 6

CHANGED TO RN81 STARTING W/RUN 13 *
VISI SENS 1.328

RN81 VISI CAL DATA Loc HZ

SINUSOIDAL DATA REDUCTION LOG

RAE-B

MASTER PAGE NO. 1774 PROJECT QUAL TEST DATE 4-13-72 D.R. DATE 4-13-72
 TAPE REEL NO. 01997 ITEM FIXTURE VSK 79594 SERIAL NO. _____ W.P.I. A52-102-124A

CAL VOLTAGE 200 MVrms OR 1000 MVpk (AT 200 Hz)

TAPE REEL
012294

CALCULATION

$$\text{CALpt} = \frac{\text{RUN}}{\text{CAL}} \times \frac{\text{CAL VOLTAGE}}{\text{ACCEL SENS}} \quad \frac{\text{MVrms}}{\text{MVrms/Gpk}} \quad \text{OR} \quad \frac{\text{MVpk}}{\text{Coul Gpk}}$$

TRACE	RUN	CHAN	S/N ACCEL	SENS ACCEL	RUN/CAL ATT	(RUN/CAL) X VOLT (ACCEL SENS)	CAL/RUN LOG ATT	CAL/RUN RANGE ATT	CAL PT	F.S.
AIz 1	3	1	NB62	2.698	3 1000	3 2.698	20 20	1 1	1.12	1
IX 2		2	TD40	2.805	3 1000	3 2.805	20 20	1 1	1.07	1
IY 3		3	TE83	2.722	3 1000	3 2.722	20 20	1 1	1.10	1
IZ 4		4	TD44	2.773	10 1000	10 2.773	20 20	1 1	3.6	1
IZ 5		5	T675	2.791	10 1000	10 2.791	20 20	1 1	3.45	1
IZ 6		6	WR11	2.956	10 1000	10 2.956	20 20	1 1	3.4	1
IZ 7	✓	7	VG57	10.886	10 100	10/100 X 200 10.886	20 20	10 10	1.85	1
IZ 8	5	1			3 1000		20 20	10 1	1.12	1
IX 9		2			3 1000		20 20	10 1	1.07	1
IY 10		3			3 1000		20 20	10 10	1.10	1
IZ 11		4			3 1000	3/2.773	20 20	10 10	1.08	1
IZ 12		5			3 1000	3/2.791	20 20	10 1	1.07	1
IX 13		6			3 1000	3/2.956	20 20	10 10	1.02	1
IZ 14	✓	7	✓	✓	20 100	20/100 X 200 10.886	20 20	10 10	3.68	1
IZ 15	7	1			3 1000		20 20	10 1	1.12	1
X 16		2			3 1000		20 20	10 10	1.07	1
IY 17		3			3 1000		20 20	10 1	1.10	1
X 18		4			10 1000		20 20	10 10	3.6	1
IZ 19		5			3 1000		20 20	10 1	1.07	1
IX 20		6			3 1000		20 20	10 10	1.07	1
IX 21	✓	7	✓	✓	50 100	50/100 X 200 10.886	20 20	10 1	9.25	1

RANDOM DATA REDUCTION LOG

MASTER PAGE NO. 1775 PROJECT RAE-P TEST DATE 4-18-72 D.R. DATE

TAPE REEL NO. 012295 & 012296 ITEM VCR'S SERIAL NO. 0000 / W.P.I.

CAL VOLTAGE 200 MV_{rms} OR 1000MV_{pk} (AT 200Hz) DEG. OF FREE. 128

CALCULATION CONST. $3989 \frac{MV_{rms}^2 (Grms)^2}{HZ (Gpk)^2}$ OR $9.82(10)^4 \frac{MV_{pk}^2 (Grms)^2}{HZ (Gpk)^2}$ Based on E.BW=6.4

CALCULATION CONST. ~~1595.6 OR 5.928 (10)⁴ Based on E.BW=16~~

TRACE	RUN	CHAN	S/N ACCEL	SENS. ACCEL	RUN/CAL ATT.	(RUN/CAL) ² (ACCEL SENS) ²	CAL/RUN INPUT ATT.	CAL/RUN OUTPUT ATT.	CAL PT	F
9 DX 9	8	YK20	1.523	25	100	$\frac{4 \times 10^{-2}}{(1.523)^2}$	20 (3)	10 (3)	68.78	1
10 EX	9	XN32	1.261	20	100	$\frac{4 \times 10^{-2}}{(1.261)^2}$	20 (3)	10	100.3	1
11 BX	10	TD44	3.035	20	100	$\frac{4 \times 10^{-2}}{(3.035)^2}$	20 (3)	20	17.32	1
12 CY	12	WR11	3.016	20	100	$\frac{4 \times 10^{-2}}{(3.016)^2}$	20 (3)	30	17.54	1
13 AY	1	TD40	2.805	30	1000	$\frac{9 \times 10^{-4}}{(2.805)^2}$	20 (4)	30 (4)	11.23	1
14 AY	2	TE83	2.722	30	1000	$\frac{9 \times 10^{-4}}{(2.722)^2}$	10 (5)	10 (5)	11.92	1
15 DX	3	X121	1.370	30	1000	$\frac{9 \times 10^{-4}}{(1.37)^2}$	20 (5)	20 (5)	47.08	1
16 EX	4	WF75	1.051	30	1000	$\frac{9 \times 10^{-4}}{(1.051)^2}$	20 (6)	10	80.01	1
17 CX	5	TD45	2.650	10	1000	$\frac{1 \times 10^{-4}}{(2.650)^2}$	10 (8)	20	1.398	1
18 CY	6	TD48	2.788	10	1000	$\frac{1 \times 10^{-4}}{(2.788)^2}$	10 (7)	10	1.263	1
19 AY	7	NB62	3.052	50	100	$\frac{.25}{(3.052)^2}$	20 (6)	10	107.06	1
20 DY	8	YK20	1.523	50	100	$\frac{.25}{(1.523)^2}$	20 (5)	0	429.9	1
21 EY	9	XN32	1.261	50	100	$\frac{.25}{(1.261)^2}$	20 (2)	0	627.1	1
22 BX	10	TD44	3.035	50	100	$\frac{.25}{(3.035)^2}$	20 (2)	10	108.26	1
23 CY	12	WR11	3.016	50	100	$\frac{.25}{(3.016)^2}$	20 (2)	0	109.63	1
DATA - ACCEL										
FBI LAB										

RANDOM DATA REDUCTION LOG

MASTER PAGE NO. 1775 PROJECT RAE-B TEST DATE 4-18-72 D.R. DATE _____

TAPE REEL NO. 012296 ITEM VCPS SERIAL NO. 00001 W.P.I.

CAL VOLTAGE 200 MV_{rms} OR 1000MV_{pk} (AT 200Hz) DEG. OF FREE. 128

$$\text{CALCULATION CONST. } 3989 \frac{MV_{rms}^2 (\text{Grms})^2}{\text{HZ} (\text{Gpk})^2} \quad \text{OR} \quad 9.82(10)^4 \frac{MV_{pk}^2 (\text{Grms})^2}{\text{HZ} (\text{Gpk})^2} \quad \text{Based on E.BW}=6.4$$

CALCULATION CONST. ~~1595.6~~ OR ~~3.928 (10)⁴~~ Based on E.BW-16

TRACE	RUN	CHAN	S/N ACCEL	SENS. ACCEL	RUN/CAL ATT.	(RUN/CAL) ² (ACCEL SENS) ²	CAL/RUN INPUT ATT.	CAL/RUN OUTPUT ATT.	CAL PT	F.S.
24	17	1	NB62	2.698	30 1000	$\frac{9 \times 10^{-4}}{(2.698)^2}$	10 (9) 25	0 25	12.14	1.0
25	✓	2	TG75	2.791	30 1000	$\frac{9 \times 10^{-4}}{(2.791)^2}$	10 (8) 25	0 10	11.34	1.0
26	✓	3	XM21	1.370	30 1000	$\frac{9 \times 10^{-4}}{(1.370)^2}$	20 (5) 25	0 25	47.08	1.0
27	✓	4	YK20	1.596	30 1000	$\frac{9 \times 10^{-4}}{(1.596)^2}$	20 (2) 25	0 20	34.69	1.0
28		5	TD45	2.650	30 1000	$\frac{9 \times 10^{-4}}{(2.650)^2}$	10 (8) 10 (8)	0 20	12.58	1.0
29		6	TD48	2.788	30 1000	$\frac{9 \times 10^{-4}}{(2.788)^2}$	10 (8) 0	0 10	11.37	.1
30		7	TD40	3.005	50 100	$\frac{.25}{(3.005)^2}$	20 (6) 0	0 20	110.4	.01
31	✓	8	TE83	2.979	50 100	$\frac{.25}{(2.979)^2}$	20 (6) 0	0 20	112.3	.01
32	✓	9	WF75	1.001	50 100	$\frac{.25}{(1.001)^2}$	20 (6) 10	0 20	995.2	1.0
33	✓	10	XV32	1.261	50 100	$\frac{.25}{(1.261)^2}$	20 (2) 10	0 10	627.1	1.0
34	✓	12	XJ29	1.636	20 100	$\frac{.04}{(1.636)^2}$	20 (5) 10	0 10	59.6	1.0

RANDOM DATA REDUCTION LOG

MASTER PAGE NO. 1775 PROJECT RAE-B TEST DATE 4/17/72 D.R. DATE 4/17/72
T. & REEL NO. 012295 ITEM VCPS SERIAL NO. 00001 W.P.I. AS2-102-121

CAL VOLTAGE 200 ~~mV~~ rms OR 1000MV_{pk} (AT 200Hz) DEG. OF FREE. 1.28

CALCULATION CONST. $3989 \frac{MV^2 (Gms)^2}{HZ (Gpk)^2}$ OR $9.82(10)^4 \frac{MV^2_{pk} (Gms)^2}{HZ (Gpk)^2}$ Based on $E.BW=6.4$

CALCULATION CONST. 1595.6 OR $3.928 (10)^4$ Based on E.BW=16

[illegible]

SINUSOIDAL DATA REDUCTION LOG

MASTER PAGE NO. 1775 PROJECT RAE-B TEST DATE 4-15/4-17 D.R. DATE _____
 TAPE REEL NO. 012295 ITEM VCPS SERIAL NO. 00001 W.P.I. AS1-103-101A

CAL VOLTAGE 200 MVrms OR 1000 MVpk (AT 200 Hz)

CALCULATION USE RUN #1 OR 6 FOR CAL, MU#1 & #2 RESPECTIVELY. FOR CHANNEL #1-6
 CAL FOR #1 FOR CHAN 7-12

CALpt = $\frac{\text{RUN}}{\text{CAL}} \times \frac{\text{CAL VOLTAGE}}{\text{ACCEL SENS}}$ OR $\frac{\text{MVrms}}{\text{MVrms/Gpk}}$ OR $\frac{\text{MVpk}}{\text{Coul Gpk}}$

TRACE	RUN	CHAN	S/N ACCEL	SENS ACCEL	RUN/CAL ATT	(RUN/CAL) x CAL PT (ACCEL SENS)	CAL/RUN LOG ATT	CAL/RUN RANGE ATT	CAL PT	F.S.
1	3	1	TD40	2.805	30/1000	30/2.805	20/20	1	10.7	10.0
2		2	TE83	2.722	10/1000	10/2.722	20/20	1	3.68	1.0
3		3	XM21	1.370	100/1000	100/1.370	20/20	1/1	73	100/10/1
4		4	WF75	1.051	30/1000	30/1.051	20/20	1	30	10/1
5		7	NB62	3.052	100/100	200/3.052	20/0	10	65.7	1.0
6		8	YK20	1.523	50/100	100/1.523	20/20	10	65.5	10/1.0
7		9	XN32	1.261	50/100	100/1.261	20/0/20	10	79.5	1.0/10/1.0
8		10	TD44	3.035	100/100	200/3.035	20/20	10/1	66.6	100/1.0
9	✓	12	WR11	3.016	50/100	100/3.016	20/20	10	33.2	1.0
10	✓	5	TD40	2.805	10/1000	10/2.805	20/20	10	3.58	1.0
11	✓	2	TE83	2.722	30/1000	30/2.722	20/20	10	11	10
12	✓	3	YK20	1.596	100/1000	100/1.596	20/20	10/1	62.9	100/10/1.0
13	✓	4	XN32	1.297	30/1000	30/1.297	20/20	10	23.2	10/1.0
14	✓	7	NB62	3.052	100/100	200/3.052	20/0	10	65.7	1.0
15	✓	8	XM21	1.325	50/100	100/1.325	20/20	10	75.8	10.0
16		9	WF75	1.001	50/100	100/1.001	20/0/20	10	100	1.0/10/1.0
17	✓	10	TD44	3.035	100/100	200/3.035	20/20	10	66.6	10.0/1.0
18	✓	12	WR11	3.016	50/100	100/3.016	20/20	10	33.2	10.0

SINUSOIDAL DATA REDUCTION LOG

MASTER PAGE NO. 1775 PROJECT RAE-B TEST DATE 4-15/4-19 D.R. DATE _____

TAPE REEL NO. 012295 ITEM VCPS SERIAL NO. 00001 W.P.I. A51-103-

CAL VOLTAGE 200 MVrms OR 1000 MVpk (AT 200 Hz)
USE CAL RUN #1 OR 6 FOR HU #1 & 2 RESPECTIVELY FOR channel #1-6

CALCULATION CAL RUN #1 for CH 7-12

$$\text{CALpt} = \frac{\text{RUN}}{\text{CAL}} \times \frac{\text{CAL VOLTAGE}}{\text{ACCEL SENS}} \quad \frac{\text{MVrms}}{\text{MVrms/Gpk}} \quad \text{OR} \quad \frac{\text{MVpk}}{\text{Coul Gpk}}$$

HU#2	TRACE	RUN	CHAN	S/N ACCEL	SENS ACCEL	RUN/CAL ATT	(RUN/CAL) x CAL VOLTAGE (ACCEL SENS)	CAL/RUN LOG ATT	CAL/RUN RANGE ATT	CAL PT	F.S.
AIX	19V	7	1	TD40	2.805	10/1000	10/2.805	20	1	3.58	.1
AIX	20	1	2	TE83	2.722	10/1000	10/2.722	20	1	3.68	.1
DX	21V	3	3	YK20	1.596	30/1000	30/1.596	20	1	18.8	10.0/1
EX	22V	4	4	XN32	1.297	30/1000	30/1.297	20	1	23.2	10.0/1
CX	23V	5	5	TD45	2.650	10/1000	10/2.650	20	1	3.77	.1
CY	24V	6	6	TD48	2.788	10/1000	10/2.788	20	1	3.6	1.0/1
AIX	25V	7	7	NB62	3.052	50/100	100/3.052	20	10	33.2	1.0
DX	26V	8	8	XN21	1.325	20/100	40/1.325	20	10	30.5	1.0
EX	27V	9	9	WF75	1.001	20/100	40/1.001	20	10	40	1.0/1
EX	28V	10	10	TD44	3.035	50/100	100/3.035	20	10	33.4	1.0/1
EX	29V	12	12	WR11	3.016	50/100	100/3.016	20	10	33.3	1.0
AIX	30	11	1	TD40	2.805	10/1000		20	1	3.58	1.0
AIX	31	2	2	TE83	2.722	10/1000		20	1	3.68	.1
DX	32	3	3	XN21	1.370	30/1000	30/1.370	20	10	21.9	1.0
EX	33	4	4	WF75	1.051	30/1000	30/1.051	20	10	30	1.0
CX	34	5	5	TD45	2.650	10/1000	10/2.65	20	1	3.77	1.0
CX	35	6	6	TD48	2.788	10/1000		20	1	3.6	.1
AIX	36	7	7	NB62	3.052	50/100	100/3.052	20	10	33.2	1.0
DX	37	8	8	YK20	1.523	20/100	40/1.523	20	10	26.2	1.0/1
EX	38	9	9	XN32	1.261	20/100	40/1.261	20	10	31.7	1.0/1
EX	39	10	10	TD44	3.035	50/100	100/3.035	20	10	33.2	10
EX	40	12	12	WR11	3.016	50/100	100/3.016	20	10	33.4	1.0

MASTER PAGE NO. 1775 PROJECT RAE-B TEST DATE 4-19-72 D.R. DATE 4-21-72

TAPE REEL NO. 012296 ITEM VCPS SERIAL NO. 00001 W.P.I. 451-103-104

CAL VOLTAGE 200 MVrms OR 1000 MVpk (AT 200 Hz)

CALCULATION CAL RUN # 12

$$\text{CALpt} = \frac{\text{RUN}}{\text{CAL}} \times \frac{\text{CAL VOLTAGE}}{\text{ACCEL SENS}} \quad \frac{\text{MVrms}}{\text{MVrms/Gpk}} \quad \text{OR} \quad \frac{\text{MVpk}}{\text{Coul Gpk}}$$

TRACE	RUN	CHAN	S/N ACCEL	SENS ACCEL	RUN/CAL ATT	(RUN/CAL) x SENS (ACCEL SENS)	CAL/RUN LOG ATT	CAL/RUN RANGE ATT	CAL PT	F.S.
41	14	1	NB62	2.698	30/1000	30/2.698	20/20	1/1	11.3	10.0
42		2	TG75	2.791	100/1000	100/2.791	20/20	1/1	35.7	10.0
43		3	XM21	1.370	100/1000	100/1.37	20/20	10/1	73	10.0
44		4	YK20	1.596	100/1000	100/1.596	20/20	10/1	62.7	10.0/1.0
45		7	TD40	3.005	50/100	100/3.005	20/20	10/1	33.4	1.0
46		8	TE83	2.979	50/100	100/2.979	20/20	10/1	33.4	1.0
47		9	WF75	1.001	50/100	100/1.001	20/20	10/1	100	10.0
48		10	XN32	1.261	50/100	100/1.261	20/20	10/1	79.5	10.0/10.0
49	✓	12	XJ29	1.636	50/100	100/1.636	20/0	10/1	61.3	1.0
50	16	1	NB62	2.698	10/1000	10/2.698	20/20	1/1	3.72	1.0/10.0
51		2	TG75	2.791	30/1000	30/2.791	20/20	1/1	10.8	10/1.0
52		3	XM21	1.370	30/1000	30/1.37	20/20	10/10	21.9	10.0/1.0
53		4	YK20	1.596	30/1000	30/1.596	20/20	10/1	18.8	10.0/1.0
54		5	TD45	2.650	10/30	10/2.65	20/0	1/1	3.78	1.0/1.0
55		6	TD48	2.788	10/30	10/2.788	20/0	1/1	3.6	1.0/1.0
56		7	TD40	3.005	20/100	40/3.005	20/20	10/1	13.3	1.0/1.0
57		8	TE83	2.979	20/100	40/2.979	20/20	10/1	13.4	1.0/1.0
58		9	WF75	1.001	20/100	40/1.001	20/20	10/10	40	10/1.0
59		10	XN32	1.261	20/100	40/1.261	20/20	10/10	31.7	10.0/1.0
60	✓	12	XJ29	1.636	20/100	40/1.636	20/20	10/1	24.4	1.0/1.0

APPENDIX D

GSFC MASS PROPERTIES REPORT

V.C.P.S. MASS PROPERTIES

BALANCE

NOTE: ALL ANGLES ARE REFERENCED AS FOLLOWS. THE S/C +X AXIS IS DEFINED AS 0° . ANGLES INCREASE C.W. LOOKING DOWN ON THE TOP OF THE V.C.P.S.

A SINGLE BALANCE WT. WAS MOUNTED ON THE UPPER RIM OF THE VCPS INTERIOR STRUCTURE. THE WT. TOTALED 426 gm, WAS LOCATED 8.29" FROM THE GEOMETRIC CENTER OF THE VCPS, AND AT AN ANGLE OF 220° .

AFTER THE ADDITION OF THE ABOVE WT. THE RESIDUAL IMBALANCE LEVELS WERE DETERMINED TO BE AS FOLLOWS:

RESIDUAL IMBALANCE (LIGHT SPOTS)

	ZERO FUEL CONDITION	FULL FUEL CONDITION
STATIC	20.8 oz-in $\angle 62^\circ$	14.4 oz-in $\angle 15^\circ$
DYNAMIC	605.6 oz-in^2 $\angle 115^\circ$	454.2 oz-in^2 $\angle 123^\circ$



V.C.P.S. MASS PROPERTIES

WT, M.I., C.G., (ZERO FUEL CONDITION)

NOTE: ALL MEASUREMENTS MADE WITH BALANCE
WT ADDED



TOTAL WEIGHT = 41.6 LBS.

SPIN M.I. = 1.703 SLUG-FT²

LATERAL #1^{*} MI = 0.925 SLUG-FT²

LATERAL #2^{*} MI = 0.883 SLUG-FT²


C.G. LOCATION = 4.33" (FORWARD OF THE AFT)
(SEPARATION INTERFACE)



V.C.P.S. MASS PROPERTIES

WT, M.I., C.G., (FULL FUEL CONDITION)

NOTE: ALL OF THE VALUES FOR THE FULL FUEL CONDITION WERE OBTAINED BY ANALYTICALLY ADDING 45 LBS OF HYDRAZINE TO THE ZERO FUEL CONDITION. IT WAS ASSUMED THAT ALL OF THE FUEL WAS LOCATED IN THE TANKS.



THIS CREATES A SLIGHT ERROR DUE TO THE PRESENCE OF A CERTAIN AMOUNT OF FUEL IN THE FEED LINES.


TOTAL WEIGHT = 86.6 LBS.

SPIN M.I. = 7.2 SLUG-FT²

LATERAL #1 M.I. = 3.7 SLUG-FT²

LATERAL #2 M.I. = 3.7 SLUG-FT²

C.G. LOCATION = 5.11" (FORWARD OF THE AFT SEPARATION INTERFACE)



APPENDIX E


SVHSER 6184 - RAE-B

GAS MANIFOLD MODIFICATION REPORT

RAE-B VCPS GAS MANIFOLD


MODIFICATION REPORT

Prepared by:



E. K. Moore
RAE-B Project Manager

Approved by:



R. L. Steinberg
RAE-B Program Manager

Date:

15 March 1973

INTRODUCTION

This report summarizes the program undertaken by Hamilton Standard in response to contract change order #18 to modify the Radio Astronomer Explorer -B, Velocity Control Propulsion Subsystem (RAE-B, VCPS) to offset intertank transfer of fluids.

The need for such a modification was revealed during a Goddard Space Flight Center (GSFC) system analysis wherein it was shown that an initial minor VCPS fluid unbalance would ultimately cause major unbalance and vehicle Z axis perturbation.

The program at Hamilton Standard included a study of various methods to eliminate intertank transfer of fluids, the implementation of the selected system and acceptance testing to confirm system leakage and cleanliness integrity.

OBJECTIVE

To select and implement a method of preventing intertank transfer of fluids in the RAE-B VCPS with minimum impact on weight, reliability, schedule and the Propellant Servicing Cart (PSC) configuration.

CONCLUSIONS

1. A method was selected which did not require changes in basic loading and pressurizing procedures.
2. The method was implemented without sacrifice of system cleanliness or leakage as evidenced by acceptance testing.
3. Weight increase was minimal at plus 0.4 pounds.
4. The modification to the subsystem requires rebalancing and redetermination of mass properties.
5. The VCPS modification was accomplished within the time period allotted.

RECOMMENDATIONS

It is recommended that:

1. The VCPS be rebalanced and mass properties be redetermined by the NASA.
2. Liquid and gas loading procedures be reexamined including both vacuum and pressure fill methods.

DISCUSSIONI. Study Phase

A number of candidate methods to prevent intertank transfer of fluids were studied and were previously reported. See Appendix A, "RAE-B VCPS Intertank Propellant Transfer Modification Report". The report suggested either of two methods be used.

Method IV-B provided a weight saving but required new fluid and gas loading procedures. Method III added a small amount of weight but did not require new liquid and gas loading procedures. GSFC elected to use Method III.

II. Design Phase

The design requirements for implementing Method III, which utilizes four Fill and Vent Valves instead of a single Fill and Vent Valve, consisted of:

Establishing locations for four fill and vent valves so that; one common mounting bracket design could be used, pressurizing hoses could be installed without interference with each other or space vehicle components, weight increase was minimized and finally, unbalance was held to a minimum.

It was determined that two brackets and valves could be attached to the hub in quadrant + x-y and two in quadrant - x+y. In each quadrant the valves would face one another but be offset along the Z axis for hose clearance. The new gas lines from tanks to valves utilized existing arm mounted tube clamps to minimize new hardware and reduce hole drilling requirements. Page 2 of drawing SV748720 Appendix B, shows the new valve, bracket and gas line locations.

The new bracket is similar in design to other brackets, but is covered with aluminized mylar tape instead of gold plate as a procurement expediency. Drawing SV755431, Appendix B, shows the new valve bracket.

The bracket used to locate the original Fill and Vent Valve was left attached to the +x arm so that the arm would not have to be detached to remove the loose rivet segments from the interior of the arm which would have resulted if the bracket were removed.

III. Qualification Test Phase

The valve and bracket were assembled and subjected to a qualification test per specification SVHS 5997 (See Appendix C).

The valve which was planned to be used for the test was the VCPS spare (GFE) Fill and Vent Valve. This valve leaked excessively when tested and rather than delay testing pending disposition of the valve by GSFC, a new valve was substituted and the test resumed.

The qualification test was completed without incident except that the test unit was misindexed relative to the X-Y axis by 36°. Since the misindexing resulting in higher effective loadings to the test unit than the true position, GSFC agreed that the outage was acceptable.

The leaking valve was delivered to GSFC for failure analysis. The bracket was delivered to government stores as a VCPS spare and the qualification valve was installed as one of the four on the VCPS.

The qualification test report is in Appendix D.

IV. VCPS Modification Phase

The VCPS modification was accomplished in several steps:

1. Gas manifold removal
2. Bracket and valve installation
3. Tube fit-up, cleaning and passivation
4. Tube welding
5. In process inspection

Step 1. To accomplish gas manifold removal without system contamination, the following procedure was used for each tubing cut:

- a. Pressurize system to 5 psig using dry filtered nitrogen.
- b. Slowly cut tubing using "chipless" tube cutter.
- c. Install squaring tool and square end of cut tube using fine cut file.
- d. Ream tube I.D. and remove burrs.
- e. Remove squaring tool and flood area with clean Isopropyl Alcohol to remove all visible particles. Allow to dry.
- f. Tape tube end.

Step 2. The hub bracket mounting holes were drilled and burred using the following procedure:

- a. Remove insulation blanket from hub.
- b. Establish hole locations
- c. Set up shop vacuum to catch drill chips
- d. Drill and burr holes
- e. Assure all chips have been collected

After hole drilling and burring, the brackets were mounted to the hub, then the valves were mounted to the brackets using required bolts, washers and nuts. The brackets were taped with aluminized mylar tape before installation.

Step 3. After the valves had been installed, each tube which had been prebent to design layouts, was fitted and cut to length, following which it was cleaned to specification HS 3150 level CE-5. (See Appendix E for CE-5 level).

Following cleaning, the tubes and valves were passivated per note 68 of drawing SV748720 except pressure was 15 psia. The passivation procedure is as follows:

- a. One hour application of a 30-35% N_2H_4 - remainder H_2O solution at $73 \pm 10^\circ F$ with wetted interior portions of the tubes and valves completely filled.
- b. Fill completely as in step (a) with 100% N_2H_4 and attach an external ullage volume of 30 ± 2 cu. in. With the system vented, raise the temperature to $120 \pm 5^\circ F$. After 4 hours, close the vent and maintain temperature for 24 hours while monitoring pressure. Pressure rise shall not exceed 7 psid in 24 hours. Note: If pressure rise does exceed 7 psid, terminate test.

No pressure rise was observed in the 24 hour period.

Following passivation, tube cleanliness was again verified to the CE-5 level.

Step 4. Prior to tube welding, the tubes were taped with aluminized mylar to within approximately 1 1/2 inches of the tube ends. The tubes were then held in position by a fixture clamp at one end and by the Astro-Arc welding head at the other. Each weld was made automatically using previously established machine settings. Two weld samples were made prior to welding and two additional samples were made after all welding was complete. All weld samples were radiographically examined.

Step 5. Following welding, each of the eight welds was die penetrant inspected and "snoop" checked at 300 psig. The system was then checked for cleanliness per HS 3150 using isopropyl alcohol.

Finally the insulating blanket was reinstalled and the VCPS released for Acceptance Testing.

V. Acceptance Test Phase

Following the modifications and in-process inspections (Phase IV), the unit was acceptance tested per SVHS 5618 ATA No. 2 (See Appendix F). The acceptance test consisted of the following individual tests:

- Examination of Product
- Weight
- Proof Pressure
- External Leakage
- Contamination Check
- Post Test Inspection

Following completion of the contamination check, and before Post Test Inspection, taping with aluminized mylar tape was completed.

All tests were completed in accordance with acceptance criteria.

VI. Schedule

The VCPS was modified in accordance with the plan and schedule of Appendix G.

Hamilton
Standard

U
A[®]
DIVISION OF UNITED AIRCRAFT CORPORATION

APPENDIX

Intertank Propellant Transfer Modification Report

RAE-B VCPS

INTERTANK PROPELLANT TRANSFER MODIFICATION REPORT

PREPARED BY: Thomas Marotta
Thomas Marotta

Carl Arvidson
Carl Arvidson

APPROVED BY: Earl K. Moore
Earl K. Moore

CONTENTS

INTRODUCTION

SUMMARY

RAE-B VCPS PROPELLANT FEED SYSTEM
MODIFICATION TRADEOFF

FLOW ANALYSIS OF HS SELECTED
MODIFICATION

SUMMARY OF FLOW DEMONSTRATION TEST

INTRODUCTION

At the direction of NASA/Goddard Space Flight Center to modify the VCPS to prevent intertank propellant transfer, a study of various system modifications was undertaken to decide which changes would have the least impact (manufacturing, weight and cost) to the subsystem. Also, a flow analysis of the selected tank isolation methods was prepared to further substantiate the choice. This report includes both the various system tradeoffs and the flow analysis associated with the VCPS modifications.

SUMMARY

After reviewing the various modification options which could be incorporated on the VCPS, the analysis associated with modification Method IV-B, and the demonstration flow test, changing the VCPS propellant feed system to the configuration illustrated in the Method IV-B schematic appears to be the best approach for retrofitting the VCPS. This method offers the advantages of lighter weight and minimum impact on mechanical changes to the VCPS and GSE Cart.

The addition of individual fill and drain valves for each tank is also an acceptable approach but results in additional VCPS weight and a more complex VCPS rework. This approach, Method III, was not analyzed since the fill procedure is identical to that used for the present system except for manifolding the four pressurant fill and drain valves together. This permits simultaneous gas pressurization of the tanks from a single source on the GSE Cart.

RAE-B VCPS PROPELLANT FEED SYSTEM MODIFICATION TRADEOFF

The following propellant feed system schematics represent methods of accomplishing prevention of intertank propellant transfer. Each schematic modification has comments regarding the impact of the change to the VCPS, to the RAE-B spacecraft, or to the GSE.


After reviewing the various options available to prevent inter-tank propellant transfer, the subsystem modification which appears to offer the greatest advantages is Method IV-B. This change offers the least impact to the system while providing a subsystem of lighter weight. The second choice would be Method III where the use of RAE-B qualified hardware could be utilized with no restraints on the spacecraft other than additional weight of the VCPS. The flow analysis which is in the following section is for Method IV-B.

The weight impact of the two modification methods considered is as follows. The results are for the worst case which assumes the VCPS balance weight to be in the region of the existing gas manifold.

Delta Weight


Method IV-B	≈ .411 lbs reduction
Method III	≈ 1.18 lbs additional

PRESENT VCPS CONFIGURATION



INTERTANK ISOLATION CONFIGURATIONS

METHOD I




COMMENTS:

- VALVES ISOLATE TANKS ON GAS SIDE BUT PROVIDE NO REDUNDANCY
- NO VEHICLE POWER REQUIRED.
- NO EFFECT ON PROPELLANT FLOW.
- AVAILABILITY OF QUALIFIED VALVE IS QUESTIONABLE.
- SYSTEM WEIGHT INCREASE.

(V) VALVE (TYPE NOT ESTABLISHED)


METHOD II



COMMENTS:

- VALVES ISOLATE TANKS ON GAS SIDE AND PROVIDE REDUNDANCY.
- NO VEHICLE POWER REQUIRED.
- NO EFFECT ON PROPELLANT FLOW.
- AVAILABILITY OF QUALIFIED VALVE QUESTIONABLE.
- SYSTEM WEIGHT INCREASE.

METHOD III



COMMENTS:


- VALVES ISOLATE TANKS - NO POSSIBILITY OF INTERNAL LEAKAGE
- NO VEHICLE POWER REQUIRED.
- NO G.S.E. POWER REQ'D.
- NO EFFECT ON PROPELLANT FLOW.
- USE OF RAE-B QUALIFIED HARDWARE
- FOUR POTENTIAL OVERBOARD LEAK SOURCES
- SYSTEM WEIGHT INCREASES.

METHOD IV A & B

COMMENTS:

A & B • VCPS CANNOT BE THRU
FLUSHED, CLEANED OR
PURGED.

- NO VEHICLE OR GSE.
POWER REQUIRED.
- SYSTEM WEIGHT DECREASE
- FILL OF DEAD-ENDED
TANK CRITICAL SINCE
OVER PRESSURIZATION
CANNOT BE VENTED.
- GSE CART CANNOT LOAD
 $N_2 H_4$ UNDER REQUIRED
PRESSURE WITHOUT
CONSIDERABLE CART
MODIFICATION.
- DO TANKS LOAD EQUALLY?




A - LOAD $N_2 H_4$ UNDER PRESSURE.

B - LOAD $N_2 H_4$ UNDER LOW
PRESSURE - THEN PRESSURIZE
WITH N_2 TO OPERATING
PRESSURE.

METHOD V

COMMENTS:


- VALVES ISOLATE TANKS AND PROVIDE REDUNDANCY
- VEHICLE POWER REQUIRED
- ADDITIONAL TELEMETRY CHANNELS PROBABLY REQUIRED.
- IMPACTS SPACE CRAFT ELECTRICAL EQUIPMENT.
- FAILED CLOSED POSITION CAN CAUSE LOSS OF MISSION.
- VALVES HAVE THERMAL IMPACT ON LINE THERMAL ANALYSIS AND MAY REQUIRE HEATERS.
- SYSTEM WEIGHT INCREASES
- AVAILABILITY OF QUALIFIED VALVE IS QUESTIONABLE.



METHOD VI

COMMENTS:

- VALVES ISOLATE TANKS BUT PROVIDE NO REDUNDANCY.
- REMOVAL OF TWO EXISTING LATCHING VALVES FROM SYSTEM CHANGES ORIGINAL PHILOSOPHY OF SYSTEM.
- LATCHING VALVE CIRCUIT REQUIRES ADDITIONAL POWER.
- IMPACT ON SPACECRAFT ELECTRICAL EQUIPMENT
- FAILED CLOSED POSITION OF ANY LATCHING VALVE CAN CAUSE LOSS OF MISSION.
- VALVES HAVE THERMAL IMPACT ON LINE THERMAL ANALYSIS AND MAY REQUIRE HEATERS.
- SYSTEM WEIGHT INCREASE.



(LV) LATCHING VALVE

FLOW ANALYSIS OF HS SELECTED MODIFICATION

The flow analysis presented in this section is prepared against propellant feed system modification Method IV-B. The analysis is divided into the following three sections:

Propellant Fill

Pressurant Fill

Propellant Withdrawal

The primary objective of these analyses is to determine the unbalance effects, if any, on the VCPS.

The propellant fill case is not of primary concern other than assuring that propellant flows to all tanks equally with the exception of the line volume effects. The primary goal of the pressurant fill analysis is to determine the degree of unbalance that exists between propellant tanks after pressurant fill and the system pressure has stabilized -- equal pressure in all tanks. The objective of the propellant withdrawal analysis is to determine the propellant expulsion efficiency. Without the tank pressurant manifold, each tank blows down independently where it is possible for one tank to ingest pressurant just before the others because of slightly different initial pressurant volumes.

The analysis indicates that an unbalance of 13 oz-in may exist after propellant and pressurant loading without adjustment of the balance weight. To assure that the system does fill as predicted for Method IV-B, an evaluation of the fill process would be demonstrated using the actual VCPS. This would be accomplished by cutting into the pressurant manifold at discreet positions, which would not affect the final direction of the modification, and sealing off these lines.

The propellant "blow-down" analysis indicates that the expulsion efficiency will be 99.83 percent instead of 99.98 percent which was initially predicted.

CASE I - UNBALANCE DUE TO LIQUID FILLING




FIG. I

STATEMENT OF PROBLEM

THE PROBLEM IS TO DETERMINE ANY UNBALANCE RESULTING FROM INITIAL LIQUID FILL. THE PROBLEM STEMS FROM THE INITIAL GAS VOLUME IN THE TANKS AND PARTICULARLY IN THE SYSTEM LINES. DURING THE FILLING PROCESS, THE GAS IN THE LINES IS DISPLACED TO THE TANKS AND COMBINES WITH THE GAS ALREADY IN THE TANKS TO BECOME COMPRESSED. THE FACT THAT THE TANKS WILL HAVE A DIFFERENT AMOUNT OF GAS, BECAUSE OF THE DISTRIBUTION OF THE PLUMBING, WILL RESULT IN SOME PROPELLANT MASS UNBALANCE UPON PRESSURE EQUALIZATION IN THE SYSTEM

ANALYSIS

- ASSUME AT END CONDITIONS $P_9 = P_{10} = P_{11} = P_{12}$
- ASSUME THAT DURING LIQUID FILLING, VAPOR LIQUID INTERFACE IS MAINTAINED SUCH THAT GAS IN LINES IS COMPLETELY DISPLACED INTO THE TANKS. (ASSUMPTION VISUALLY CONFIRMED)

- ASSUME DISTRIBUTION OF GAS IN SYSTEM RESULTS AS FOLLOWS

$$\text{TANK 9: } \bar{V}_9 = 25\% V_{1-2} + V_{2-5} + V_{9, \text{INITIAL}}$$

$$\text{TANK 10: } \bar{V}_{10} = 25\% V_{1-2} + 33\% V_{2-3} + V_{3-6} + V_{10, \text{INITIAL}}$$

$$\text{TANK 11: } \bar{V}_{11} = 25\% V_{1-2} + 33\% V_{2-3} + 50\% V_{3-4} + V_{4-7} + V_{11, \text{INITIAL}}$$

$$\text{TANK 12: } \bar{V}_{12} = 25\% V_{1-2} + 33\% V_{2-3} + 50\% V_{3-4} + V_{4-8} + V_{12, \text{INITIAL}}$$

WHERE \underline{V} IS THE VOLUME ASSOCIATED WITH THE DIFFERENT COMPONENTS SHOWN IN FIG. I

A. • CONSIDER NOMINAL CASE
FROM TABLE I

$$\text{LINES } V_{1-2} = .4362 \text{ IN}^3$$

$$V_{2-5} = .8376 \text{ IN}^3$$

$$V_{2-3} = .1919 \text{ IN}^3$$

$$V_{3-6} = 1.0295 \text{ IN}^3$$

$$V_{3-4} = 1.1168 \text{ IN}^3$$

$$V_{4-7} = 1.0295 \text{ IN}^3$$

$$V_{4-8} = 1.0295 \text{ IN}^3$$

$$\text{TANKS } V_{9, \text{INIT}} = 508.90 \text{ IN}^3$$

$$V_{10, \text{INIT}} = 509.46 \text{ IN}^3$$

$$V_{11, \text{INIT}} = 508.63 \text{ IN}^3$$

$$V_{12, \text{INIT}} = 510.01 \text{ IN}^3$$

INITIAL GAS VOLUMES

$$\bar{V}_9 = (.25 \times .4362) + (.8376) + 508.90$$

$$\bar{V}_{10} = (.25 \times .4362) + (.33 \times .1919) + (1.0295) + 509.46$$

$$\bar{V}_{11} = (.25 \times .4362) + (.33 \times .1919) + (.50 \times 1.1168) + 1.0295 + 508.63$$

$$\bar{V}_{12} = (.25 \times .4362) + (.33 \times .1919) + (.50 \times 1.1168) + 1.0295 + 510.01$$

$$\therefore \bar{V}_9 = 509.847 \text{ IN}^3$$

$$\bar{V}_{10} = 510.662 \text{ IN}^3$$

$$\bar{V}_{11} = 510.390 \text{ IN}^3$$

$$\bar{V}_{12} = 511.770 \text{ IN}^3$$

$$\bar{V}_T = \text{TOTAL INITIAL GAS VOLUME IN SYSTEM} = \bar{V}_9 + \bar{V}_{10} + \bar{V}_{11} + \bar{V}_{12} = 2042.669 \text{ IN}^3$$

ASSUME INITIAL PRESSURE = 15 PSIA
OF SYSTEM

ASSUME ADDITION OF 45 lbs OF PROPELLANT TO THE SYSTEM

$$V_P = \frac{45}{\rho} = \frac{45 \text{ lbm}}{0.036 \frac{\text{lbm}}{\text{in}^3}} = 1250 \text{ in}^3$$

$$\therefore \text{FINAL GAS VOLUME OF SYSTEM} = \bar{V}_T - V_P$$

$$\bar{V}_{\text{FIN}} = 2042.669 - 1250 = 792.669 \text{ in}^3$$

ASSUME AN ISOTHERMAL FILL PROCESS

$$P_{\text{FINAL}} = \frac{P_{\text{INITIAL}} \times \bar{V}_T}{\bar{V}_{\text{FIN}}}$$

$$P_{\text{FINAL}} = \frac{15 \times 2042.669}{792.669} = 38.654 \text{ PSIA}$$

WITH THIS FINAL PRESSURE IN EACH TANK, DETERMINE THE FINAL GAS VOLUMES IN EACH TANK:

GAS VOLUMES, FINAL

$$V_9 = \frac{15 \times 509.847}{38.654} = 197.850 \text{ in}^3$$

$$V_{10} = \frac{15 \times 510.662}{38.654} = 198.164 \text{ in}^3$$

$$V_{11} = \frac{15 \times 510.390}{38.654} = 198.061 \text{ in}^3$$

$$V_{12} = \frac{15 \times 511.770}{38.654} = 198.594 \text{ in}^3$$

TANK PROPELLANT VOLUMES, FINAL

$$V_{P9} = 508.90 - 197.850 = 311.050 \text{ in}^3$$

$$V_{P10} = 509.46 - 198.164 = 311.296 \text{ in}^3$$

$$V_{P11} = 508.63 - 198.061 = 310.569 \text{ in}^3$$

$$V_{P12} = 510.01 - 198.594 = 311.416 \text{ in}^3$$

MASS OF PROPELLANT IN TANKS


$$M_9 = 11.1978 \text{ lbs}$$

$$M_{10} = 11.2066 \text{ lbs}$$

$$M_{11} = 11.1804 \text{ lbs}$$

$$M_{12} = 11.2109 \text{ lbs}$$

LOOK AT SYSTEM UNBALANCE DUE TO THE ABOVE PROPELLANT DISTRIBUTION - ASSUME A BALANCED DRY SYSTEM



C.G. SHIFT

$$\bar{Y} = \frac{(11.2109 - 11.1978) \times 23.5}{65}$$

$$\bar{Y} = +.00473$$

$$\bar{X} = \frac{(11.2066 - 11.1804) \times 23.5}{65}$$

$$\bar{X} = +.00946 \text{ in}$$

TORQUE DUE TO C.G. SHIFT:

$$T = \text{Mass}_{\text{sys}} \times \sqrt{\bar{X}^2 + \bar{Y}^2}$$

$$T = 65 \text{ lbs} \times \frac{1603}{16} \times \sqrt{.00473^2 + .00946^2} = 65 \times 16 \times .0105$$

$$T = 11.00 \text{ IN-OZ}$$

280<

B. CONSIDER AN EXTREME CASE, WHERE THE

TOLERANCES OF THE TANKS & LINES ARE
IN A CONDITION THAT WILL MAKE THE
UNBALANCE A MAXIMUM. INVESTIGATE EFFECT
OF HAVING LINES IN MIN & MAX CONDITION

ASSUME THE FOLLOWING ~ (APPARENT WORST CONDITION)

V₂₋₅ IS MAXIMUM

V₃₋₆ = MINIMUM

V₁₋₂ IS NOMINAL

V₂₋₃ IS NOMINAL

V₃₋₄ IS MINIMUM

V₄₋₇ IS MAXIMUM

V₄₋₈ IS MINIMUM

V_{9,INIT}

V_{10,INIT}

V_{11,INIT}

V_{12,INIT}

ACTUALS

• FROM TABLE I

$$V_{2-5 \text{ max}} = .9741 \text{ IN}^3$$

$$V_{3-6 \text{ min}} = .8841 \text{ IN}^3$$

$$V_{1-2 \text{ nom}} = .4362$$

$$V_{9, \text{IN}} = 508.90 \text{ IN}^3$$

$$V_{2-3 \text{ nom}} = .1919$$

$$V_{10, \text{IN}} = 509.46 \text{ IN}^3$$

$$V_{3-4 \text{ min}} = .9583$$

$$V_{11, \text{IN}} = 508.63 \text{ IN}^3$$

$$V_{4-7 \text{ max}} = 1.1973$$

$$V_{12, \text{IN}} = 510.01 \text{ IN}^3$$

$$V_{4-8 \text{ min}} = .8841$$

GAS VOLUME BEFORE LIQUID FILLING

$$\text{TANK 9 } \bar{V}_9 = (.25 \times .4362) + (.9741) + 508.90 = 509.983 \text{ IN}^3$$

$$\text{" 10 } \bar{V}_{10} = (.25 \times .4362) + (.33 \times .1919) + .8841 + 509.46 = 510.516 \text{ IN}^3$$

$$\text{" 11 } \bar{V}_{11} = (.25 \times .4362) + (.33 \times .1919) + (.50 \times .9583) + 1.1973 + 508.63 = 510.516 \text{ IN}^3$$

$$\text{" 12 } \bar{V}_{12} = (.25 \times .4362) + (.33 \times .1919) + (.50 \times .9583) + .8841 + 510.01 = 511.016 \text{ IN}^3$$

$$\bar{V}_T = \text{TOTAL INITIAL GAS VOLUME IN SYSTEM} = 2042.523 \text{ IN}^3$$

ASSUME INITIAL PRESSURE OF SYSTEM = 15 PSIA

AFTER ADDING 45 LBS PROPELLANT WHAT IS GAS VOL

$$V_{g \text{ FINAL}} = 2042.523 - \frac{45}{.036} = 792.523 \text{ IN}^3$$

FINAL PRESSURE IN EACH TANK

$$P_{\text{FINAL}} = \frac{15 \times 2042.523}{792.523} = 38.659 \text{ PSIA}$$

TANK GAS VOLUMES, FINAL

$$V_9 = \frac{15 \times 509.983}{38.659} = 197.887 \text{ in}^3$$

$$V_{10} = \frac{15 \times 510.516}{38.659} = 198.084$$

$$V_{11} = \frac{15 \times 510.479}{38.659} = 198.069$$

$$V_{12} = \frac{15 \times 511.545}{38.659} = 198.483$$

TANK PROPELLANT VOLUMES, FINAL

$$V_{p9} = 508.90 - 197.887 = 311.013 \text{ in}^3$$

$$V_{p10} = 509.46 - 198.084 = 311.376$$

$$V_{p11} = 508.63 - 198.069 = 310.561$$

$$V_{p12} = 510.01 - 198.483 = 311.527$$

MASS OF PROPELLANT IN EACH TANK


$$M_9 = 11.1964 \text{ lbm}$$

$$M_{10} = 11.2095 \text{ lbm}$$

$$M_{11} = 11.1802 \text{ lbm}$$

$$M_{12} = 11.2149 \text{ lbm}$$

LOOK AT C.G. SHIFT & UNBALANCE



C. G SHIFT

$$\bar{Y} = \frac{(11.2149 - 11.1969) \times 23.5}{65} = +.00668$$

$$\bar{X} = \frac{(11.2095 - 11.1802) \times 23.5}{65} = +.01059$$

STATIC UNBALANCE (.0125)

$$T = 65 \times 16 \sqrt{.00668^2 + .01059^2} = \underline{\underline{13.024 \text{ IN-OZ}}}$$

CONCLUSION: THE STATIC UNBALANCE RESULTING FROM THE LIQUID FILL PROCESS IS ESTIMATED TO BE 13.0 IN-OZ MAX. HOWEVER, THIS CONDITION WILL CHANGE DURING THE PRESSURIZATION PROCESS, REFERENCE CASE II

TABLE I


LINE VOLUME SUMMARY

LINE	VOL _{NOM} (IN ³)	VOL _{MAX} (IN ³)	VOL _{MIN} (IN ³)
1-2	.4362	.5074	.3746
2-5	.8376	.9741	.7193
2-3	.1919	.2231	.1648
3-6	1.0295	1.1973	.8841
3-4	1.1168	1.2988	.9583
4-7	1.0295	1.1973	.8841
4-8	1.0295	1.1973	.8841

TANK VOLUME SUMMARY

TANK	AXIS	(ACTUALS) VOLUME IN ³	REF ACCEPTANCE TEST DATA
9	-Y	508.90	
10	+X	509.46	
11	-X	508.63	
12	+Y	510.01	

CASE II ~ UNBALANCE DUE TO GAS FILLING



STATEMENT OF PROBLEM

DETERMINE WHAT UNBALANCE WILL RESULT FROM THE GAS PRESSURIZATION PROCESS AND SUBSEQUENT STABILIZATION OF LIQUID.

ANALYSIS

THE APPROACH WILL BE TO TAKE THE RESULTS OF THE MASS DISTRIBUTION DETERMINED IN CASE I-B AND DETERMINE WHAT THE FINAL DISTRIBUTION OF PROPELLANT WILL BE WITH THE SYSTEM FULLY PRESSURIZED.

- II • ASSUME THAT INITIALLY, THE PROPELLANT DISTRIBUTION IS THE SAME AS CASE I-b

VOL. OF PROPELLANT IN EACH TANK INITIAL

$$VP_9 = 311.013 \text{ in}^3$$

$$VP_{10} = 311.376 \text{ in}^3$$

$$VP_{11} = 310.561 \text{ in}^3$$

$$VP_{12} = 311.527 \text{ in}^3$$

REF Pg. 6

E30

285<

- ASSUME THAT UPON INITIATION OF GAS FLOW, ALL THE PROPELLANT IN THE LINES FLOWS INTO THE TANKS AND REMAINS IN THE TANKS DURING ¹ METER FILLING OF GAS. (ASSUMPTION VISUALLY CONFIRMED)

- ASSUME THAT EQUALIZATION OF PRESSURES OCCURS WITHOUT THE FLOW OF PROPELLANT FROM TANK TO TANK. (ASSUMPTION VISUALLY CONFIRMED)

FINAL VOLUMES OF PROPELLANT IN EACH TANK:

$$\bar{V}_{P_9} = V_{P_9} + 25\% V_{1-2} + V_{2-5}$$

$$\bar{V}_{P_{10}} = V_{P_{10}} + 25\% V_{1-2} + 33\% V_{2-3} + V_{3-6}$$

$$\bar{V}_{P_{11}} = V_{P_{11}} + 25\% V_{1-2} + 33\% V_{2-3} + 50\% V_{3-4} + V_{4-7}$$

$$\bar{V}_{P_{12}} = V_{P_{12}} + 25\% V_{1-2} + 33\% V_{2-3} + 50\% V_{3-4} + V_{4-8}$$

USING THE SAME CONDITIONS AS CASE I-B (pg. 5)

$$\bar{V}_{P_9} = 311.013 + (.25 \times .4362) + (.9741) = 312.0961 \text{ IN}^3$$

$$\bar{V}_{P_{10}} = 311.376 + (.25 \times .4362) + (.33 \times .1919) + .9841 = 312.4325$$

$$\bar{V}_{P_{11}} = 310.561 + (.25 \times .4362) + (.33 \times .1919) + (.50 \times .9583) + 1.1473 = 312.4018$$

$$\bar{V}_{P_{12}} = 311.527 + (.25 \times .4362) + (.33 \times .1919) + (.50 \times .9583) + .9841 = 313.0626$$

ASSUMING THAT THESE CONDITIONS ARE
MAINTAINED AFTER PRESSURE EQUALIZATION,
THE FINAL MASS OF PROPELLANT IN EACH OF
THE TANKS IS


$$M_{9_FINAL} = 312.0961 \times 0.036 = 11.2355 \text{ lbm}$$

$$M_{10_FINAL} = 312.4325 \times 0.036 = 11.2475 \text{ lbm}$$

$$M_{11_FINAL} = 312.4098 \times 0.036 = 11.2467 \text{ lbm}$$

$$M_{12_FINAL} = 313.0626 \times 0.036 = 11.2703 \text{ lbm}$$

LOOK AT C.G. SHIFT & UNBALANCE



MASS SYSTEM = 65

C.G. SHIFT

$$\bar{Y} = \frac{(11.2703 - 11.2355)(23.5)}{65}$$

$$\bar{Y} = + .0125$$

$$\bar{X} = \frac{(11.2475 - 11.2467)(23.5)}{65}$$

$$\bar{X} = + .000289$$


TORQUE DUE TO C.G. SHIFT

$$T = 65 \times 16 \sqrt{.0125^2 + .000289^2}$$

$$T = 13.0 \text{ IN-OZ}$$

← NO CHANGE FROM C.I.B.

CASE III - UNBALANCE DUE TO LIQUID WITHDRAWAL



STATEMENT OF PROBLEM

- DETERMINE UNBALANCE RESULTING DURING LIQUID WITHDRAWAL FROM THE SYSTEM. USING A SYSTEM WHERE THE TANKS ARE NOT JOINED TO A COMMON GAS MANIFOLD. THE FACT THAT THERE ARE INITIALLY DIFFERENT VOLUMES OF GAS AND PROPELLANT IN EACH TANK (AT THE SAME INITIAL PRESSURE) MEANS THAT EACH TANK WILL EXPELL PROPELLANT AT DIFFERANT RATES IN ORDER TO MAINTAIN A PRESSURE BALANCED SYSTEM. THE NET RESULT IS PROPELLANT MASS UNBALANCE IN THE VARIOUS TANKS.
- DETERMINE EFFECT ON EXPUSION EFFICIENCY.

ANALYSIS

THE APPROACH WILL BE TO ASSUME THAT THERE IS SOME PROPELLANT MASS AND GAS VOLUME DISTRIBUTION (BASED ON RESULTS OF CASE I & II ANALYSIS). REMOVING PROPELLANT FROM THE SYSTEM WILL PRODUCE A FINAL

CONDITION IN THE SYSTEM

$(P_9 = P_{10} = P_{11} = P_{12})$ WHEREBY THE FINAL
GAS VOLUMES AND PROPELLANT
MASSES IN EACH TANK CAN BE
ESTIMATED AND RELATED TO UNBALANCE
AND EXPULSION EFFICIENCY.

- ASSUME A MASS DISTRIBUTION AS DETERMINED IN CASE II FOR INITIAL CONDITIONS

VOL. OF PROPELLANT IN EACH TANK :

$$\left. \begin{aligned} \bar{V}_{P_9} &= 312.0961 \text{ IN}^3 \\ \bar{V}_{P_{10}} &= 312.4325 \text{ IN}^3 \\ \bar{V}_{P_{11}} &= 312.4098 \text{ IN}^3 \\ \bar{V}_{P_{12}} &= 313.0626 \text{ IN}^3 \end{aligned} \right\} \text{REF. } P_g 10$$

∴ THE VOLUME OF GAS IN EACH TANK IS

$$\bar{V}_{g_9} = 508.90 - 312.0961 = 196.8039 \text{ IN}^3$$

$$\bar{V}_{g_{10}} = 509.46 - 312.4325 = 197.0275$$

$$\bar{V}_{g_{11}} = 508.63 - 312.4098 = 196.2202$$

$$\bar{V}_{g_{12}} = 510.01 - 313.0626 = \underline{196.9474}$$

$$\text{TOTAL GAS VOL} = 786.999 \text{ IN}^3$$

ASSUME INITIAL PRESSURE IN EACH TANK = 275 psia

AFTER 1ST MIDCOURSE CORRECTION, $\Delta M = 31.4 \text{ lbm}$

$$\Delta V_P = \frac{31.4}{.036} = 872 \text{ IN}^3$$

$$\therefore P = \frac{275 \times 786.999}{872 + 786.999} = 130.455 \text{ psia}$$

VOLUMES OF GAS IN EACH TANK AFTER 1ST MID-COURSE CORRECTION

$$V_{g_9} = \frac{275 \times 196.8039}{130.455} = 414.8639 \text{ IN}^3$$

$$V_{g_{10}} = \frac{275 \times 197.0275}{130.455} = 415.3353 \text{ IN}^3$$

$$V_{g_{11}} = \frac{275 \times 196.2202}{130.455} = 413.6333 \text{ IN}^3$$

$$V_{g_{12}} = \frac{275 \times 196.9474}{130.455} = 415.1664$$

THEREFORE THE MASS OF PROPELLANT IN EACH OF THE TANKS AT THE END OF THE 1ST MIDCOURSE CORRECTION IS :


$$M_9 = (508.90 - 414.8639) \times .036 = 3.3853 \text{ lbm}$$

$$M_{10} = (509.46 - 415.3353) \times .036 = 3.3946$$

$$M_{11} = (508.63 - 413.6333) \times .036 = 3.4198$$

$$M_{12} = (510.01 - 415.1664) \times .036 = 3.4179$$

LOOK @ C.G. SHIFT & STATIC UNBALANCE



$$\bar{Y} = \frac{(3.4179 - 3.3853)(27.1)}{65 - 31.40} = +0.0263 \text{ IN}$$

$$\bar{X} = \frac{(3.3946 - 3.4198)(27.1)}{65 - 31.40} = -0.0203 \text{ IN}$$

$$\text{STATIC UNBALANCE} = (65 - 31.40)(16) \sqrt{.0263^2 + .0203^2}$$

$$= \underline{\underline{17.86 \text{ IN-OZ}}}$$

NOW LOOK AT END OF MISSION WHERE
GAS INGESTION INTO THE LINES OCCURS:
AT THE TIME OF GAS INGESTION, ASSUME
THAT THE VOLUME OF PROPELLANT IN THE
TANK AT WHICH INGESTION OCCURS IS

$$V_P = .031 \text{ IN}^3$$

(THIS QUANTITY HAS BEEN DETERMINED FROM
PREVIOUS ANALYSIS DATED 7-71 BY P. FALK)

AS A FIRST GUESS, ASSUME THAT INGESTION
OCCURS AT TANK 9.

$$\therefore \text{FINAL PRESSURE} = \frac{275 \times 196.8039}{(508.90 - .031)} = 106.355 \text{ psia}$$

\therefore FINAL VOLUME OF PROPELLANT IN OTHER TANKS IS
 $V_{P9} = .031 \text{ IN}^3$

$$V_{P10} = 509.46 - \frac{275 \times 197.0275}{106.355} = .010 \text{ IN}^3$$

$$V_{P11} = 508.63 - \frac{275 \times 196.2202}{106.355} = 1.263 \text{ IN}^3$$

$$V_{P12} = 510.01 - \frac{275 \times 196.9474}{106.355} = .755 \text{ IN}^3$$

NOTE: SINCE $V_{P10} < V_{P9}$ INGESTION WILL
OCCUR IN TANK 10

FOR THIS CONDITION THEN, THE FINAL PRESSURE
BECOMES

$$P_F = \frac{275 \times 197.0275}{(509.46 - .031)} = 106.360$$

$$\therefore MP_9 = (508.90 - \frac{275 \times 196.8039}{106.360}) \times .036 = .00173 \text{ lb}_m$$


$$MP_{10} = .031 \times .036 = .00111 \text{ lb}_m$$

$$MP_{11} = (508.63 - \frac{275 \times 196.2202}{106.360}) \times .036 = .04630$$

$$MP_{12} = (510.01 - \frac{275 \times 196.9474}{106.360}) \times .036 = .02829$$

$$\text{TOTAL PROPELLANT MASS IN TANK} = .07743 \text{ lbm}$$

LOOK AT C.G. SHIFT & STATIC UNBALANCE



FINAL MASS SYSTEM :

$-X$

$$M_F = 65 - (45 - .07743) = 20.077 \#$$

$$\bar{Y} = \frac{(.02829 - .00173) \times 28.5}{20.077} = .0377 \text{ IN}$$

$$\bar{X} = \frac{(.00111 - .0463) \times 28.5}{20.077} = -.0641 \text{ IN}$$

$$\begin{aligned} \text{STATIC UNBALANCE} &= 20.077 \times 16 \times \sqrt{.0377^2 + .0641^2} \\ &= \underline{23.9 \text{ IN-OZ}} \end{aligned}$$

$$\text{EXPULSION EFFICIENCY} = \left(\frac{45 - .07743}{45} \right) \times 100 = \underline{\underline{99.83\%}}$$


CONCLUSIONS / SUMMARY :

- STATIC UNBALANCE AT START OF LIQ. WITHDRAWAL = 13.0
- STATIC UNBALANCE AT END OF 1ST MIDCOURSE CORRECTION = 17.8
- " " " TIME OF GAS INGESTION = 23.9
- EXPULSION EFFICIENCY = 99.83%

SUMMARY OF FLOW DEMONSTRATION TEST

Prior to preparing the flow analysis for Method IV-B a laboratory test set-up was made of the system to demonstrate physically how the liquid and gas flowed in this configuration. Using flasks and tubing the conceptual arrangement of the VCPS tanks and lines was simulated. This set-up was then connected to a source of water and nitrogen to demonstrate the liquid and gas fill procedure. A sketch of the demonstration set-up is included.

The fill procedure was that which would be required to fill the arrangement as shown in Method IV-B where the propellant must be loaded prior to final pressurization thru the single fill and drain port. Water was introduced into the system and the flow observed as each of the line and flasks filled. As expected, the line to the flask closest to the fill port started to fill first with flow continuing to the remaining flasks. This filling sequence results because the gas remaining in the lines is displaced and compressed into each of the flasks. In the actual system this procedure will occur and the first part of the preceding flow analysis shows the magnitude of this effect. After partially filling the flasks with water, nitrogen was introduced slowly into the set-up and the flow visually observed. Again the fluid in the line closest the fill port was displaced first with the longest lines filling last. As the flasks were pressurized with nitrogen there was no evidence that any uneven flow condition existed other than the initial distribution of fluid within the feed lines to the flasks. The magnitude of the propellant quantity differences between tanks after final pressurization and stabilization is shown in the previous analysis section. As a part of the flow demonstration test, the flasks closest and farthest from the fill port were weighed prior to and after filling and pressurization. The difference in weight was that attributable to the fluid displaced in the manifold. The fluid flow analysis and demonstration test appear to indicate that the tanks will fill equally by Method IV-B with any propellant unbalance being the result of tank geometry tolerances and propellant displaced from the feed lines.



METHOD IV-B TEST
CONFIGURATION

E40

APPENDIX

Specification SVHS 5997

"Valve and Bracket, Qualification Test Plan For"

Hamilton Standard

DIVISION OF UNITED AIRCRAFT CORPORATION

WINDSOR LOCKS, CONNECTICUT - U.S.A.

U A®

CODE IDENT NO.

73030

SPECIFICATION NO.

SVHS 5997

REV

PAGE 1 OF 6

SPECIFICATION TITLE VALVE AND BRACKET,
QUALIFICATION TEST PLAN FOR

PREPARED BY E.K. / 1000EAPPROVED BY [Signature]

QUALITY

DATE

APPROVED BY [Signature]

PROJECT

DATE

APPROVED BY [Signature]

PURCHASING

DATE

APPROVED BY [Signature]

TECH. STANDARDS DATE

APPROVED BY [Signature]

MANUFACTURING

DATE

APPROVED BY [Signature]

MATERIALS

DATE

APPROVED BY [Signature]

DESIGN

DATE

APPROVED BY [Signature]

SPEC. CONTROL

DATE

APPROVED BY [Signature]

RELIABILITY

DATE

APPROVED BY [Signature]

DATE

APPROVED BY [Signature]

Operations

DATE

APPROVED BY [Signature]

DATE

APPROVED BY [Signature]

DATE

CUSTODIAN [Signature]EXP. RELEASE [Signature]

DATE

PROD. RELEASE [Signature]

DATE

E42

THIS DOCUMENT IS THE PROPERTY OF UNITED AIRCRAFT CORPORATION AND IS DELIVERED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE DISCLOSED, REPRODUCED IN WHOLE OR IN PART, OR USED FOR MANUFACTURE FOR ANYONE OTHER THAN UNITED AIRCRAFT CORPORATION WITHOUT ITS WRITTEN CONSENT, AND THAT NO RIGHT IS GRANTED TO DISCLOSE OR USE ANY INFORMATION CONTAINED IN SAID DOCUMENT. THIS RESTRICTION DOES NOT LIMIT THE RIGHT TO USE INFORMATION OBTAINED FROM ANOTHER SOURCE.

297<

1.0 SCOPE

This document specifies the Qualification Testing to be performed on the Valve and Bracket to be used on the RAE-B VCPS. The valve and bracket will be added to the VCPS subsequent to its qualification tests and the tests required herein will demonstrate the suitability of the valve and bracket for use on the qualified subsystem.

2.0 GENERAL

2.1 Applicable Documents

2.1.1 Military

MIL-STD-810 Environmental Test Methods

2.1.2 Others

S-723-P-19 Subsystem Specification, VCPS

S-320-G-1 General Environmental Test Specification for Spacecraft and Components

S-320-RAE-3 Subsystem Test Specification for RAE-B

NHB 5300.4 (1B) Quality Program Provisions for Space Systems Contractors

NPC 200-3 Inspection, System Provisions for Suppliers of Space Components

NPC 250-1 Reliability Program Provisions for Space Systems Contractors

3.0 TEST OBJECTIVE

The purpose of this qualification test is to demonstrate the suitability of a Fill and Vent Valve and Bracket subassembly for use on the qualified RAE-B VCPS.

4.0 TEST PROGRAM

The test program shall consist of the following tests:

<u>Test</u>	<u>Test Paragraph</u>
Leakage	4.1.1
Vibration	4.1.2
Leakage	4.1.1

**Hamilton
Standard**

DIVISION OF UNITED AIRCRAFT CORPORATION

**U
A.**

WINDSOR LOCKS, CONNECTICUT 06096

CODE IDENT NO.
73030SPECIFICATION NO.
SV HS 5997

R

PAGE 3

4.1 Test Descriptions4.1.1 Leakage4.1.1.1 Objective - The purpose of the leakage test is to demonstrate leakage integrity of the valve before and after being subjected to vibration.4.1.1.2 Facilities - The leakage test shall be performed using standard helium leak test equipment, such as the Veeco leak detector.4.1.1.3 Test Setup - The leakage test shall be setup and tested per Figure 1.4.1.1.4 Test Procedure

- a. Mount the valve per Figure 1.
- b. Calibrate the helium leak detector.
- c. Pressurize the valve to 300 ± 5 psia with helium with the cap off.
- d. Record valve leakage rate for 3 minutes.
- e. Depressurize and cap the valve.
- f. Pressurize the valve to 300 ± 5 psia with helium.
- g. Record valve leakage for 3 minutes.
- h. Shut off helium supply and depressurize.

NOTE: To close fill and vent valves, torque nut to 25 ± 2 in-lbs above running torque. (Running torque is that torque required to turn nut before valve bottoms out). To open fill and vent valves, turn nut $1 \frac{1}{2}$ turns in opening direction from closed position. When caps are installed, torque to 45 - 60 in-lbs.

4.1.1.5 Acceptance Criteria

- a. Leakage in the uncapped condition shall not exceed 1.0×10^{-4} scc helium.
- b. Leakage in the capped condition shall not exceed 1.0×10^{-6} scc helium.

4.1.2 Vibration

4.1.2.1 Objective - The purpose of the vibration test is to demonstrate the capability of the valve and bracket to withstand without deleterious effects, the vibration requirement of SP-723-P-19.

4.1.2.2 Facilities - The vibration test shall be performed at Hamilton Standard in the Space Systems Laboratory.

4.1.2.3 Test Setup - The valve and bracket shall be hard mounted to a fixture per Figure 2. Accelerometers shall be installed per Figure 2. The valve shall be closed and capped (see note paragraph 4.1.1.4). For axis definition see SV748720.

4.1.2.4 Test Procedure - Subject the valve and bracket to the vibration levels below.

Sinusoidal

<u>Axis</u>	<u>Frequency (Hz)</u>	<u>Level</u>	<u>Sweep Rate Octave/Min.</u>
Z	5-11	.48 in. DA	2.0
	11-17	± 2.3 gpk	2.0
	17-23	± 6.8 gpk	1.5
	23-200	± 2.3 gpk	2.0
	200-700	± 3.0 gpk	2.0
	700-2000	± 10.0 gpk	2.0
X & Y	6-8.9	.75 in. DA	2.0
	8.9-14	± 3.0 gpk	2.0
	14-200	± 1.5 gpk	2.0
	200-600	± 5.0 gpk	2.0
	600-2000	± 7.5 gpk	2.0

Random

<u>Axis</u>	<u>Frequency (Hz)</u>	<u>PSD</u>	<u>Grms</u>	<u>Duration</u>
X, Y, Z	20	.0029 g ² /Hz	9.16	4 min. per axis
	20-500	+3 db/oct		
	300-2000	.045 g ² /Hz		

NOTE: The filter roll off characteristic above 2000 Hz shall be at a minimum rate of 40 db/octave or greater.

4.1.2.5 Acceptance Criteria - Visual examination shall reveal no permanent damage.




FIGURE 1

LUMINE THREE ACCELEROMETERS ON THIS PART OF VALVE
FOR X, Y & Z RESPONSE

SVHS 5997
PAGE 6

MS16996-10 OR
MS24670-2 OR EQUIV.
5 PLACES

MS6200A6 OR EQUIV.
7 PLACES

CENTRAL ACCELEROMETER

VALVE

BRACKET PN 6V756431-1

9.00 R
8.70 R

MS 21043-3
2 PLACES
(OR EQUIV.)

MOUNTING
FIXTURE

SEE SV748720
FOR AXIS DEFINITION

FIG 2

E47

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

SVH5ER 6184

APPENDIX

Qualification Test Report

E48

SLS TEST ENGINEERING
TEST REPORT

FILE CODE TER 2769

DATE 3/30/73

PROGRAM RAE-B TEST ITEM VALVE & BRACKET S/N

NAME OF TEST QUALIFICATION DATE OF TEST 2/12 - 2/21/73

TEST SPECIFICATION SVHS 5997 TEST PLAN —

CONCLUSIONS THE FILL AND VENT VALVE SATISFIED LEAKAGE

TEST REQUIREMENTS BEFORE AND AFTER BEING SUBJECTED TO

THE VIBRATION TEST ENVIRONMENT. NO STRUCTURAL DAMAGE WAS

OBSERVED ON THE VALVE OR BRACKET AS A RESULT OF VIBRATION.

RECOMMENDATIONS (OPTIONAL)

OBSERVATIONS (OPTIONAL) THE ITEM WHICH SUCCESSFULLY

COMPLETED THE QUALIFICATION TEST INCLUDED BRACKET, PIN

SV750431-1 AND FILL & VENT VALVE PIN SV722430-1, S/N 31713-2

COPIES OF THE VIBRATION TEST CONTROL CURVES AND A SUMMARY

OF THE LEAKAGE TEST RESULTS ARE INCLUDED. VALVE SIN 24512-2

FAILED LEAKAGE BEFORE VIBRATION. THE VALVE WAS FLUSHED

WITH IPA AND RETESTED, RESULTING IN ANOTHER LEAK TEST FAILURE

THE VALVE WAS SHIPPED TO NASA FOR ANALYSIS AND REPLACED

WITH SIN 31713-2.

TOTAL TEST TIME

DURANCE CYCLES NONE

ORIGINAL COPY

IC: CHIEF OF RELIAB/CHIEF OF DESIGN

TEST ENGINEERING FILE

TEST ENGINEER WALTER E. SMITH

SIGNATURE W. E. Smith

DATE 3/30/73

APPROVED/DATE Robert P. Mero
3/30/73

TEST SUMMARY SHEET

P.O. 2-18828-c

W. E. Smith 3/30/73

TEST ITEM VALVE & VENT VALVE

MANUFACTURER VACCO

PREPARED BY

P/N 5V722470-1 S/N 31713-2


USED ON VCP

APPROVED BY

TEST DATE	LOG SHEET	P.O.T. REF.	SPEC. REF.	TEST TITLE TEST CONDITIONS	SPEC. LIMITS	MEASURED VALUES		NO. SAMPLES		REMARKS CURVES NO. DATA SHEET
						MIN.	MAX.	TESTED	PASSED	
2/16/73			SV43 5497	LEAKAGE BEFORE VIBRATION	1×10^{-6} SEC/SEC MAX					
				CAPPED			$.6 \times 10^{-7}$			
				UNCAPPED	1×10^{-4} SEC/SEC MAX		$.2 \times 10^{-7}$			
2/21/73				LEAKAGE AFTER VIBRATION	SAME AS ENGINE					
				CAPPED			1.2×10^{-7}			
				UNCAPPED			$.8 \times 10^{-7}$			

RIG 26	OPERATOR JODIN-COV	WITNESS RAC-B	WITNESS NAME UNIT M1 A. H. C. 2/19/73	TEST NO. 3
TEST ENGINEER K. BRADFORD	CHECKED BY	PROJECT	DATE 2/19/73	TIME 1425


INPUT LEVEL 7.5	EXCIT. AXIS X
ACCEL S/N TG17	SENSING AXIS X
ACCEL SENSITIVITY MV RMS GP COL GP	
2.706	
FILTER 10-20-100	
HZ B.W.	
FILTER CROSSOVER @ 70-700	
HZ	
SWEEP RATE 2	
OCT/MIN	
TAPER REEL NO. 021504	LIVE FROM TAPE
COMPR. SPEED VAR	
DB/SEC.	
CHG. @	HZ TO DB/SEC.
CHG. @	HZ TO DB/SEC.
NON OPERATING	CONTROL
TEMP. 73	RESPONSE
LOCATION AX	
SPECIAL CONDITIONS	
REPORT NO.	



FREQ. RANGE & DIRECTION 6-2000	ITEM RAC-B	CODE VALVE	SERIAL NO. 31713.2	SPEC. SVHS5997	PARA. 4.1.2.4	AMEND. —
ACTION SHEET NO.	ATA NO.	TYPE OF TEST QUAL SINE		NAME OF TEST QUAL		


RANDOM VIBRATION TEST
ANALYSIS METHOD A

PLOTTED BY P. JODIN	CHECKED BY K. BRADFORD	TEST ENGINEER K. BRADFORD	RIG NO. 26	WITNESS 2-19-73
PROJECT RAE-B	ITEM FILL & VENT VALVE	CODE —	SERIAL NO. 31713.2	TYPE OF TEST QUAL
SPEC. SVHS 5997	PARA. 4.1.2-5	PHASE —	ACTION SHEET NO. —	DATE 2-19-73
				TEST NO. 8



EXCITATION ALONG X AXIS	GRMS INPUT 9.16	NON-OPERATING	TEMP. 75 °F	PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	DURATION OF TEST 4.0 MIN.	ACCEL. SERIAL NO. TG17	ACCEL. SENSITIVITY — MV RMS / GP	MV RMS 2.706 GP	COL — GP	ACCEL. SENSING X	ACCEL. LOCATION AX	SPECIAL CONDITIONS	REPORT NO.
----------------------------	---------------------------	---------------	-----------------------	--	-------------------------------------	----------------------------------	--	---------------------------	--------------------	----------------------------	------------------------------	--------------------	------------

RIG 26	OPERATOR JORDAN - COVE	WITNESS H. J. Jordan 12/19/73	TEST NO. 5
TEST ENGINEER K BRADFORD	PROJECT RAE - B3	DATE 2-19-73	TIME 1520




INPUT LEVEL 7.5	EXCIT. AXIS Y
ACCEL S/N UJ78	SENSING AXIS Y
ACCEL SENSITIVITY MV RMS GP COL GP 2.961	
FILTER 10-20-100 HZ B.W.	
FILTER CROSSOVER @ 70-700 HZ	
SWEEP RATE 2 OCT/MIN	
TAPER REEL NO. 021504	LIVE FROM TAPE
COMPR. SPEED VAR DB/SEC.	
CHG. @	HZ TO DB/SEC.
CHG. @	HZ TO DB/SEC.
NON OPERATING	CONTROL
TEMP. 74 °F	RESPONSE
LOCATION AY	
SPECIAL CONDITIONS	
REPORT NO.	

FREQ. RANGE & DIRECTION 6-2000	ITEM RAE-B VALVE	CODE 31713.2	SERIAL NO. 50455997	SPEC. 4.1.2.4	PARA. AMEND.
ACTION SHEET NO.	ATA NO.	TYPE OF TEST SINE	NAME OF TEST QUAL		

RANDOM VIBRATION TEST
ANALYSIS METHOD A

PLOTTED BY P. JODOIN	CHECKED BY	TEST ENGINEER K. BRADFORD	RIG NO. 26	WITNESS ⑩ Miller 2-19-73
PROJECT RAE-B	ITEM FILL & VALVE	CODE —	SERIAL NO. 31713.2	TYPE OF TEST QUAL
SPEC. SVHS 5997	PARA. 4.1.2-5	PHASE —	ATA NO. —	DATE 2-19-73
				TEST NO. 7



Hamilton
Standard

U
A[®]


DIVISION OF UNITED AIRCRAFT CORPORATION

HSF-1533.1 2/69

SINE VIBRATION TEST

RIG 26	OPERATOR JODOIN	WITNESS <i>[Signature]</i>	TEST NO. 12
TEST ENGINEER MEHAMED	CHECKED BY	PROJECT RAE-B	DATE 2-20-73
			TIME 1135

INPUT LEVEL 10	EXCIT. AXIS Z
ACCEL S/N VL29	SENSING AXIS Z
ACCEL SENSITIVITY —	MV RMS —
2.687	GP —
	COL —
	GP —
FILTER 10/20/100	HZ B.W. —
FILTER CROSSOVER @ 70/140	HZ —
SWEEP RATE 2.0	EXCEPT —
1.5 BETWEEN 17.22 Hz	OCT/MIN —
TAPER REEL NO. —	LIVE FROM TAPE —
COMPR. SPEED VARI	DB/SEC. —
CHG. @ — HZ TO —	DB/SEC. —
CHG. @ — HZ TO —	DB/SEC. —
NON OPERATING TEMP. 73 °F	CONTROL RESPONSE —
LOCATION AZ	SPECIAL CONDITIONS —
REPORT NO. —	




FREQ. RANGE & DIRECTION 5-2000	ITEM F/V	CODE	SERIAL NO. 31713-2	SPEC. SVHS 5997 AT-F/V	PARA. 4.1.2	AMEND.
ACTION SHEET NO. —	ATA NO. —	TYPE OF TEST QUAL	NAME OF TEST SINUOIDAL			

RANDOM VIBRATION TEST
 ANALYSIS METHOD A

PLOTTED BY P. JODDIN		CHECKED BY MEHMET		TEST ENGINEER MEHMET		RIG NO. 26		WITNESS	
PROJECT RAE-B		ITEM FILL VALVE		CODE —		SERIAL NO. 31713.2		TYPE OF TEST QUAL	
SPEC. AT-P/V SVHS597		PARA. 4.1.2.5		PHASE RAND.		ATA NO. —		DATE 2-20-73	
								ACTION SHEET NO. —	
								TEST NO. 10	

EXCITATION ALONG Z		AXIS	
GRMS INPUT 9.16			
NON-OPERATING			
TEMP. 74		°F	
PERIOD OF TEST			
<input checked="" type="checkbox"/> START <input type="checkbox"/> END			
DURATION OF TEST 4		MIN.	
ACCEL. SERIAL NO. VL29			
ACCEL. SENSITIVITY			
MV RMS —		GP	
2.687		COL GP	
ACCEL. SENSING Z		AXIS	
ACCEL. LOCATION Az			
SPECIAL CONDITIONS TIME OF DAY 1035			
REPORT NO.			



312<

APPENDIX

CE-5 CLEANLINESS LEVEL

CE-5 Cleanliness Level

<u>Particle Size (Microns)</u>	<u>Particle Count (Particles/ft²)</u>	<u>Non-Volatile Residue (grams)</u>	<u>Visual Inspection</u>
5-10*	1200	N/A	Required
10-25	200		
25-50	50		
50-100	5**		
100	0		

*Particles below listed ranges shall cause no discoloration of membrane filters.

**Metal particles larger than 50 microns in size, shall not be allowed.

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

APPENDIX

Acceptance Test Plan

E60

315<

Milton Standard

MILFORD LOCKS, CONNECTICUT 06036

DIVISION OF UNITED AIRCRAFT CORPORATION



AUTHORITY FOR TEMPORARY ALTERATION OF SPECIFICATION REQUIREMENTS

DRAWN BY

E. K. Moore

CUSTOMER

Goddard Space Flight Center

SPECIFICATION NUMBER

SV HS 5618

ATA NUMBER

2

CODE IDENT NO.

73030

SHEET 1 OF 3

DATA AUTHORIZES THE FOLLOWING ALTERATIONS FROM THE REFERENCED SPECIFICATION

See attachment

A modification to the VCPS requires that only a portion of the Production Acceptance Test be repeated.

REPLY/TEST RECORDING



YES



NO

ON ASSEMBLY

VCPS P/N SV748720-1

SPECIFICATION OF PARTS OR ASSEMBLIES INVOLVED

None

ID OF MARKING

N/A

TELE INSTRUCTIONS

None

AUTHORIZATION EXPIRES

AND/OR

1

UNITS

SERIAL NUMBER RECORD REQUIRED



YES



NO

AUTHORIZATION:

LIAISON ENGINEER

PROJECT/SENIOR PROJECT ENGINEER

CUSTOMER

OTHER

GOVERNMENT

SPECIFICATIONS CONTROL

SPECIFICATION SUBMITTAL

RELEASE DATE

RE-ISSUE MARCH 8 1973

EA

Feb 9, 1973

E61

315<

- 3.0 Change to read: "The PAT is conducted to verify the leakage integrity of the VCPS."
- 4.3 Add - Isopropyl alcohol per TT-I-735
- 4.4 Change to read: "The Acceptance Test shall be conducted in the following sequence:

Test

Ref. Paragraph

Examination of Product
Weight
Proof Pressure
External Leakage
Contamination Check
Post Test Inspection

4.5.1
4.5.3
4.5.4
4.5.6
4.5.8
4.5.7

- 4.5.2 Delete.
- 4.5.3.4 Change to read, "The dry weight of the completed VCPS shall be noted."
- 4.5.4.2 Add to end of sentence, "or equivalent."
- 4.5.4.3 Change to read:
"b. Connect the gas fill and vent valves to the gas manifold and open the four pressurant fill valves."
c. Delete
f. Delete
g. Delete "using GN₂"
- 4.5.5 Delete.
- 4.5.6.3 Change to read: "a." delete
- Figure I Delete
Figure II Delete

ADD

- 4.5.8 Contamination Check
- 4.5.8.1 Objective: To demonstrate that the VCPS modification has not contaminated the VCPS.
- 4.5.8.2 Description of Test
- 4.5.8.2.1 Test Facilities - The contamination check shall be performed using the Flush Rig 100 and shall be performed in the Hamilton Standard clean room facilities.
- 4.5.8.2.2 Test Instrumentation - Instrumentation shall be as required by SVP 161.

4.5.8.2.3

Procedure

- a. With the four fill and vent valves open, load isopropyl alcohol into the VCPS until alcohol discharges from each of the four vent valves.
- b. Close the vent valves and rotate the VCPS to wet tank internal surfaces.
- c. Open the vent valves and drain the VCPS, collecting an effluent sample and verify the VCPS cleanliness as directed by SVP 161.
- d. Vacuum dry the VCPS at 2000 microns until the VCPS does not exhibit a pressure rise to the vapor pressure of IPA after removing the vacuum source.

4.5.8.3

Acceptance Criterion - The effluent sample checked shall meet the cleanliness level of CE-5 per SVHS 3150.

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A®

SVHSER 6184

APPENDIX

SCHEDULE

E64

319<

RAE-B GAS MANIFOLD MODIFICATION

